

ORIGINAL SURVY	SURVED	BY	DATE
NOTE BOOK	PLOTTED		
	TEMPLATE		
	AREAS		
NO.	AREAS CHECKED		

22	SCHEDULE OF STORM SEWERS AND TRENCH BACKFILL																
STATION			550A0050	550A0070	550A0090	550A0120	550A0140	550A0160	550B0070	Z0056604	Z0056608	Z0056610	Z0056612	Z0056616	Z0056620	Z0056622	20800150
FROM	TO	PIPE #	SS, CL A, TY 1,12"	SS, CL A, TY 1,18"	SS, CL A, TY 1,18"	SS, CL A, TY 1,24"	SS, CL A, TY 1,30"	SS, CL A, TY 1,36"	SS, CL B, TY 1,15"	SS WM REQ 8"	SS WM REQ 12"	SS WM REQ 15"	SS WM REQ 18"	SS WM REQ 24"	SS WM REQ 30"	SS WM REQ 36"	TRNCH BK FILL (CU YD)
		98	19														7
		99	22														6
		100	48														7
34+80	39+50	101	104														14
		102	5														1
		103	24														4
		104	54														12
		105	61														12
		106						101									54
		107	23														4
		108	8														2
		109	37														5
		110	12														2
		111						9									4
		112	60														14
		113						49									17
		114						7									3
		115													37		6
		116													43		5
		117										30					7
		118										44					4
		119										55					10
		120											68				50
39+50	45+00	121	164														2
		122	15														1
		123	5														32
		124	98														7
		125	38														2
		126	6														98
		127	138														147
		128	115														28
		129	26														1
		130									28						6
		131									17						21
		132									40						4
		133									28						30
45+00	50+55	134	41														1
		135									11						11
		136									72						1
		137	39														4
		138									27						8
		139									56						8
		140									56						7
		141	47														5
		142									37						4
		143									24						3
		144									22						6
		145									38						1
		146								6							12
		147									90						9
		148										61					9
		149	62														5
50+55	55+00	150									33						1
		151									23						11
		152										82					17
		153										236					7
		154								266							
PROJECT TOTAL			2,967	613	125	180	65	345	266	6	1,535	857	147	71	80	84	2,300