--- (149'-E-Z'')---DRILL EXISTING-HANDHOLE (1) INTERCONNECT NOTES THE EMPTY CONDUIT ALONG WASHINGTON STREET FROM CEDAR LAKE ROAD TO WEST OF HAINESVILLE ROAD SHALL INCLUDE A PULL STRING FOR FUTURE FIBER OPTIC CABLE INSTALLATION. (312'-E-2") A. -DRILL EXISTING HANDHOLE (1) THE TRAFFIC SIGNAL CONTROLLER EQUIPMENT FOR THIS PROJECT SHALL BE "ECONCLITE" AND NTCIP COMPLIANT TO MATCH THE EXISTING ADJACENT SYSTEM. RESTORATION OF WORK AREA.
RESTORATION OF THE TRAFFIC SIGNAL WORK AREA SHALL BE INCIDENTAL TO THE
RELATED PAY ITEM SUCH AS FOUNDATION, CONDUIT, HAVADHOLE, TERCH AND BACKFILL,
ETC., AND NO EXTRA COMPENSATION SHALL BE ALLOWED. ALL ROADWAY SURFACES SUCH
AS SHOULDER, MEDIAN, SIDEWALKS. PAVEMENT, ETC. SHALL BE REPLACED IN KIND. ALL
DAMAGE TO MOWED LAWNS SHALL BE REPLACED WITH AN APPROVED SALT TOLERANT SOD,
AND ALL DAMAGE TO UNMOWED FIELDS SHALL BE SEEDED IN ACCORDANCE WITH STANDARD
SPECIFICATIONS 252 AND 250 RESPECTIVELY. DESIGNED - BRD

450 E Devon Ave, Suite 300 Itasca, Illinois 60143 CIVILTECH Tel: 630.773.3900 Fax: 630.773.3975 www.civittechinc.com

DATE

REVISED DRAWN - MFB REVISED CHECKED - JJE REVISEO - 12/17/2012 REVISED

STATE OF ILLINOIS **DEPARTMENT OF TRANSPORTATION**

INTERCONNECT PLAN CEDAR LAKE ROAD HART ROAD TO S. ROSEDALE ROAD SCALE: 1" = 50' SHEET NO. 1 OF 4 SHEETS

SECTION 0187 05-00121-07-WR LAKE 223 128 CONTRACT NO. 63765