

ITEM NO.	DESCRIPTION	UNITS	TOTAL QUANTITY	SPTS FUNDS
2010010	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	171	171
2010020	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	42	42
2010100	TREE TRUNK PROTECTION	EACH	18	18
2020010	EARTH EXCAVATION	CU YD	1,773	1,773
2020120	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	177	177
2040080	FURNISHED EXCAVATION	CU YD	163	163
2070020	POROUS GRANULAR EMBANKMENT	CU YD	177	177
2110101	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	11,893	11,893
25000100	SEEDING, CLASS 1	ACRES	2.00	2.00
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	199	199
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	199	199
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	199	199
25100630	EROSION CONTROL BLANKET	SQ YD	11,345	11,345
25200100	SODDING	SQ YD	549	549
28000400	PERIMETER EROSION BARRIER	FOOT	306	306
28000500	INLET & PIPE PROTECTION	EACH	21	21
30300104	AGGREGATE SUBGRADE IMPROVEMENT 4"	SQ YD	1,472	1,472
30300108	AGGREGATE SUBGRADE IMPROVEMENT 8"	SQ YD	3,976	3,976
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	1,636	1,636
40600300	AGGREGATE (PRIME COAT)	TON	9	9
40600380	HOT-MIX ASPHALT BINDER COURSE, 11-19.0, N50	TON	501	501
40600335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	579	579
42400200	PORTLAND CEMENT CONCRETE SIDEWALK, 5 INCH	SQ FT	6,736	6,736
42400800	DETECTABLE WARNINGS	SQ FT	361	361
44000100	PAVEMENT REMOVAL	SQ YD	3,996	3,996
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	1,621	1,621
44000600	SIDEWALK REMOVAL	SQ FT	2,841	2,841
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	2	2
54213660	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"	EACH	1	1
54213662	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	1	1
56400400	FIRE HYDRANTS TO BE RELOCATED	EACH	2	2
60100600	CONCRETE HEADWALLS FOR PIPE DRAINS	EACH	1	1
60100905	PIPE DRAINS 4"	FOOT	184	184
60201105	CATCH BASIN, TYPE A, 4-DIAMETER, TYPE I FRAME, OPEN LID	EACH	1	1
60201105	CATCH BASIN, TYPE A, 4-DIAMETER, TYPE II FRAME AND GRATE	EACH	2	2
60207905	CATCH BASIN, TYPE C, TYPE II FRAME AND GRATE	EACH	1	1
60218400	MANHOLES, TYPE A, 4-DIAMETER, TYPE I FRAME, CLOSED LID	EACH	1	1
60219300	MANHOLES, TYPE A, 4-DIAMETER, TYPE II FRAME AND GRATE	EACH	2	2
60221100	MANHOLES, TYPE A, 5-DIAMETER, TYPE I FRAME, CLOSED LID	EACH	1	1
60236800	INLETS, TYPE A, TYPE II FRAME AND GRATE	EACH	1	1
60255500	MANHOLES TO BE ADJUSTED	EACH	2	2
60257900	MANHOLES TO BE RECONSTRUCTED	EACH	1	1
60403800	LIDS, TYPE I, CLOSED LID	EACH	2	2
60500040	REMOVING MANHOLES	EACH	2	2
60500050	REMOVING CATCH BASINS	EACH	1	1
60500060	REMOVING INLETS	EACH	3	3
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	2,283	2,283
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	104	104
72000100	SIGN PANEL - TYPE 1	SQ FT	132	132
72400100	REMOVE SIGN PANEL ASSEMBLY - TYPE A	EACH	16	16
72900100	METAL POST - TYPE A	FOOT	396	396
78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	285	285
78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	2,175	2,175
78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	250	250
78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	65	65
78000630	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	23	23
78300100	PAVEMENT MARKING REMOVAL	SQ FT	5,030	5,030
81028200	UNDERGROUND CONDUIT, GALVANIZED STEEL, 2" DIA.	FOOT	152	152

ITEM NO.	DESCRIPTION	UNITS	TOTAL QUANTITY	SPTS FUNDS
81600000	UNIT DUCT, 60W, 2-1C NO.8, 1/2" NO.8 GROUND, Q&P-TYPE USE, 3/4" DIA. POLYETHYLENE	FOOT	478	478
81600055	UNIT DUCT, 60W, 3-1C NO.8, 1/2" NO.8 GROUND, Q&P-TYPE USE, 1" DIA. POLYETHYLENE	FOOT	705	705
82104500	LUMINAIRE, SODIUM VAPOR, RECTILINEAR TYPE, 250 WATT	EACH	10	10
83600200	LIGHT POLE FOUNDATION, 24" DIAMETER	FOOT	91	91
84200600	REMOVAL OF LIGHTING UNIT, NO SALVAGE	EACH	1	1
84200804	REMOVAL OF POLE FOUNDATION	EACH	4	4
84400105	RELOCATE EXISTING LIGHTING UNIT	EACH	3	3
550A0050	STORM SEWERS, CLASS A, TYPE I 12"	FOOT	167	167
550A0070	STORM SEWERS, CLASS A, TYPE I 15"	FOOT	61	61
550A0090	STORM SEWERS, CLASS A, TYPE I 18"	FOOT	164	164
550A0120	STORM SEWERS, CLASS A, TYPE I 24"	FOOT	311	311
A 2000120	TREE, ACER X FRSTMANII AUTUMN BLAZE (AUTUMN BLAZE FREEMAN MAPLE), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	7	7
A 2000320	TREE, ACER MIYABII MORTON (STAY-GREEN MIYABII MAPLE), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	16	16
A 2002720	TREE, CARYA OVATA (SHAGBARK HICKORY), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	6	6
A 2002820	TREE, CATALPA SPECIOSA (NORTHERN CATALPA), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	2	2
A 2007120	TREE, QUERCUS RUBRA (RED OAK), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	1	1
A 2007820	TREE, THUJA AMERICANA (AMERICAN LINDEN/HASSWOOD), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	4	4
B2001124	TREE, QUERCUS CANADENSIS (EASTERN REDBUD), 1" CALIPER, BALLED AND BURLAPPED	EACH	4	4
B2001420	TREE, CORNUS MAS COEDEN GLORY CORNUS (ANCHOVY DOGWOOD), 2" CALIPER, BALLED AND BURLAPPED	EACH	9	9
C2000505	SHRUB, CAROPTERIS X CLAUDONENSIS BLUEBUSH (BLUEBUSH BLUEBUSH), 5 GALLON	EACH	5	5
C2001524	SHRUB, CORNUS RACEMOSA (GREY DOGWOOD), 2' HEIGHT, BALLED AND BURLAPPED	EACH	10	10
C2011024	SHRUB, RHYNGIA PATULA MISS KIM (MISS KIM MANCHURIAN LILAC), 2' HEIGHT, BALLED AND BURLAPPED	EACH	14	14
C2012024	SHRUB, VIBURNUM DENTATUM SYNNESTVEDT (CHICAGO LUSTRE ARROWWOOD VIBURNUM), 2' HEIGHT, BALLED AND BURLAPPED	EACH	8	8
C2013224	SHRUB, CORNUS SERICEA CARDINAL (CARDINAL REDDOSEH DOGWOOD), 2' HEIGHT, BALLED AND BURLAPPED	EACH	13	13
C2014224	SHRUB, PYRUS IOWA (DWARF COMMON NINEBARK), 2' HEIGHT, BALLED AND BURLAPPED	EACH	10	10
C2015224	SHRUB, VIBURNUM DENTATUM RALPH SENIOR (AUTUMN JAZZ ARROWWOOD VIBURNUM), 2' HEIGHT, BALLED AND BURLAPPED	EACH	15	15
C2016224	SHRUB, WIGELA FLORIDA RED PRINCE (RED PRINCE OLD FASHIONED WIGELA), 2' HEIGHT, BALLED AND BURLAPPED	EACH	35	35
D2001526	TREE, PSUDOTSUGA MENZIESII (DOUGLAS FIR), 7' HEIGHT, BALLED AND BURLAPPED	EACH	13	13
K0013020	PERENNIAL PLANTS, PRAIRIE TYPE, GALLON POT	UNIT	17	17
K0026010	TRANSPLANTED SALVAGED TREES	EACH	3	3
X0022917	PROPOSED STORM SEWER CONNECTION TO EXISTING MANHOLE	EACH	4	4
X0322936	REMOVE EXISTING FLARED END SECTION	EACH	2	2
X0322939	RELOCATE EXISTING FLARED END SECTION	EACH	3	3
X0323256	REMOVE AND RELOCATE FLAGPOLE	EACH	1	1
X0323586	PIPE DRAIN REMOVAL	FOOT	107	107
X0323706	TRASH RECEPTACLE RELOCATION	EACH	1	1
X0323864	BRICK SIDEWALK REMOVAL	SQ FT	108	108
X0327008	REMOVE AND RELOCATE SIGN (SPECIAL)	EACH	1	1
X0327146	RELOCATE BIKE RACK	EACH	2	2
X0327149	RELOCATE BENCH	EACH	3	3
X5510100	STORM SEWER REMOVAL	FOOT	675	675
X5610008	DUCTILE IRON WATER MAIN PIPE INSTALLATION	FOOT	40	40
X5610790	WATER MAIN REMOVAL	FOOT	29	29
X6022930	MANHOLES, TYPE A, 5-DIAMETER, WITH SPECIAL FRAME AND GRATE	EACH	2	2
X6023204	INLETS, TYPE A, TYPE I FRAME, OPEN LID, SPECIAL	EACH	1	1
X6023840	REMOVE AND RELOCATE INLETS	EACH	1	1
X6026050	SANITARY MANHOLES TO BE ADJUSTED	EACH	1	1
X6064200	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12 (SPECIAL)	FOOT	148	148
X7010216	TRAFFIC CONTROL AND PROTECTION (SPECIAL)	L SUM	1	1
X8302405	LIGHT POLE, ALUMINUM, 20 M.H., 6 MAST ARM	EACH	10	10
X8440105	RELOCATE EXISTING SIGN LIGHTING LUMINAIRE	EACH	2	2
X8950130	MODIFY EXISTING LIGHTING CONTROLLER	EACH	1	1
XZ177600	REMOVE EXISTING BUMPER BLOCKS	EACH	16	16
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1
Z0017400	DRAINAGE & UTILITY STRUCTURES TO BE ADJUSTED	EACH	1	1

△ SPECIAL PROVISION
* SPECIALTY ITEMS

ESI ESI CONSULTANTS, LTD
1919 N. MILL STREET, SUITE 100
NAPERVILLE, IL 60563
(815) 420-1700
WWW.ESI.IL.COM
ILLINOIS DEPARTMENT OF PROFESSIONAL REGULATION REGISTRATION #184-003985

DESIGNED - BW	REVISED - 2/22/13
DRAWN - BR	REVISED -
CHECKED - BW	REVISED -
DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: N.T.S. SHEET NO. 1 OF 1 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1591	08-00043-00-BR	COOK	24	4

CONTRACT NO. 63804
ILLINOIS FED. AID PROJECT