


PROFILE	SURVEYED _____ BY _____ DATE _____
NOTE BOOK	PLOTTED _____
NO.	B.M. NOTED _____ STRUCTURE NOTATIONS CHRD _____

SUMMARY OF QUANTITIES				0028 BIKE PATH 80% STA 20% LA	0008 BRIDGE 80% STA 20% LA	0021 SAFETY 80% STA 20% LA
* CODE NO	PAY ITEM	UNIT	QUANTITY			
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	133	133		
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	382	382		
20101000	TEMPORARY FENCE	FOOT	900	900		
20101100	TREE TRUNK PROTECTION	EACH	20	20		
20101200	TREE ROOT PRUNING	EACH	20	20		
20101300	TREE PRUNING (1 TO 10 INCH DIAMETER)	EACH	10	10		
20101350	TREE PRUNING (OVER 10 INCH DIAMETER)	EACH	10	10		
20200100	EARTH EXCAVATION	CU YD	518	518		
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	4,451	4451		
20400800	FURNISHED EXCAVATION	CU YD	22,681	22681		
20800150	TRENCH BACKFILL	CU YD	43	43		
21101625	TOPSOIL FURNISH AND PLACE, 6"	SG YD	33,513	33513		
21301072	EXPLORATION TRENCH 72" DEPTH	FOOT	100	100		
25000200	SEEDING, CLASS 2	ACRE	2.4	2.4		
25000310	SEEDING, CLASS 4	ACRE	4.6	4.6		
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	630	630		
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	630	630		
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	630	630		
25100635	HEAVY DUTY EROSION CONTROL BLANKET	SG YD	22,218	22218		
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	7,000	7000		
28000305	TEMPORARY DITCH CHECKS	FOOT	24	24		
28000400	PERIMETER EROSION BARRIER	FOOT	3,835	3835		
30300001	AGGREGATE SUBGRADE IMPROVEMENT	CU YD	227	227		
31101200	SUBBASE GRANULAR MATERIAL, TYPE B 4"	SG YD	489	489		
35102100	AGGREGATE BASE COURSE, TYPE B 9"	SG YD	2,487	2,487		
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	1,577	1,577		
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SG YD	48	48		
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	553	553		
42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SG YD	16	16		
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SG YD	1,150	1,150		
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	199	199		
44000600	SIDEWALK REMOVAL	SG FT	246	246		
50102400	CONCRETE REMOVAL	CU YD	2			2
50105220	PIPE CULVERT REMOVAL	FOOT	117	117		
50200100	STRUCTURE EXCAVATION	CU YD	821			821
50300225	CONCRETE STRUCTURES	CU YD	145			145
50300255	CONCRETE SUPERSTRUCTURE	CU YD	22			22
50300300	PROTECTIVE COAT	SG YD	481			481
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	28,710			28,710
51200957	FURNISHING METAL SHELL PILES 12" X 0.250"	FOOT	1,549			1,549
51202305	DRIVING PILES	FOOT	1,549			1,549
51203200	TEST PILE METAL SHELLS	EACH	4			4
51500100	NAME PLATES	EACH	1			1
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	4	4		
54213663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"	EACH	2	2		
542A0217	PIPE CULVERTS, CLASS A, TYPE 1 12"	FOOT	99	99		
542A0223	PIPE CULVERTS, CLASS A, TYPE 1 18"	FOOT	57	57		
542A2737	PIPE CULVERTS, CLASS A, TYPE 4 12"	FOOT	138	138		
58700300	CONCRETE SEALER	SG FT	1,620			1,620
60100060	CONCRETE HEADWALLS FOR PIPE DRAINS	EACH	2			2
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	175	175		
66400105	CHAIN LINK FENCE, 4'	FOOT	262			262
66400205	CHAIN LINK FENCE, 5'	FOOT	3,603	3,603		
66900200						

△ CONSTRUCTION CODE TYPE = 0042

• SPECIALTY ITEM



DESIGNED	-	CEC
DRAWN	-	CEC
CHECKED	-	DWB
DATE	-	02/04/2013

REVISED
REVISED
REVISED
REVISED

REVISED
REVISED
REVISED
REVISED

REVISED
REVISED
REVISED
REVISED

REVISED
REVISED
REVISED
REVISED

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

BUSSE WOODS TRAIL OVERPASS SUMMARY OF QUANTITIES

SCALE:	SHEET NAME:	STA.	TO STA.
--------	-------------	------	---------

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
341	09-00058-00-BT	COOK	43	3
		CONTRACT NO. 63809		
FED. ROAD DIST. NO. 7 ILLINOIS FED. AID PROJECT				