TREES SCHEDULE

LOCATION	(6 TO 15 UNITS DIAMETER) (UNIT)	(OVER 15 UNITS DIAMETER) (UNIT)
STA 139+83 - 2 LT		17
STA 145+50 - 12 LT		17
STA 149+18 - 7 LT	12	
STA 149+95 - 9 RT	12	
STA 192+76 - 4 RT		24
TOTAL	24	58

EROSION CONTROL SCHEDULE

LOCATION	PERIMETER EROSION CONTROL BARRIER (FOOT)	INLET AND PIPE PROTECTION (EACH)
STA 145+00 TO 149+39	439	
STA 145+30 RT		1
STA 149+73 TO 153+60	387	
STA 154+91 TO 164+11	920	
STA 200+79 TO 206+78	599	
TOTAL	2345	1

EARTH EXCAVATION SCHEDULE

LOCATION	EARTH EXCAVATION (CU YD)
STA 139+70 TO 144+36	330
STA 148+20 TO 149+39	195
STA 149+73 TO 153+60	245
STA 153+60 TO 154+91	15
STA 154+91 TO 158+35	144
STA 159+35 TO 160+33	22
STA 160+33 TO 161+53	38
STA 161+80 TO 163+70	26
STA 163+70 TO 164+11	17
STA 164+35 TO 165+13	38
STA 172+83 TO 173+68	19
STA 173+88 TO 174+63	17
STA 174+72 TO 175+24	14
STA 175+43 TO 175+74	9
STA 175+94 TO 176+32	11
STA 176+46 TO 177+30	19
STA 177+42 TO 177+99	13
STA 178+11 TO 178+43	7
STA 178+59 TO 178+97	6
STA 179+09 TO 179+51	9
STA 179+80 TO 179+93	7
STA 180+08 TO 180+50	10
STA 180+59 TO 180+95	8
STA 181+04 TO 181+52	11
STA 181+71 TO 182+55	19
STA 182+69 TO 183+44	17
STA 183+55 TO 184+02	10
STA 184+19 TO 184+61	9
STA 184+72 TO 185+68	21
STA 185+80 TO 186+31	11
STA 186+47 TO 186+84	8
STA 187+08 TO 189+74	60
STA 190+03 TO 192+34	51
STA 192+39 TO 193+13	6
STA 193+25 TO 193+56	3
STA 193+96 TO 194+77	7
STA 195+13 TO 195+87	6
STA 195+97 TO 196+37	3
STA 196+55 TO 197+03	4
STA 197+15 TO 198+16	8
STA 198+36 TO 198+68	3
STA 199+06 TO 199+24	3
STA 199+31 TO 199+36	1
STA 199+60 TO 200+38	7
STA 200+67 TO 201+83	47
STA 201+83 TO 205+51	75
STA 205+75 TO 206+78	21
TOTAL	1633

SIGNS SCHEDULE

LOCATION	SIGN PANEL - TYPE 1 (SQ FT)	METAL POST - TYPE A (FOOT)	TELESCOPING STEEL SIGN SUPPORT (FOOT)	
STA 139+50 - 8 LT	4.5	10		PATH NARROWS (W5-4a) (18"X18") and LOW CLEARANCE (W12-2) (18"X18")
STA 139+70 - 8 LT	2.25	8.5		STOP SIGN (R1-1) (18"X18")
STA 149+36 - 8 RT	2.25	8.5		STOP SIGN (R1-1) (18"X18")
STA 149+76 - 8 LT	2.25	8.5		STOP SIGN (R1-1) (18"X18")
STA 164+08 - 8 RT	2.25	8.5		STOP SIGN (R1-1) (18"X18")
STA 164+38 - 8 LT	2.25	8.5		STOP SIGN (R1-1) (18"X18")
STA 165+10 - 8 RT	2.25	8.5		STOP SIGN (R1-1) (18"X18")
STA 166+50 - 18 RT	3	9		BIKE ROUTE (D11-1) (24"X18")
STA 172+20 - 20 LT	3	9		BIKE ROUTE (D11-1) (24"X18")
STA 189+71 - 8 RT	2.25	8.5		STOP SIGN (R1-1) (18"X18")
STA 190+08 - 8 LT	2.25	8.5		STOP SIGN (R1-1) (18"X18")
STA 192+27 - 8 RT	2.25	8.5		STOP SIGN (R1-1) (18"X18")
STA 192+42 - 8 LT	2.25	8.5		STOP SIGN (R1-1) (18"X18")
STA 206+72 - 8 LT	4	9		NO MOTOR VEHICLES (R5-3) (24"X24")
STA 206+75 - 8 RT	2.25	8.5		STOP SIGN (R1-1) (18"X18")
STA 209+40 - 23 RT	3	9		BIKE ROUTE (D11-1) (24"X18")
STA 210+20 - 23 RT	6.25	10		BICYCLES MAY USE FULL LANE (R4-11) (30"X30")
STA 211+00 - 23 LT	3	9		BIKE ROUTE (D11-1) (24"X18")
STA 212+15 - 23 RT	3		10.5	BIKE ROUTE (D11-1) (24"X18")
STA 213+80 - 23 LT	6.25		11.5	BICYCLES MAY USE FULL LANE (R4-11) (30"X30")
STA 214+90 - 23 RT	3		10.5	BIKE ROUTE (D11-1) (24"X18")
STA 216+25 - 23 LT	3		10.5	BIKE ROUTE (D11-1) (24"X18")
STA 217+50 - 23 LT	3		10.5	BIKE ROUTE (D11-1) (24"X18")
STA 217+50 - 23 RT	3.75		11.25	BIKE ROUTE (D11-1) (24"X18") and LEFT ARROW (M6-1) (12"X9")
STA 218+50 - 19 RT	3	9		BIKE ROUTE (D11-1) (24"X18")
STA 220+90 - 20 LT	3	9		BIKE ROUTE (D11-1) (24"X18")
TOTAL	79.5	176.5	64.75	

REMOVALS SCHEDULE

LOCATION	DRIVEWAY PAVEMENT REMOVAL (SQ YD)	COMBINATION CURB AND GUTTER REMOVAL (FOOT)	SIDEWALK REMOVAL (SQ FT)
STA 140+83 TO 148+17			4375
STA 148+54 TO 149+39			425
STA 149+73 TO 153+60			1905
STA 150+03 RT			130
STA 154+91 TO 159+35			2408
STA 160+33 TO 161+53			720
STA 163+70 TO 164+11			312
STA 164+00 LT			40
STA 164+35 TO 164+60			300
STA 165+07		10	100
STA 172+81		15	
STA 172+81 TO 192+38	600		7800
STA 189+74		10	
STA 190+03		10	
STA 192+38 TO 200+36	380		220
STA 200+67 TO 201+83			726
TOTAL	980	45	19490

SIDEWALK SCHEDULE

LOCATION	PORTLAND CEMENT CONCRETE SIDEWALK 5" (SQ FT)	DETECTABLE WARNINGS (SQ FT)
STA 148+20 TO 148+50	150	
STA 149+34		16
STA 149+73		16
STA 153+60 TO 161+53	6340	
STA 154+91		8
STA 161+80 TO 165+13	2380	
STA 163+70 TO 164+11		16
STA 164+00 LT		8
STA 164+35		32
STA 165+07 LT		8
STA 172+81		8
STA 172+81 TO 192+38	13620	
STA 187+08		12
STA 190+03		12
STA 192+38 TO 200+36	2610	
STA 200+65 TO 201+82	1170	
STA 201+82 TO 206+77	2480	
STA 205+75		16
TOTAL	28750	152

MISCELLANEOUS SCHEDULE

LOCATION	BOLLARDS (EACH)	STORM SEWERS, CLASS A, TYPE 1 12" (FOOT)	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12" (EACH)	SANITARY MANHOLES TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID (EACH)	SANITARY MANHOLES TO BE RECONSTRUCTED WITH NEW TYPE 1 FRAME, CLOSED LID (EACH)	RELOCATE EXISTING LIGHTING UNIT (EACH)	RELOCATE BENCH (EACH)	VINYL FENCE, 6' (FOOT)
STA 145+27 - 11 LT					1			
STA 145+28.78 - 37.2 LT			1					
STA 145+37		64						
STA 145+44.03 - 37.14 RT			1					
STA 146+45 - 8 LT							2	
STA 147+59 - 5 RT				1				
STA 147+65 - 6 RT				1				
STA 148+33 - 5 LT						1		
STA 190+83 TO 192+13 LT								130
STA 206+75	1							
TOTAL	1	64	2	2	1	1	2	130

PAVEMENT SCHEDULE

LOCATION	AGGREGATE BASE COURSE, TYPE B 4" (SQ YD)	AGGREGATE BASE COURSE, TYPE B 4" (SQ YD)	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N30 (TON)	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH (SQ YD)	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12 (FOOT)
STA 139+70 TO 148+17		1040	158		
STA 148+20 TO 148+50	18				
STA 148+54 TO 149+34		100	15		
STA 149+73 TO 153+60		475	72		
STA 153+60 TO 161+53	775				
STA 161+80 TO 165+13	290				
STA 165+07					10
STA 172+81 TO 192+38	3422			600	
STA 177+83					15
STA 189+74					10
STA 190+03					10
STA 192+38 TO 200+36	710			380	
STA 200+65 TO 201+82	143				
STA 201+82 TO 206+77	302				
TOTAL	5660	1615	245	980	45

TURF ESTABLISHMENT SCHEDULE

LOCATION	TOPSOIL FURNISH AND PLACE, 4" (SQ YD)	SEEDING, CLASS 1 (ACRE)	EROSION CONTROL BLANKET (SQ YD)	NITROGEN FERTILIZER NUTRIENT (POUND)	PHOSPHORUS FERTILIZER NUTRIENT (POUND)	POTASSIUM FERTILIZER NUTRIENT (POUND)
STA 139+70 TO 149+39	2120	0.45	2120	40	40	40
STA 149+73 TO 164+10	2560	0.55	2560	48	48	48
STA 164+35 TO 165+13	170	0.05	170	4	4	4
STA 172+81 TO 192+38	1150	0.30	1150	28	28	28
STA 192+38 TO 200+36	530	0.15	530	17	17	17
STA 200+65 TO 201+82	260	0.05	260	5	5	5
STA 201+82 TO 206+77	550	0.10	550	9	9	9
TOTAL	7340	1.65	7340	151	151	151

PAVEMENT MARKING SCHEDULE

LOCATION	THERMOPLASTIC PAVEMENT MARKING LINE 4" (FOOT)	THERMOPLASTIC PAVEMENT MARKING LINE 12" (FOOT)	
STA 139+70 TO 149+39	242		SKIP DASH YELLOW
STA 139+73		5	STOP BAR WHITE
STA 149+36		5	STOP BAR WHITE
STA 149+73 TO 164+10	359		SKIP DASH YELLOW
STA 149+76		5	STOP BAR WHITE
STA 164+07		5	STOP BAR WHITE
STA 164+35 TO 165+13	19		SKIP DASH YELLOW
STA 164+38		5	STOP BAR WHITE
STA 165+10		5	STOP BAR WHITE
STA 173+83 TO 189+73	397		SKIP DASH YELLOW
STA 173+86		5	STOP BAR WHITE
STA 189+71		5	STOP BAR WHITE
STA 190+03 TO 206+78	418		SKIP DASH YELLOW
STA 190+08		5	STOP BAR WHITE
STA 206+75		5	STOP BAR WHITE
STA 206+78 TO 208+28 RT	150		LINE WHITE
STA 206+78 TO 207+29 LT	51		LINE WHITE
TOTAL	1636	50	

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
N/A	*	KANKAKEE	18	5

CONTRACT NO. 87539

MUN. ROAD DIST. NO. | ILLINOIS | FED. AID PROJECT

*10-00276-00-BT

TYSON ENGINEERING, INC.
CONSULTING CIVIL ENGINEERS
LAND SURVEYORS
DESIGN FIRM LICENSE #184-001136
367 SOUTH SCHUYLER AVENUE
KANKAKEE, ILLINOIS 60901
PHONE (815) 932-7406

This document and the ideas and designs incorporated herein, as an instrument of professional service, is the property of Tyson Engineering Inc. and is not to be used in whole or in part, for any other project without written authorization of Tyson Engineering Inc.

Do not scale drawings. Use dimensions only.

Contractor shall be responsible for verifying all dimensions.

Information hereon and herein is confidential.

REVISIONS

NO.	DATE	BY	DESCRIPTION
1	7/6/12	MRG	PER IDOT REVIEW

SCHEDULE OF QUANTITIES

PROJECT: PROPOSED IMPROVEMENTS FOR **RIVERFRONT TRAIL PHASE II** KANKAKEE, ILLINOIS

SECTION 10-00276-00-BT

DATE: 6/7/12 | JOB NO. E10054

SCALE: N/A | FILE NO.

DRAWN BY: MRG | SHEET 5

CHECKED BY: SRM