SCHEDULE OF QUANTITIES

		EARTH	WORK SLIMMAR			
I.OCATION	20200100	20300100	50200100	50200300	EMBANKMENT	*ESTIMATED
	EARTH	CHANNEL	STRUCTURE	COFFERDAM	(Ctl YD)	EARTH
	EXCAVATION	EXCAVATION	EXCAVATION	EXCAVATION		WASTE
[(CU YD)	(CU YD)	(CU YD)	(CU YD)		(CU YD)
C.H. 21 (KENNEY RD.)	136	717	122	94	399	570
TOTALS	136	717	122	94	399	570

*EARTH WASTE = EARTH EXCAVATION + CHANNEL EXCAVATION + STRUCTURE EXCAVATION + COFFERDAM EXCAVATION - (EMBANKMENT x 1.25 SHRINKAGE FACTOR)

- NOTES

 1. THE INDICATED EARTHWORK VOLUMES ARE ESTIMATES BASED ON THE "AVERAGE END AREA" METHOD OF CALCULATION.
 EARTHWORK VOLUMES WILL VARY WITH ACTUAL SOIL CONDITIONS ENCOUNTERED DURING CONSTRUCTION. THESE ESTIMATES
 ARE PROVIDED FOR THE CONVENENCE OF THE CONTRACTOR ONLY AND SHOULD BE CONSIDERED APPROXIMATE, ACTUAL
 VOLUMES OF EARTH EXCAVATION, CHANNEL EXCAVATION, STRUCTURE EXCAVATION, COFFERDAM EXCAVATION, AND EMBANKMENT
 WILL BE PAID FOR IN ACCORDANCE WITH THE STANDARD SPECIFICATIONS.
- THE EMBANKMENT QUANTITIES DO NOT ACCOUNT FOR SHRINKAGE FACTORS. A 25% SHRINKAGE FACTOR HAS BEEN APPLIED
 TO THE EMBANKMENT TO DETERMINE THE ESTIMATED VOLUME OF EARTH WASTE. THE EMBANKMENT QUANTITIES INCLUDE
 THE 4" THICK TOPSOIL LAYER.
- 3. EXCESS EARTH MATERIAL SHALL BE DISPOSED OF OFF-SITE BY THE CONTRACTOR. THE COST OF DISPOSING OF EXCESS EARTH MATERIAL WILL NOT BE PAID FOR SEPARATELY AND SHALL BE INCLUDED IN THE COST OF EARTH EXCAVATION.
- 4. AN ESTIMATED QUANTITY FOR THE REMOVAL AND DISPOSAL OF UNSUITABLE MATERIALS HAS BEEN INCLUDED IN THE CONTRACT.
 THE REMOVAL AND DISPOSAL OF UNSUITABLE MATERIALS WILL BE AS DIRECTED BY THE ENGINEER AND WILL BE MEASURED AND
 PAID FOR AS DESCRIBED IN THE SPECIAL PROVISIONS.

20201200 REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL

CHARLE INVITE	m1 12714	
LOCATION		CU YD
ASSUMED QUANTITY FOR UNSUITABLE SUBGRADE CONDITIONS		20
	TOTAL	20

25000400, 25000500, 25000600 FERTILIZER NUTRIENTS (NITROGEN, PHOSPHORUS, POTASSIUM)

#1211/44E/4 1/19E/		
LOCATION		POUND
C.H. 21 (KENNEY RD.) 313+10 TO 317+23 LT. & RT.		54
	TOTAL	54

21000300 GRANULAR EMBANKMENT, SPECIAL

OTATIONAL PROPERTY	, , 0, 2037.2	
LOCATION		TON
ASSUMED QUANTITY FOR UNSUITABLE SUBGRADE CONDITIONS		40
*	TOTAL	40

25100115 MULCH, METHOD 2

LOCATION		ACRE
C.H. 21 (KENNEY RD.) 313+10 TO 317+23 LT. & RT.		0.6
	TOTAL	0.6

21001000 GEOTECHNICAL FABRIC FOR GROUND START TATTON

GROUND STABILIZATI	ŲN
LOCATION	SQ YE
ASSUMED QUANTITY FOR UNSUITABLE SUBGRADE CONDITIONS	60
	TOTAL 60

28000250 TEMPORARY EROSION CONTROL SEEDING

LOCATION		POUND
C.H. 21 (KENNEY RD.) 313+10 TO 317+23 LT. & RT.		60
	TOTAL	60

25000200 SEEDING, CLASS 2

SCEUING,	CHASS &	
OCATION		ACRE
.H. 21 (KENNEY RD.) 313+10 TO 317+23 LT. & RT.		0.6
	TOTAL	0.6

31100500

	31100300				
SUBBASE GRANULAR	MATERIAL, TYPE	A 6"			
STATION	TO STATION	SQ YD			
C.H. 21 (KENNEY RD.)					
314+30.07 LT. & RT.	314+50.07 LT. & RT.	69			
315+30.74 LT. & RT.	315+50.74 LT. & RT.	69			
	TOTAL	138			

40200800

AGGREGATE SURFACE	COURSE,	TYPE	В
LOCATION			TON
C.H. 21 (KENNEY RD.) 316+60 RT F.E. (8" THICK)			56
•	TQ	TAL	56

48100100

SHOULDERS, TYPE A	
TO STATION	TON
314+50.07 LT.	28
314+50.07 RT.	28
316+59,0 LT.	28
316+45.9 RT.	26
TOTAL	110
	314+50,07 LT. 314+50.07 RT. 316+59,0 LT.

50300300

PROTECTIVE	COAT	
LOCATION		SQ YE
C.H. Z1 (KENNEY RD.)		
BRIDGE APPROACH PAVEMENT		125
BRIDGE DECK		314
	TOTAL.	439

X4201400

BRIDGE	APPROACH	PAVEMENT	(SPECIAL	_)
STATION		TO STATION		SQ YD
C.H. 21 (KENNEY	RD.)			
314+30-07 LT.	& RT.	314+50.07 LT.	& RT,	62.2
315+30.74 LT.	& RT.	315+50.74 LT.	& RT.	62.2
			TOTAL	125

FILE NAME = p:\m0320040_macon county - ch 21 bridge replacement\plans\sheets\schedule.dgn PLOT DATE = 12/21/2012 10:49:32 AM

DESIGNED	-	R.L.H.	REVISED -
DRAWN	-	J.L.B.	REVISED -
CHECKED	-	S.M.W.	REVISED -
DATE	-	NOV. 2012	REVISEO -

STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION

	F. F. T.	TOTAL SHEET
	RTE. SECTION	COUNTY SHEETS NO.
SCHEDULE OF QUANTITIES	546 10-00237-00-BR	MACON 25 5
		CONTRACT NO. 95694
SCALE : NONE SHEET NO. 5 OF 25 SHEETS STA. TO STA.	FED. ROAD DIST. NO. ILLINOIS FED.	AID PROJECT