

### **Prepared for:**

Illinois Department of Transportation, District 4 401 Main Peoria, Illinois 61602

### **Structure Designer:**

Michael Mendenhall Hanson Professional Services Inc. 1525 South Sixth Street Springfield, Illinois 62703 (217) 788-2450

### **Prepared By:**

Hanson Professional Services Inc. 1525 South Sixth Street Springfield, Illinois 62703 (217) 788-2450

rchantome@hanson-inc.com

## Abbreviated Structure Geotechnical Report

F.A.P. Route 317 (US 150) Section 15B(BR) Peoria County Job No. P-94-018-13 Contract No. 68B46 PTB No. 169-028 Ramp SW over Illinois River Tributary Structure No. 090-2020 Existing Structure No. 090-2013 Submitted August 2017 Revised June 2018



## Abbreviated Structure Geotechnical Report

| Original Report Date: 8/24/2017     | Proposed SN: 090-20 | 20 Route:   | US 150 - IL 116 SW Ramp |
|-------------------------------------|---------------------|-------------|-------------------------|
| Revised Date: 6/22/18               | Existing SN: 090-20 | 13 Section: | 15B(BR)                 |
| Geotechnical Engineer: Robert Chant | ome                 | County:     | Tazewell                |
| Structural Engineer: Hanson Profess | ional Services Inc. | Contract:   | 68B46                   |

Indicate the proposed structure type, substructure types, and foundation locations (attach plan and elevation drawing):

The proposed structure will be a 10 ft x 8 ft cast-in-place double barrel box culvert with horizontal cantilevered wing walls. The proposed location is at Ramp SW Sta. 26+80.35. The skew angle to the ramp is approximately 15 degrees. The proposed structure is approximately 90 ft downstream of the current structure, which will be removed. The proposed structure is in the same location as a 10 ft x 6 ft cast-in-place double box culvert that was removed to construct the current structure. The older culvert and an old Ramp SW alignment very similar to the proposed alignment was in place from 1963 to 1993. A plan and profile drawing of the old Ramp SW alignment is attached. **Discuss the existing boring data, existing plans foundation information, new subsurface exploration and need for any additional exploration to be provided with SGR Technical Memo (attach all data and subsurface profile plot):** 

There is no boring data shown on the existing structure plans. Two 50 ft soil borings were completed at the proposed structure location (SB-44 and SB-45). Additional soil exploration is not necessary.

Provide the location and maximum height of any new soil fill or magnitude of footing bearing pressure. Estimate the amount and time of the expected settlement. Indicate if further testing, analysis, and/or ground improvement/treatment is necessary:

The proposed structure will require approximately 10 ft of fill over the existing stream bed and approximately 3.5 ft of fill over the top slab. Service bearing pressure will be approximately 850 psf. Soil moisture contents and unconfined strengths were used to estimate the expected settlement. The soils at this site are known to be overconsolidated because of the old ramp embankment. It was assumed that cohesive soil settlement would be 10 to 20 percent of that calculated for normally consolidated soils. Estimated cohesive soil settlement is less than 0.5 inches under both the culvert and the tallest fill section.

No removal or treatment is required to remediate the settlement.

Identify any new cuts or fill slope angles and heights. Estimate the factor of safety against slope failure. Indicate if further testing, analysis or ground improvement/treatment is necessary:

The roadway embankment will be approximately 10 ft, maximum, above existing grade and have 1.0V:4.0H side slopes. This is very similar to the embankment that was in place on this site from 1963 to 1993. The proposed slopes are considered to be stable by inspection.

Indicate at each substructure, the 100-year and 200-year total scour depths in the Hydraulics report, the nongranular scour depth reduction, the proposed ground surface, and the recommended foundation design scour elevations:

Scour is not considered for box culvert design.

Determining the seismic soil site class, the seismic performance zone, the 0.2 and 1.0 second design spectral accelerations and indicate if that the soils are liquefiable: AASHTO does not require seismic analysis for buried structures.

cc: Bureau of Bridges and Structures

Confirm feasibility of the proposed foundation or wall type and provide design parameters. Attach a pile design table indicating feasible pile types, various nominal required bearings, factored resistances available and corresponding estimated lengths at locations where piles will be used. Provide factored bearing resistance and unit sliding resistance at various elevations and confirm no ground improvement/treatment is necessary where spread footings are proposed. Estimated top of rock elevations as well as preliminary factored unit side and tip resistance values shall be indicated when drilled shafts are proposed:

The proposed culvert is expected to have a factored bearing pressure of approximately 1.6 ksf at Elev. 467.5±. Thin, discontinuous, layers of soft cohesive soils and/or loose granular soils are present below Elev. 465.6 in Boring SB-44 and below Elev. 463.9 in Boring SB-45. At Elev. 467.5, the factored bearing resistance is 2.7 ksf, assuming no ground improvement and including the influence of the softer layers at depth.

Very soft soils may be present at the west end of the structure. This material should be removed and replaced where encountered at the subgrade elevation. For plan limits, the bottom of unsuitable removal should be Elev. 464.4, Removal should start 10 ft from the west end of the culvert and continue 3 ft. past the west end. Width of the removal should extend 3 ft beyond the edges of the culvert. Replacement material should be Rock Fill choked with 6 in. of CA7 or CA11..

# Calculate the estimated water surface elevation and determine the need for cofferdams (type 1 or 2), and seal coat:

EWSE = Elev. 472.1

Streamwater flow during construction will be diverted in accordance with the Standard Specifications. A cofferdam is not required.

# Assess the need for sheeting or soil retention or temporary construction slope and provide recommendation for other construction concerns:

All excavation will be shallow with room to lay back temporary slopes.

Although the soils at the bearing elevation will provide sufficient support for the structure, poor weather and construction disturbance may make them unstable. A working platform may be required to facilitate construction. Per IDOT policy, the need for a working platform should be determined during construction by the field engineer. District 4 policy is to include a 6 in. minimum layer of Porous Granular Embankment (CA7 or CA11) below all culverts. District Std 540000-D4, Detail of Excavation and Backfill for Box Culverts, and Special Provision 31100, Rock Fill, should be included in the contract documents.









## <u>LEGEND</u>

Ν Standard Penetration Test N (blows/ft)

Qu Unconfined Strength (tsf)

w% Natural Moisture Content (%)

Water Surface Elevation Encountered in Boring DD = during drilling

DD 558.10 √

Oh = at completion

24h = 24 hours after completion

| -  | USER NAME =           | DESIGNED - EJM | REVISED - |                              |                        | F.A.P.       | SECTION C             | OUNTY S | TOTAL SHEET |
|--|-----------------------|----------------|-----------|------------------------------|------------------------|--------------|-----------------------|---------|-------------|
|  |                       | CHECKED - RGC  | REVISED - | STATE OF ILLINOIS            |                        | 317          | 15B(BR) TA            | ZEWELL  |             |
|  | PLOT SCALE =          | DRAWN - EJM    | REVISED - | DEPARTMENT OF TRANSPORTATION | 51KUCIUKE NU. 090-2020 | _ CONTRACT N |                       |         | NO. 68B46   |
| Copyright Hanson Professional Services Inc. 2017 | PLOT DATE = 8/18/2017 | CHECKED – RGC  | REVISED - |                              | SHEET NO. 1 OF 1       |              | ILLINOIS FED. AID PRO | OJECT   |             |

8-inch thick, brown SILTY LOAM - TOPSOIL Soft to stiff, brown CLAY LOAM, trace gravel, trace organic debris; moist to wet

Very soft, brown SANDY LOAM; saturated Medium stiff, brown SILTY CLAY; moist

Soft, brown CLAY LOAM to LOAM; wet

Medium stiff to stiff, brown to gray SILTY CLAY to SILTY CLAY LOAM; moist

Medium dense, gray SILTY LOAM to SILT; wet

Medium dense, brown, medium SAND, little gravel;

Bottom of Hole = 50.0 feet





Client

Project

## **BORING LOG SB-44**

WEI Job No.: 414-09-01

wangeng@wangeng.com 1145 N Main Street Lombard, IL 60148 Telephone: 630 953-9928 Fax: 630 953-9938

## TYLin/Hanson

US 150 over Illinois River - McClugage

Datum: NAVD 88 Elevation: 472.38 ft North: 1474477.74 ft East: 2472726.90 ft Station: 26+56 Offset: 22.0 RT

| F                 | Fax: 630 953-9938 Location Peoria and Tazewell Counties, IL Offset: 22.0 RT |   |   |            |                          |             |                         |          |                   |   |                               |                  |                 |                          |             |                         |
|-------------------|---|---|---|------------|--------------------------|-------------|-------------------------|----------|-------------------|---|-------------------------------|------------------|-----------------|--------------------------|-------------|-------------------------|
| Profile           | Elevation   | E SOIL AND ROCK<br>DESCRIPTION                  | Depth<br>(ft)<br>Sample Type<br><sub>recovery</sub> | Sample No. | SPT Values<br>(blw/6 in) | Qu<br>(tsf) | Moisture<br>Content (%) | Profile  | Elevation<br>(ft) | SOIL AND ROCH<br>DESCRIPTION                                    | Depth (f)                     | Sample Type      | Sample No.      | SPT Values<br>(blw/6 in) | Qu<br>(tsf) | Moisture<br>Content (%) |
|                   |   |   |   |            |                          |             |                         |          |                   |   |                               |                  |                 |                          |             |                         |
|                   |   |   |   |            |                          |             |                         |          |                   |   |                               |                  |                 |                          |             |                         |
|                   |   |   |   |            |                          |             |                         |          |                   |   |                               |                  |                 |                          |             |                         |
|                   | <u>422</u>  | <sup>2.4</sup><br>Boring terminated at 50.00 ft | 50  | 16         | 3<br>4<br>6              | NP          | 21                      |          |                   |   |                               |                  |                 |                          |             |                         |
|                   |   |   | -   |            |                          |             |                         |          |                   |   |                               |                  |                 |                          |             |                         |
|                   |   |   | -<br>55<br>-<br>-<br>-                              |            |                          |             |                         |          |                   |   |                               |                  |                 |                          |             |                         |
| ANGENG.GDT 4/3/17 |   |   | -<br>-<br>-<br>-<br>-<br>-<br>-                     |            |                          |             |                         |          |                   |   |                               |                  |                 |                          |             |                         |
| ≥<br>L            |   |   |   |            |                          |             |                         |          |                   |   |                               |                  |                 |                          |             |                         |
| <u>а</u> 901.GI   | eain  | Drilling 09-23-2016                             |   |            | lina                     | 0           | 9-23                    | -201     | 16                | While Drilling  |                               |                  | AI.<br>70       | A<br>0 ft                |             |                         |
| D 4140            | rilling   | g Contractor Wang Testin                        | g Service   | <br>D      | Drill Rig                | D!          | 50 A                    | <u> </u> |                   | At Completion of Drilling                                       | <u>+</u>                      | 1                | 29.0            | 00 ft                    |             | •••••                   |
| D BIN             | riller  | K&N Logger                                      | J. Foote  |            | . Che                    | ecked I     | ру (                    | С. М     | arin              | Time After Drilling   | NA                            |                  |                 |                          |             |                         |
| D den             | rilling   | g Method 3.25" IDA HSA; I                       | ooring back   | fill       | ed uj                    | oon d       | comp                    | oleti    | on                | Depth to Water  | NA                            | <u></u>          |                 |                          |             |                         |
| MAN               |   |   |   |            |                          |             |                         |          |                   | The stratification lines repro-<br>between soil types; the actu | sent the app<br>al transition | roxima<br>may br | ate bo<br>e gra | oundary<br>dual.         | /           |                         |



VANGENGINC 4140901.GPJ WANGENG.GDT 4/3/17

| w<br>1  | rangeng(<br>145 N M   | Wang<br>Engineering          | Client              |             |            | BC                       |              | NG<br>Job<br>TYL        | <b>L</b><br>No.<br>in/H | OG<br>: 414<br>lanso | <b>SB-45</b><br>1-09-01       |
|---------|-----------------------|------------------------------|---------------------|-------------|------------|--------------------------|--------------|-------------------------|-------------------------|----------------------|-------------------------------|
| F       | elephone<br>ax: 630 9 | e: 630 953-9928<br>953-9938  | Project<br>Location | ι<br>Ι ω    | U          | S 150<br>Peo             | ove<br>ria a | r Illin<br>nd Ta        | iois<br>azev            | Rive<br>vell (       | r - McClugage<br>Counties, IL |
| Profile | Elevation<br>(ft)     | SOIL AND ROCK<br>DESCRIPTION | Depth<br>(ft)       | Sample Type | Sample No. | SPT Values<br>(blw/6 in) | Qu<br>(tsf)  | Moisture<br>Content (%) | Profile                 | Elevation<br>(ft)    | SOIL AND<br>DESCRII           |
|         |                       | light rig cha                | -<br><br>atter      |             |            |                          |              |                         |                         |                      |                               |

## Datum: NAVD 88 Elevation: 471.85 ft North: 1474472.52 ft East: 2472768.00 ft Station: 26+70 Offset: 17.0 LT

| WANGEN  | INC 41                      | 40901.            | .GPJ        | 5PJ WANGENG.GDT 4/3/17  |                                    |                                      |
|---|-----------------------------|-------------------|-------------|---|------------------------------------|--------------------------------------|
| Dr  | Dr<br>Dr                    | Be                |             |   |                                    | Profile                              |
| illing Me                                       | illing Co<br>iller          | egin Drill        | •           | 421.9<br>Bo   |                                    | Elevation<br>(ft)                    |
| ethod <b>3.25"</b>                              | ontractor W                 | ling 09-22        |             | oring terminated  |                                    | SOIL ANI<br>DESCRI                   |
| IDA HSA; bo                                     | ang Testing                 | 2-2016            | GENER       | d at 50.00 ft   | light rig chatte<br>possible grave | D ROCK<br>PTION                      |
| oring I   | Servi                       | Com               | AL N        | 45<br>45<br>-<br>-<br>-<br>-<br>-<br>-<br>-<br>-<br>-<br>-<br>-<br>-<br>-<br>-<br>-<br>-<br>- | -<br>                              | Depth<br>(ft)                        |
| oac   | ice<br>oot                  | plete             | ΟΤ          |   |                                    | Sample Type                          |
| kfill   | C<br>Ə                      | Dril              | ES          | 15<br>16  |                                    | Sample No.                           |
| ed u  | Drill Rig<br>C.h.           | ling              |             | 7<br>8<br>9<br>3<br>5<br>7  |                                    | SPT Values<br>(blw/6 in)             |
| pon   | D<br>ecked                  |                   | •           | NP  |                                    | Qu<br>(tsf)                          |
| com   | 50 A                        | 9-22              |             | 23  |                                    | Moisture<br>Content (%)              |
| pleti   | TV [<br>C. №                | 2-20 <sup>°</sup> | •           |   |                                    | Profile                              |
| on  | 88%]<br>Iarin               | 16                |             |   |                                    | Elevation<br>(ft)                    |
| Depth to W<br>The stratification between soil   | At Complet                  | While Drillin     |             |   |                                    | SOIL AI<br>DESCI                     |
| ater<br>ation lines represent types; the actual | ion of Drilling<br>Drilling | ng                | WATER       | WATER   |                                    | ND ROCK<br>RIPTION                   |
| NA<br>sent the app                              | ▼<br>NA                     | <u> </u>          | <b>LEVE</b> |   |                                    | Depth<br>(ft)                        |
| roximate<br>nay be c                            | 35                          | 8                 | LDA         |   |                                    | Sample Type<br>recovery<br>Sample No |
| boundar<br>radual.                              | .00 ft                      | 50 ft             | ΤA          | TA  |                                    | SPT Values<br>(blw/6 in)             |
| у   |                             |                   |             |   |                                    | Qu<br>(tsf)                          |
|   |                             |                   |             |   |                                    | Moisture<br>Content (%)              |

Page 2 of 2



CONTINUE

STATE OF ILLINOIS DETAIL OF EXCAVATION AND BAG **DEPARTMENT OF TRANSPORTATION** NOT TO SCALE

|                         | F.A.<br>RTE. | SEC          | TION            | COUNTY     | TOTAL<br>SHEETS | SHEET<br>NO. |
|-------------------------|--------------|--------------|-----------------|------------|-----------------|--------------|
| CKFILL FOR BOX CULVERIS |              |              |                 |            |                 |              |
|                         |              |              |                 | CONTRACT   | NO.             |              |
| CADD STD. 540000-D4     | FED. RO      | AD DIST. NO. | ILLINOIS FED. A | ID PROJECT |                 |              |

## 31100

Designer Note: Check with Materials before using this special provision. Can be used Districtwide since this is the lowest quality (B) rock. This special provision is intended to be used when rock fill is recommended for ground stabilization or undercuts. This material may need to be capped with 6" CA 7 or CA 11, crushed stone depending upon situation and modify this special provision. Remember when using precast box culverts, a 6" bedding layer is included in the box culvert pay item.

A filter fabric (or bedding material) may be required - discuss with the Geotechnical Engineer. He may want you to provide a pay item/quantity for "Geotechnical Fabric for Ground Stabilization".

## **ROCK FILL**

Effective October 15, 1995 Revised April 26, 2013

This work shall consist of furnishing, transporting and placing rock fill for ground stabilization.

For Rock Fill depths ≤18", the material shall meet Quality Designation "B" as required in Article 1004.01 of the Standard Specifications for Road and Bridge Construction. The material shall be crushed stone and meet the gradation of CA 7 or CA 11 per Article 1004.01 of the Standard Specifications for Road and Bridge Construction.

The aggregate shall be placed in 6 in. (150 mm) lifts, loose measurements, and compacted in a manner approved by the Engineer, except that if the desired results are being obtained, the compacted thickness of any lift may be increased to a maximum of 8 in. (200 mm).

For Rock Fill depths > 18", the top 6" shall meet the requirements listed above for depths ≤18" and the remaining depth shall meet Quality Designation "B" as required in <u>Article 1005.01</u> of the Standard Specifications for Road and Bridge Construction and may be shot rock or primary crusher run. It shall not contain objectionable quantities of dirt, sand, clay or rock fines. The material shall be well graded with a maximum stone dimension of 8 inches (200 mm). No more than 35% shall have a dimension less than 2 inches (50 mm).

Rock fill will be measured for payment in tons (metric tons), in accordance with Article 311.08 except that all references to cubic yard (cubic meter) measurement and payment shall be deleted.

This work will be paid for at the contract unit price per Ton (Metric Ton) for ROCK FILL.