

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		100% STATE 0004		
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	315	315		
20400800	FURNISHED EXCAVATION	CU YD	324	324		
21400100	GRADING AND SHAPING DITCHES	FOOT	93	93		
28000400	PERIMETER EROSION BARRIER	FOOT	337	337		
28100107	STONE RIPRAP, CLASS A4	SO YD	128	128		
28200200	FILTER FABRIC	SO YD	173	173		
28300400	AGGREGATE DITCH	TON	3	3		
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	12	12		
50102400	CONCRETE REMOVAL	CU YD	9	9		
50200100	STRUCTURE EXCAVATION	CU YD	61	61		
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	8770	8770		
52200020	TEMPORARY SOIL RETENTION SYSTEM	SO FT	208	208		
54002020	EXPANSION BOLTS 3/4 INCH	EACH	28	28		
54003000	CONCRETE BOX CULVERTS	CU YD	45.3	45.3		

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		100% STATE 0004		
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	1	1		
542A1069	PIPE CULVERTS, CLASS A, TYPE 2 24"	FOOT	24	24		
67100100	MOBILIZATION	L SUM	1	1		
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1		
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	15	15		
70107025	CHANGEABLE MESSAGE SIGN	CAL DA	56	56		
X0426200	DEWATERING	L SUM	1	1		
X2501000	SEEDING, CLASS 2 (SPECIAL)	ACRE	0.2	0.2		
XX009289	TRAFFIC CONTROL AND PROTECTION, STANDARD BLR 21	L SUM	1	1		
* Z0054402	ROCK FILL - REPLACEMENT	CU YD	39	39		
* SPECIALTY ITEM						

MODEL: Default
 FILE NAME: I:\1108\FEB\DOT\EG\Illinois\gdp\PHWDOT\Documents\DOT_Offices\District_7\Projects\71886\CAD\Drawings\DOT71886-Sub-500.dgn

REV. 4-18-2019 REV. - MS

USER NAME = steffenmk	DESIGNED -	REVISED -
PLOT SCALE = 100.0000' / in.	DRAWN -	REVISED -
PLOT DATE = 1/28/2019	CHECKED -	REVISED -
	DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**SUMMARY OF
QUANTITIES**

SCALE: NA SHEET 1 OF 1 SHEETS STA. TO STA.

F.A.P. RTE. 332	SECTION 19CLV	COUNTY CRAWFORD	TOTAL SHEETS 16	SHEET NO. 3
CONTRACT NO. 74886				
ILLINOIS FED. AID PROJECT				