

SUMMARY OF QUANTITIES					CONSTRUCTION TYPE CODE	CONSTRUCTION TYPE CODE	CONSTRUCTION TYPE CODE
					80% FEDERAL / 20% ROUND LAKE BEACH	80% FEDERAL / 20% ROUND LAKE BEACH	80% FEDERAL / 20% ROUND LAKE BEACH
	CODE NO.	ITEM	UNIT	TOTAL QUANTITY	HOOK DRIVE 0005	ORCHARD LANE 0005	TRAINEES 0042
	70300570	PAVEMENT MARKING TAPE, TYPE III 24"	FOOT	244	0	244	0
*	72000100	SIGN PANEL - TYPE 1	SQ FT	18	18	0	0
*	72400310	REMOVE SIGN PANEL - TYPE 1	SQ FT	9	9	0	0
*	72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	30	30	0	0
*	78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	234	234	0	0
*	78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	35,044	20,527	14,517	0
*	78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	4,137	1,903	2,234	0
*	78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	2,388	1,797	591	0
*	78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	478	223	255	0
	78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	50	50	0	0
SP	X0323389	STORM SEWER CONNECTION	EACH	13	0	13	0
SP	X0323455	ADJUST MONITORING WELLS	EACH	1	1	0	0
SP	X0327036	BIKE PATH REMOVAL	SQ YD	79	79	0	0
SP	X0327301	RELOCATE EXISTING MAILBOX	EACH	44	0	44	0
SP	X0327727	PLANTER REMOVAL	L SUM	1	1	0	0

SP - SPECIAL PROVISION \* SPECIALTY ITEM

USER NAME = jrusak	DESIGNED - MJV	REVISED - 4/2/2019
PLOT SCALE = 1/8" = 1' / 1"	DRAWN - PJS	REVISOR -
PLOT DATE = 4/7/2019	CHECKED - KLB	REVISOR -
	DATE - 2/13/2019	REVISOR -

STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES  
 ORCHARD LANE / HOOK DRIVE

SCALE: NONE SHEET 6 OF 8 SHEETS STA. TO STA.

F.A. RTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1043	15-0078-00-PV	LAKE	228	9
MUN. RTE				
1061				
CONTRACT NO. 61F65				
ILLINOIS FED. AID PROJECT				

SUMMARY OF QUANTITIES					CONSTRUCTION TYPE CODE	CONSTRUCTION TYPE CODE	CONSTRUCTION TYPE CODE
					80% FEDERAL / 20% ROUND LAKE BEACH	80% FEDERAL / 20% ROUND LAKE BEACH	80% FEDERAL / 20% ROUND LAKE BEACH
	CODE NO.	ITEM	UNIT	TOTAL QUANTITY	HOOK DRIVE 0005	ORCHARD LANE 0005	TRAINEES 0042
SP	X1700021	BRICK PAVER REMOVAL AND REINSTALLATION, SPECIAL	SQ FT	332	0	332	0
SP	X3400004	RETAINING WALL REMOVAL	FOOT	99	0	99	0
SP	X4021000	TEMPORARY ACCESS (PRIVATE ENTRANCE)	EACH	48	0	48	0
SP	X4022000	TEMPORARY ACCESS (COMMERCIAL ENTRANCE)	EACH	9	0	9	0
SP	X4023000	TEMPORARY ACCESS (ROAD)	EACH	22	0	22	0
SP	X4024000	TEMPORARY ACCESS (FIELD ENTRANCE)	EACH	4	0	4	0
SP	X4060995	TEMPORARY RAMP, SPECIAL	SQ YD	123	0	123	0
SP	X6030205	FRAMES AND GRATES TO BE ADJUSTED (SPECIAL)	EACH	1	1	0	0
SP	X6700410	ENGINEER'S FIELD OFFICE, TYPE A (SPECIAL)	CAL MO	18	9	9	0
SP	X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	0.5	0.5	0
* SP	X8440116	RELOCATE EXISTING LIGHTING UNIT, SPECIAL	EACH	1	0	1	0
SP	Z0013798	CONSTRUCTION LAYOUT	L SUM	1	0.5	0.5	0
SP	Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	57	0	57	0
SP	Z0051500	REMOVING AND RESETTING STREET SIGNS	EACH	25	1	24	0
SP	Z0056648	STORM SEWERS, TYPE 1, WATER MAIN QUALITY PIPE, 12"	FOOT	226	0	226	0
SP	Z0056668	STORM SEWERS, TYPE 2, WATER MAIN QUALITY PIPE, 12"	FOOT	23	0	23	0

SP - SPECIAL PROVISION \* SPECIALTY ITEM

4800.016-041	USER NAME = jhamilton	DESIGNED - MJV	REVISED - 4/2/2019	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES ORCHARD LANE / HOOK DRIVE		F.A.U. RTE. 1948	SECTION 15-00078-00-PV	COUNTY LAKE	TOTAL SHEETS 228	SHEET NO. 10
	PLOT SCALE = 1/8" = 1'-0"	DRAWN - PJS	REVISED -		SCALE: NONE	SHEET 7 OF 8 SHEETS	STA. TO STA.	ILLINOIS	FED. AID PROJECT		
	PLOT DATE = 4/23/2019	CHECKED - KLB	REVISED -								
		DATE - 2/13/2019	REVISED -								