



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

April 12, 2024

SUBJECT FAP Route 303 (IL 173)
Project NHPP-HU7W(271)
Section 2020-187-RS&SW
McHenry & Lake Counties
Contract No. 62M25
Item No. 194, April 26, 2024 Letting
Addendum A

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised the Schedule of Prices
2. Revised page ii of the Table of Contents to the Special Provisions
3. Revised pages 28 & 88 of the Special Provisions
4. Revised sheets 3, 4, 6 & 7 of the Plans

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

A handwritten signature in black ink, appearing to read "Jack A. Elston".

Jack A. Elston, P.E.
Bureau Chief, Design and Environment

MTS

CONSTRUCTION AIR QUALITY – DIESEL RETROFIT (BDE).....	74
DISADVANTAGED BUSINESS ENTERPRISE PARTICIPATION (BDE)	76
FUEL COST ADJUSTMENT (BDE).....	85
HOT-MIX ASPHALT (BDE).....	88
HOT-MIX ASPHALT – LONGITUDINAL JOINT SEALANT (BDE).....	89
PERFORMANCE GRADED ASPHALT BINDER (BDE).....	90
PORTLAND CEMENT CONCRETE (BDE)	95
REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES (BDE)	95
SEEDING (BDE)	96
SHORT TERM AND TEMPORARY PAVEMENT MARKINGS (BDE).....	101
SOURCE OF SUPPLY AND QUALITY REQUIREMENTS (BDE)	104
SUBCONTRACTOR AND DBE PAYMENT REPORTING (BDE)	104
SUBCONTRACTOR MOBILIZATION PAYMENTS (BDE)	105
SUBMISSION OF PAYROLL RECORDS (BDE).....	105
SURFACE TESTING OF PAVEMENTS – IRI (BDE)	106
TRAINING SPECIAL PROVISIONS (BDE)	113
IDOT TRAINING PROGRAM GRADUATE ON-THE-JOB TRAINING SPECIAL PROVISION.....	116
VEHICLE AND EQUIPMENT WARNING LIGHTS (BDE)	118
WEEKLY DBE TRUCKING REPORTS (BDE).....	118
WORK ZONE TRAFFIC CONTROL DEVICES (BDE)	118
WORKING DAYS (BDE).....	120
MENTOR-PROTÉGÉ PROGRAM	121
PROJECT LABOR AGREEMENT	122

Revised 4/12/2024

SPECIAL PROVISIONS:

Maintenance of Roadways (D-1)
Public Convenience and Safety (D-1)
Temporary Information Signing
Work Zone Traffic Control Devices (BDE)
Vehicle and Equipment Warning Lights (BDE)
Pavement and Shoulder Resurfacing (Recurring SP CS#13)
Short Term and Temporary Pavement Markings (BDE)

CURB OR COMBINATION CURB AND GUTTER REMOVAL AND REPLACEMENT (D1)

Effective: November 1, 2020
Revised: September 1, 2022

Description. This work shall consist of the complete removal and replacement of curb or combination curb and gutter. Work shall be according to Sections 440 and 606 of the Standard Specifications, State Standard 606001, District Detail BD-24 and as directed by the Engineer except as modified herein.

Curb or combination curb and gutter removal and replacement shall match the type of the existing curb or combination curb and gutter. Types may be variable and are to meet existing dimensions and field conditions. Locations of removal and replacement shall be determined by the Resident Engineer at the time of construction.

Unsuitable material to be removed, as directed by the Engineer, shall be replaced with subbase granular material, type B or additional thickness of concrete. Suitable backfill material, when required, shall be replaced as directed by the Engineer.

Epoxy coated tie bars, #6 (20) - 24" (610) long at 24" (610) centers, shall be used except when adjacent to flexible pavement. Longitudinal bars, if encountered, are not to be replaced.

Hot-mix asphalt surface removal on the existing gutter flag, if encountered, shall be included in the removal of the curb and gutter.

Saw cuts shall be according to Article 440.03 of the Standard Specifications.

½" (13) preformed expansion joints shall be used at concrete sidewalks, driveways and medians.

Method of Measurement. Concrete curb removal and replacement, or combination concrete curb and gutter removal and replacement will be measured for payment in feet (meters) along the face of concrete curb. A minimum replacement length of 4 feet is required.

Revised 4/12/2024

Basis of Payment. Fuel cost adjustments may be positive or negative but will only be made when there is a difference between the FPI_L and FPI_P in excess of five percent, as calculated by:

$$\text{Percent Difference} = \{(FPI_L - FPI_P) \div FPI_L\} \times 100$$

Fuel cost adjustments will be calculated for each calendar month in which applicable work is performed; and will be paid or deducted when all other contract requirements for the items of work are satisfied. The adjustments shall not apply during contract time subject to liquidated damages for completion of the entire contract.

HOT-MIX ASPHALT (BDE)

Effective: January 1, 2024

Revise the second paragraph of Articles 1030.07(a)(11) and 1030.08(a)(9) of the Standard Specifications to read:

“When establishing the target density, the HMA maximum theoretical specific gravity (G_{mm}) will be based on the running average of four available Department test results for that project. If less than four G_{mm} test results are available, an average of all available Department test results for that project will be used. The initial G_{mm} will be the last available Department test result from a QMP project. If there is no available Department test result from a QMP project, the Department mix design verification test result will be used as the initial G_{mm} .”

In the Supplemental Specifications, replace the revision for the end of the third paragraph of Article 1030.09(h)(2) with the following:

“When establishing the target density, the HMA maximum theoretical specific gravity (G_{mm}) will be the Department mix design verification test result.”

Revise the tenth paragraph of Article 1030.10 of the Standard Specifications to read:

“Production is not required to stop after a test strip has been constructed.”

Revised 4/12/2024