LETTING ITEM NO. 01A IDOT LETTING APRIL 26, 2024

CITY OF DEKALB DEKALB COUNTY, ILLINOIS

INDEX TO SHEETS

- COVER SHEET 1.
- SITE PLAN / PROJECT CONTROL 2.
- CONSTRUCTION SAFETY AND PHASING PLAN 3.
- 4. CONSTRUCTION SAFETY AND PHASING PLAN GENERAL NOTES AND DETAILS

J.U.L.I.E.

THE LOCATION, SIZE AND TYPE OF MATERIAL OF EXISTING LINDERGROUND.

UTILITES INDICATED ON THE PLANS IS NOT REPRESENTED AS BEING ACCURATE, SUFFICIENT OR COMPLETE IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO

DETERMINE ACTUAL LOCATIONS OF ALL SUCH FACILITIES, INCLUDING SERVICE CONNECTIONS TO UNDERGROUND UTILITIES, PRIOR TO CONSTRUCTION, THE CONTRACTOR SHALL NOTIFY UTILITY COMPANIES OF HIS OPERATIONAL PLANS

OBTAIN FROM RESPECTIVE UTILITY COMPANIES DETAILED INFORMATION AND ASSISTANCE RELATIVE TO THE LOCATION OF THEIR FACILITIES AND THE WORKING SCHEDULE OF THE COMPANIES FOR REMOVAL OR ADJUSTMENT WHERE REQUIRED

IN THE EVENT AN UNEXPECTED UTILITY INTERFERENCE IS ENCOUNTERED DURING

CONSTRUCTION, THE CONTRACTOR SHALL IMMEDIATELY NOTIFY THE UTILITY COMPANY OF JURISDICTION AND THE ONE-CALL NOTICE SYSTEM. THE ENGINEER

SHALL ALSO BE IMMEDIATELY NOTIFIED, ANY SUCH UTILITY OR SERVICES SHALL BE

BESTORED TO SERVICE AT ONCE AND PAID FOR BY THE CONTRACTOR AT NO ADDITIONAL COST TO THE CONTRACT.

CALL J.U.L.I.E. FOR UTILITY INFORMATION AT 811.

CITY OF DEKALB

BENJAMIN TROMPETER, AIRPORT OPERATIONS MANAGER

MARCH 1

3232 PLEASANT STREET DEKALB, ILLINOIS 60115 Felephone: 815.748.8102

DEKALB TAYLOR MUNICIPAL AIRPORT

2024

www.illinois1call.com

JOINT UTILITY LOCATING INFORMATION FOR EXCAVATORS

- 5 FENCING PLAN 1
- 6. FENCING PLAN 2
- 7. FENCING PLAN 3
- 8 FENCING PLAN 4
- 9. ELECTRIC GATE PLAN 1
- 10. ELECTRIC GATE PLAN 2
- 11. CANTILEVER GATE DETAILS
- 12. FENCING DETAILS 1
- 13. FENCING DETAILS 2

RT

APPROVED BY

DATE

- 14. FENCING DETAILS 3
- 15 ELECTRIC GATE DETAILS
- 16. STORMWATER POLLUTION PREVENTION PLAN

Know what's below.

Call before you dig.



REPLACE PERIMETER FENCING, PHASE 1



ILLINOIS PROJECT: DKB-5118 S.B.G. PROJECT: 3-17-SBGP-TBD



MARCH 1, 2024

ITE BASE AR1 AR1 AR16 AR16 AR1 AR16 AR16 AR16 AR16 AR16 AR1 AR1 AR1 AR8 AR8 AR8 ARS AR9 ADDI AS16 AS16 AS16 AS800 AS800 AS90 AS908

SITE PLAN

DK065 TOTAL SHEETS = 16

SUMMARY OF QUANTITIES				
VI NO.	DESCRIPTION	UNIT	ESTIMATED QUANTITY	RECORD QUANTITY
E BID				
50520	MOBILIZATION	L SUM	1	
61900	REMOVE CLASS C FENCE	FOOT	1120	
62216	CLASS E MANUAL SLIDE GATE-16'	EACH	1	
62510	CLASS E FENCE 10'	FOOT	640	
62531	WALKWAY GATES, CLASS E	EACH	15	
62612	CLASS E GATE-12'	EACH	6	
62716	ELECTRIC GATE-16'	EACH	1	
62724	ELECTRIC GATE-24'	EACH	1	
62726	ELECTRIC GATE-26'	EACH	2	
62900	REMOVE CLASS E FENCE	FOOT	4700	
62905	REMOVE GATE	EACH	17	
62908	REMOVE ELECTRIC GATE	EACH	6	
63000	TEMPORARY CONSTRUCTION FENCE	FOOT	2000	
00011	ELECTRIC GATE-26', SPECIAL	L SUM	1	
00110	CLASS E FENCE 10' W/4' BURY	FOOT	5130	
00173	WILDLIFE DETERRENT BARRIER-PAD	SQ FT	280	
01510	SEEDING	ACRE	1.5	
08514	LIGHT DUTY-HYDRAULIC MULCH	ACRE	1.5	
TIVE ALTERNATE NO. 1				
2612	CLASS E GATE-12'	EACH	2	
2900	REMOVE CLASS E FENCE	FOOT	1180	
2905	REMOVE GATE	EACH	3	
0110	CLASS E FENCE 10' W/4' BURY	FOOT	1200	
0173	WILDLIFE DETERRENT BARRIER-PAD	SQ FT	100	
1510	SEEDING	ACRE	0.5	
8514	LIGHT DUTY-HYDRAULIC MULCH	ACRE	0.5	

CALL J.U.L.I.E. BEFORE **EXCAVATING AT 811** DEKALB TAYLOR MUNICIPAL AIRPORT

TOWNSHIP: 40 NORTH RANGE: 5 EAST SECTION: 17, 18 AND 19 COUNTY: DEKALB TOWNSHIP: CORTLAND

© Copyright CMT, Inc.		23005748.00
CRAWFORD, MURPHY 8 CONSULTING ENGINEER License No. 184-000613	TILLY, INC. RS	
SUBMITTED BY	allam Mou	lon
DATE	MARCH 1	





GENERAL

- THE CONTRACTOR AND ALL SUBCONTRACTORS SHALL FOLLOW THE REQUIREMENTS OF THE AIRPORT'S APPROVED CONSTRUCTION SAFETY AND PHASING PLAN (CSPP), FAA AC 150/5370-2(LATEST EDITION), AND ALL AIRPORT SAFETY AND SECURITY REQUIREMENTS.
- PRIOR TO THE START OF CONSTRUCTION THE CONTRACTOR SHALL 2. SUBMIT TO THE AIRPORT FOR APPROVAL A SAFETY PLAN COMPLIANCE DOCUMENT (SPCD) IN ACCORDANCE WITH FAA AC 150/5370-2(LATEST EDITION). NO CONSTRUCTION ACTIVITY SHALL BEGIN UNTIL THE AIRPORT HAS APPROVED THE SPCD.
- THE CSPP COVERS OPERATIONAL SAFETY. THE CONTRACTOR SHALL BE З. RESPONSIBLE FOR THE INDIVIDUAL SAFETY OF HIS/HER PERSONNEL AND MEETING SAFETY REQUIREMENTS.
- A MINIMUM OF 10 DAYS PRIOR TO THE PRECONSTRUCTION MEETING THE CONTRACTOR SHALL PROVIDE A LIST OF SUBCONTRACTORS AND MATERIAL SUPPLIERS
- A MINIMUM OF 10 DAYS PRIOR TO THE NOTICE TO PROCEED THE CONTRACTOR SHALL SUBMIT THE SPCD FOR APPROVAL
- THE SUGGESTED SEQUENCE OF CONSTRUCTION SHOWN IS INTENDED TO ALLOW FOR THE ORDERLY CONSTRUCTION OF THE NEW IMPROVEMENTS WHILE MAINTAINING AIRCRAFT ACCESS AT ALL TIMES. THE PHASING SHOWN IS A SUGGESTED SEQUENCE OF CONSTRUCTION ONLY. THIS SEQUENCE MAY BE MODIFIED WITH THE APPROVAL OF THE AIRPORT. HOWEVER, ALTERNATE STAGING PLANS MUST MAINTAIN AIRPORT OPERATIONS TO THE SATISFACTION OF THE AIRPORT.
- THE CONTRACTOR SHALL BE REQUIRED TO PROVIDE DUST CONTROL AT ALL TIMES DURING THE PROJECT DURATION. A WATER TRUCK SHALL BE REQUIRED TO BE ONSITE DURING ALL CONSTRUCTION OPERATION WORKING HOURS, UNLESS WAIVED BY THE AIRPORT, PAYMENT FOR DUST CONTROL SHALL BE CONSIDERED INCIDENTAL TO THE CONTRACT
- PAYMENT FOR ALL AIRSIDE AND ROADWAY TRAFFIC CONTROL INCLUDING BUT NOT LIMITED TO, TEMPORARY CONSTRUCTION FENCING, BARRICADES, SIGNING, AIR OPERATIONS AREA (A.O.A) LATH AND RIBBON. ETC. SHALL BE CONSIDERED INCIDENTAL TO THE CONTRACT
- ALL CONTRACTOR COSTS ASSOCIATED WITH THE REQUIREMENTS LISTED ON THIS SHEET SHALL BE CONSIDERED INCIDENTAL TO THE CONTRACT UNLESS A SPECIFIC PAY ITEM IS PROVIDED.

. COORDINATION

- PRIOR TO THE START OF CONSTRUCTION THE CONTRACTOR SHALL ATTEND A PRECONSTRUCTION CONFERENCE WITH THE AIRPORT. RESIDENT ENGINEER, AND ILLINOIS DIVISION OF AERONAUTICS (IDA). THE COST OF PREPARING FOR AND ATTENDING THE PRECONSTRUCTION CONFERENCE SHALL BE INCIDENTAL TO THE CONTRACT.
- ON OR BEFORE THE PRECONSTRUCTION CONFERENCE, THE CONTRACTOR SHALL SUBMIT A PROPOSED SCHEDULE FOR THE PROJECT. THE SCHEDULE SHALL INCLUDE A START AND COMPLETION DATE FOR EACH ITEM OF WORK. THE SCHEDULE SHALL BE UPDATED ON A WEEKLY BASIS ALL COSTS ASSOCIATED WITH THE SCHEDULE SHALL BE INCIDENTAL TO THE CONTRACT.

2. PHASING

TOTAL CONTRACT TIME SHALL BE 56 CALENDAR DAYS.

PHASING SHALL BE AS NOTED BELOW AND AS SHOWN ON THE 2 CONSTRUCTION SAFETY AND PHASING PLAN SHEET.

3. AREAS AND OPERATIONS AFFECTED BY CONSTRUCTION

- ALL RUNWAYS, TAXIWAYS AND APRONS SHALL BE KEPT OPEN TO AIRCRAFT TRAFFIC DURING CONSTRUCTION EXCEPT AS NOTED ON THE CONSTRUCTION SAFETY AND PHASING PLAN SHEET.
- WHEN CONFLICTS ARISE BETWEEN CONSTRUCTION ACTIVITIES AND AIRCRAFT OPERATIONS AND SAFETY, AIRCRAFT OPERATIONS AND SAFETY SHALL TAKE PRECEDENCE AND SHALL GOVERN FINAL AUTHORITY IN THE APPROVAL OF CONSTRUCTION SEQUENCING LIES WITH THE AIRPORT
- AIRCRAFT OPERATIONS HAVE THE RIGHT-OF-WAY ON THE AIRFIELD. ALL 3 CONSTRUCTION TRAFFIC SHALL IMMEDIATELY YIELD TO ONCOMING AIRCRAFT AT ALL TIMES.
- SHOULD IT BE NECESSARY FOR THE CONTRACTOR TO TEMPORARY RELOCATE EQUIPMENT AT ANY TIME TO ALLOW AN AIRCRAFT TO PASS, THE CONTRACTOR SHALL DO SO IMMEDIATELY AT NO EXTRA COST TO THE

4. PROTECTION OF NAVIGATION AIDS (NAVAIDS)

THE CONTRACTOR SHALL REMAIN CLEAR OF THE ILS CRITICAL AREAS AND OTHER NAVAIDS FACILITIES AT ALL TIMES.

5. CONTRACTOR ACCESS

- CONTRACTOR ACCESS SHALL BE AS NOTED BELOW AND AS SHOWN ON THE SITE PLAN AND CONSTRUCTION SAFETY AND PHASING PLAN SHEETS
- THE CONTRACTOR IS TO ACCESS THE SITE USING THE EXISTING GATE SHOWN. THE ENTRANCE SHALL BE SIGNED ACCORDINGLY AS TO ALLOW ONLY CONSTRUCTION VEHICLES ACCESS AND WILL ONLY BE ACCESSIBLE DURING THE CONTRACTOR'S SCHEDULED WORK DAY, ALL SIGNAGE SHALL CONFORM TO CITY OF DEKALB AND IDOT CONSTRUCTION STANDARDS FOR VEHICLES ENTERING AND LEAVING THE SITE.
- SUPERVISORY PERSONNEL SHALL DEMONSTRATE IN THE PRESENCE OF

THE AIRPORT MANAGER THAT THEY ARE FAMILIAR WITH AIRPORT RADIO AND AIRPORT DRIVING PROCEDURES IN ORDER TO PERFORM WORK OTHER CONSTRUCTION PERSONNEL CAN BE WITHIN THE AIRFIELD LIMITS PROVIDED THAT THEY ARE UNDER ESCORT AND IN THE PRESENCE OF AN AUTHORIZED SUPERVISOR. KNOWLEDGE OF THE AIRPORTS PROCEDURE'S BY THE SUPERVISORY PERSONNEL MUST BE DEMONSTRATED PRIOR TO THE START OF CONSTRUCTION.

- THE CONTRACTOR'S STORAGE AND STAGING AREA WILL BE AS SHOWN IN THE SITE PLAN AND CONSTRUCTION PHASING PLAN.
- THE CONTRACTOR'S MATERIAL AND EQUIPMENT, WHEN NOT IN USE, SHALL 5. BE STORED IN THE CONTRACTOR'S STAGING AREA. ALL DELIVERIES EQUIPMENT REFUELING, EQUIPMENT MAINTENANCE AND EQUIPMENT TRANSFER SHALL TAKE PLACE WITHIN THE CONTRACTOR'S STAGING
- THE CONTRACTOR WILL BE PERMITTED TO STORE EQUIPMENT AND MATERIALS ONLY AT THE LOCATIONS SHOWN. PARKED EQUIPMENT AND MATERIAL STOCKPILES SHALL NOT PENETRATE SURFACES DEFINED BY F.A.R. TITLE 14 PART 77 - OBJECTS AFFECTING NAVIGABLE AIRSPACE.
- ALL PAVEMENTS, DRIVES OR ANY OTHER AREAS UTILIZED BY THE CONTRACTOR FOR HAUL ROADS, STORAGE AREAS AND/OR STAGING AREAS SHALL BE MAINTAINED AND REPAIRED TO THE SAME CONDITION OR BETTER THAN THEY WERE PRIOR TO BEGINNING CONSTRUCTION, NO ADDITIONAL COMPENSATION WILL BE MADE TO THE CONTRACTOR FOR THIS WORK
- ALL VEHICLE AND EQUIPMENT OPERATORS USED BY THE CONTRACTOR SHALL BE PROPERLY TRAINED BY THE CONTRACTOR.

6. WILDLIFE MANAGEMENT

- THE CONTRACTOR SHALL NOTIFY AIRPORT OPERATIONS OR THE RESIDENT ENGINEER IF ANY WILDLIFE IS SEEN ENTERING THE AIRPORT.
- 2. CONTRACTOR ACCESS GATES SHALL REMAIN CLOSED WHEN THE CONTRACTOR IS NOT WORKING
- 3. THE CONTRACTOR SHALL DISPOSE OF ALL TRASH INCLUDING FOOD SCRAPS IN APPROVED CONTRACTOR PROVIDED CONTAINERS.
- 7. FOREIGN OBJECT DEBRIS (FOD) MANAGEMENT THE CONTRACTOR SHALL PICK UP ANY FOREIGN OBJECT DEBRIS (FOD) SEEN ON THE AIBEIELD PAVEMENTS.
- THE CONTRACTOR SHALL SECURE ALL LOOSE ITEMS FROM VEHICLES 2. PRIOR TO DRIVING ON AIRFIELD PAVEMENTS

8. HAZARDOUS MATERIALS (HAZMAT) MANAGEMENT 1. THE CONTRACTOR SHALL DEVELOP A HAZMAT MANAGEMENT PLAN AND KEEP COPIES ON THE JOBSITE OF MATERIAL SAFETY DATA SHEETS (MSDS) FOR ALL MATERIALS HANDLED ON THE JOBSITE.

9. NOTIFICATION OF CONSTRUCTION ACTIVITIES

- THE CONTRACTOR SHALL PROVIDE A 24 HOUR EMERGENCY CONTACT PERSON AND PHONE NUMBER.
- THE CONTRACTOR SHALL GIVE A MINIMUM OF 72 HOURS NOTICE TO AIRPORT OPERATIONS PRIOR TO CLOSING ANY PAVEMENTS SO THAT 2. PROPER NOTAMS MAY BE ISSUED BY THE AIRPORT
- FOR ANY EQUIPMENT USED BY THE CONTRACTOR WITH A HEIGHT 3. GREATER THAN 25', THE CONTRACTOR SHALL PROVIDE TO THE AIRPORT THE TYPE OF EQUIPMENT. TOTAL HEIGHT, AND LOCATION WHERE THE EQUIPMENT WILL BE USED. THE AIRPORT WILL SUBMIT FAA FORM 7460-1 TO THE FAA FOR AN AIRSPACE STUDY. NO EQUIPMENT WITH A HEIGHT GREATER THAN 25' SHALL BE USED UNTIL A DETERMINATION FROM FAA IS
- IN THE EVENT OF AN EMERGENCY, THE CONTRACTOR SHALL CALL 911. 4.
- CONTACTS FOR THIS PROJECT WILL BE DETERMINED AT THE 5. PRECONSTRUCTION MEETING PRIOR TO THE PROJECT START

10. INSPECTION REQUIREMENTS

- THE CONTRACTOR SHALL INSPECT THE JOBSITE DAILY TO ENSURE COMPLIANCE WITH THE CSPP. THE CHECKLIST FOUND IN APPENDIX 3 OF FAA AC 150/5370-2F MAY BE USED TO AID IN THE INSPECTIONS.
- THE CONTRACTOR SHALL ATTEND AN INSPECTION OF EACH PHASE WORK AREA PRIOR TO OPENING THE AREA TO AIRPORT OPERATIONS. 2.

11. UNDERGROUND UTILITIES 1. IT WILL BE NECESSARY FOR THE CONTRACTOR TO MAKE HIS OWN FIELD INVESTIGATION TO DETERMINE THE EXACT LOCATION OF THE UNDERGROURD UTILITIES AT CRITICAL POINTS. SEE SECTION 70-16 OF THE STANDARD SPECIFICATIONS AND SPECIAL PROVISIONS FOR SPECIFIC REQUIREMENTS. THE LOCATION OF UNDERGROUND UTILITIES AS INDICATED ON THE PLANS HAS BEEN OBTAINED FROM EXISTING RECORDS. NEITHER THE OWNER NOR THE ENGINEER ASSUMES ANY RESPONSIBILITY IN RESPECT TO THE ACCURACY, COMPLETENESS OR SUFFICIENCY OF THE INFORMATION. THERE IS NO GUARANTEE, EITHER EXPRESSED OR IMPLIED, THAT THE LOCATIONS, SIZE AND TYPE OF MATERIAL OF EXISTING UNDERGROUND UTILITIES AS INDICATED ARE REPRESENTATIVE OF THOSE TO BE ENCOUNTERED DURING CONSTRUCTION. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO DETERMINE THE ACTUAL LOCATION OF ALL SUCH FACILITIES, INCLUDING SERVICE CONNECTIONS TO UNDERGROUND UTILITIES. PRIOR TO CONSTRUCTION, THE CONTRACTOR SHALL NOTIFY THE UTILITY COMPANY/OWNER OF HIS OPERATIONAL PLANS. THE CONTRACTOR SHALL MAKE ARRANGEMENTS FOR DETAILED

INFORMATION AND ASSISTANCE IN LOCATING UTILITIES. IN THE EVENT AN UNEXPECTED UTILITY INTERFERENCE IS ENCOUNTERED DURING CONSTRUCTION THE CONTRACTOR SHALL IMMEDIATELY NOTIFY THE UTILITY COMPANY, THE OWNER AND THE ENGINEER. ANY SUCH MAINS AND/OR SERVICES DISTURBED BY THE CONTRACTOR'S OPERATIONS SHALL BE RESTORED IMMEDIATELY AT HIS EXPENSE TO THE SATISFACTION OF THE OWNER AND THE ENGINEER

- BEFORE INITIATING ANY DIGGING, DRILLING OR EXCAVATING ON THE AIRPORT PROPERTY, THE CONTRACTOR SHALL CALL J.U.L.I.E. AND CONTACT THE LOCAL FAA OFFICE TO ARRANGE FOR UTILITY LOCATES SEE SECTION 70-16 OF THE SPECIAL PROVISIONS FOR UTILITY CONTACT INFORMATION
- SHOULD A UTILITY COMPANY OR GOVERNMENT AGENCY BE UNABLE TO LOCATE FACILITIES, THE CONTRACTOR SHALL LOCATE THESE FACILITIES. PAYMENT FOR THIS LOCATION SHALL BE INCIDENTAL TO THE IMPROVEMENTS REQUIRING THE LOCATE.
- THE CONTRACTOR SHALL BE RESPONSIBLE FOR LOCATING ALL AIRPORT OWNED UTILITIES AND SHALL BE CONSIDERED INCIDENTAL TO THE CONTRACT

2.

12. PENALTIES 1. NONCOMPLIANCE BY THE CONTRACTOR WITH AIRPORT RULES AND REGULATIONS OR FAILURE TO COMPLY WITH THE AIRPORT'S APPROVED CSPP AND THE CONTRACTOR'S APPROVED SPCD MAY RESULT IN FINES AS ALLOWED BY LAW.

13. SPECIAL CONDITIONS

ADJACENT CONSTRUCTION MAY IMPACT THE OPERATIONS OF THE CONTRACTOR. SEE THE COORDINATION NOTES FOR ADDITIONAL INFORMATION.

14. RUNWAY AND TAXIWAY VISUAL AIDS 1. RUNWAY OR TAXIWAY CLOSURES ARE AS DETAILED IN THE CONSTRUCTION SAFETY AND PHASING PLAN FOR THIS PROJECT. IF ANY RUNWAY OR TAXIWAY CLOSURES ARE REQUESTED BY THE CONTRACTOR AND APPROVED BY THE AIRPORT, THE CONTRACTOR SHALL USE MARKING, LIGHTING AND SIGNS THAT FOLLOW THE REQUIREMENTS OF FAA AC 150/5370-2(LATEST VERSION).

15. HAZARD MARKING AND LIGHTING

- THE CONTRACTOR SHALL FURNISH, ERECT, AND MAINTAIN MARKINGS AND ASSOCIATED LIGHTING OF OPEN TRENCHES, EXCAVATIONS, TEMPORARY STOCKPILES, AND HIS/HER CONSTRUCTION EQUIPMENT
- ALL CONSTRUCTION EQUIPMENT SHALL BE FLAGGED AND/OR LIGHTED IN 2. ACCORDANCE WITH FAA ADVISORY CIRCULAR 150/5370-2(LATEST EDITION) AND 150/5210-5(LATEST EDITION) AT ALL TIMES WHILE OPERATING ON AIRPORT PROPERTY. THE MAXIMUM EQUIPMENT HEIGHT IS 25'
- BARRICADES SHALL BE PLACED AT THE LOCATIONS SHOWN ON THE CONSTRUCTION SAFETY AND PHASING PLAN SHEET OR AS DIRECTED BY THE RESIDENT ENGINEER. THE CONTRACTOR SHALL PLACE ALL BARRICADES AND CONSTRUCTION SETBACK LINES ITEMS AS SHOWN PRIOR TO INITIATING WORK IN EACH PHASE. ALL COSTS TO FURNISH, INSTALL, REPOSITION, AND MAINTAIN THESE ITEMS SHALL BE CONSIDERED INCIDENTAL TO THE PROJECT.
- THE CONTRACTOR SHALL INSPECT THE BARRICADES ONCE DURING EACH WORK DAY TO INSURE PROPER PLACEMENT AND PROPER OPERATION OF THE RED LIGHTS AND FLAG PLACEMENT.

16. PROTECTION

3.

CONTRACTOR PERSONNEL, VEHICLES, EQUIPMENT AND BARRICADES SHALL NOT BE ALLOWED WITHIN THE TAXIWAY OBJECT FREE AREA (TOFA) OF ACTIVE TAXIWAYS AND THE RUNWAY SAFETY AREA (RSA) OF ACTIVE RUNWAYS

17. OTHER LIMITATIONS ON CONSTRUCTION

- IF, DURING CONSTRUCTION, AN EMERGENCY IS DECLARED BY THE AIRPORT, THE CONTRACTOR SHALL IMMEDIATELY CLEAR THE PAVEMENT OF ALL VEHICLES, PERSONNEL AND EQUIPMENT.
- THE CONTRACTOR SHALL KEEP ALL TRUCKS, EQUIPMENT AND MATERIALS 2. OFF OF THE EXISTING APRONS, RUNWAYS AND TAXIWAYS OUTSIDE OF THE PROJECT LIMITS EXCEPT AS SHOWN OR WITH THE PRIOR PERMISSION OF THE RESIDENT ENGINEER. SHOULD THE CONTRACTOR TRACK ANY DEBRIS ONTO EXISTING PAVEMENTS, THIS DEBRIS SHALL BE REMOVED IMMEDIATELY WITH A PICK UP SWEEPER. A PICK UP SWEEPER SHALL BE REQUIRED TO BE ON SITE AND OPERATE DURING ALL CONSTRUCTION OPERATION WORKING HOURS
- THE CONTRACTOR SHALL PROVIDE WASTE RECEPTACLES THROUGHOUT THE WORK ZONE AND MAINTAIN SANITARY FACILITIES FOR EMPLOYEES TO USE. FACILITIES WITHIN THE HANGARS/AIRPORT BUILDINGS SHALL NOT BE LISED
- WORK PERFORMED BY THE CONTRACTOR OUTSIDE OF DAYLIGHT HOURS SHALL BE DONE UNDER SUFFICIENT ARTIFICAL AREA LIGHTING TO ALLOW FOR PROPER CONSTRUCTION METHODS AND INSPECTIONS. LIGHT SHALL CONSIST OF MOVEABLE POLE MOUNTED FLOODLIGHTS AND/OR SPOTLIGHTS OF SUFFICIENT NUMBER TO ILLUMINATE WORK AREA VEHICLE HEADLIGHTS WILL BE ALLOWED ONLY IN ADDITION TO OTHER LIGHTS MENTIONED ABOVE LIGHTING SHALL BE APPROVED BY THE ENGINEER AND SHALL NOT BE USED IF THEY AFFECT FLIGHT SAFETY.
- THE CONTRACTOR SHALL SUPPLY AND HAVE IN THEIR POSSESSION AT ALL TIMES AT LEAST ONE AIRPORT RADIO. IN THE EVENT THAT THE AIRPORT MANAGER NEEDS TO CONTACT THE CONTRACTOR DIRECTLY. THE

OTHERWISE SPECIFIED.

6.















SURVEY BOOK # BOOK # BOOK # REVISIONS NUMBER BY DATE PY DATE P	IL. CONTRACT: DK065 IL. LETTING ITEM: 01A IL. PROJECT: DKB-5118 S.B.G. PROJECT: 3-17-SBGP-TBD		
NUMBER BY DATE BY DATE BY DATE Date Date Design Design Design Jone Design Jone Design Jone Date Jone Date Jone Jone Zate Jone Zate Jone Zate Jo	SURVEY BOOK	# BOOK#	
Consultance of the control of the c	NUMBER	BY	DATE
Construction of the const			
DEKATE PLAN - 2 CONSULTING ENGINE CONSULTING ENGINE CONSULTING			
DEKATE PLAN - 2 Trins BAR IS EQUAL TO 2" AT FULL SCALE (34X22): THIS BAR IS EQUAL TO 2" AT FULL SCALE (34X22): DEKATE TAXLOR MUNICIDAL AIRPORT DEKATE TAXLOR MUNICIDAL AIRPORT DEKATE INNOIS CAMPBORT DEKATE FENCING, PHASE 1 DEKATE FENCING 1 DEKATE FENCING 1 DET			
THIS BAR IS EQUAL TO 2" AT FULL SCALE (34X22).	0	1	2
BEKALB TAYLOR MUNICIPAL AIRPORT CRAMEDRATIC AIRPORT CRAMEDRATIC AIRPORT CRAMEDRATERS CAMPANA CRAMEDRATERS CAMPANA CRAMEDRATERS CAMPANA CRAMEDRATERS CAMPANA CRAMEDRATERS CAMPANA CRAMEDRATERS CAMPANA CRAMEDRATERS CAMPANA CAMPANA CRAMEDRATERS CAMPANA CAMPANA CAMPANA CRAMEDRATERS CAMPANA	THIS E AT FL	3AR IS EQUAL JLL SCALE (34	TO 2" X22).
DESIGN BY: ABM DRAWN BY: JRO CHECKED BY: AB APPROVED BY APPROVED BY: AB APPROVED BY APPROVED BY APPROVED BY APPROVED BY APPROVED B	DEKALB TAYLOR MUNICIPAL AIRPORT DEKALB, ILLINOIS	KEPLACE PEKIMETEK FENCING, PHASE 1	ELECTRIC GATE PLAN - 2
DESIGN BY: ABM DRAWN BY: JRO CHECKED BY: AB APPROVED BY: ABM DATE: 3/1/2024 JOB No: 23005748.00		CONSULTING ENGINEERS License No. 184-000613	DI INCIPAL A Dekalb Taylor Municipal Airport
DHAWN BY: JRO CHECKED BY: AB APPROVED BY: ABM DATE: 3/1/2024 JOB No: 23005748.00	DESIGN BY:		ABM
APPROVED BY: ABM DATE: 3/1/2024 JOB No: 23005748.00	DHAWN BY: CHECKED B	Y:	JRO
DATE: 3/1/2024 JOB No: 23005748.00	APPROVED I	BY:	ABM
EINIAI	DATE:	3/1/	2024
	FINAL		



Sign.jpg ogo-black.jpg

IL. CONTRACT: DK065 IL. LETTING ITEM: 01A IL. PROJECT: DKB-5118 S.B.G. PROJECT: 3-17-SBGP-TBD		
SURVEY BOOK	K# BOOK# REVISIONS	
NUMBER	BY	DATE
0 THIS I AT FU	1 BAR IS EQUAL JLL SCALE (34	2 TO 2" X22).
DEKALB TAYLOR MUNICIPAL AIRPORT DEKALB, ILLINOIS	REPLACE PERIMETER FENCING, PHASE 1	CANTILEVER GATE DETAILS
Cosynghic CMT Cosynghic CMT. Inc.	CONSULING ENGINEERS License No. 184-000613	DITING A
DESIGN BY:		ABM
CHECKED B	Y:	JHU DKP
APPROVED	BY:	ABM
DATE:	3/1	/2024
JOB NO:	FINAL	5748.UU
SHEET 1	11 OF 1	6 SHEETS









FENCE POST/GATE POST REMOVAL AND REPLACEMENT IN PCC PAVEMENT

N.T.S.

NOTES:

- 1. PCC PAVEMENT TO BE REMOVED FULL DEPTH
- 2. H: BITUMINOUS BASE OR AGGREGATE BASE COURSE AND/OR SUBGRADE TO BE REMOVED SUCH THAT THE DEPTH "H" IS A MINIMUM OF 6 INCHES. REPLACE WITH ITEM 208 AGGREGATE.
- 3. NEW FENCE SHALL REUSE EXISTING POST HOLES AS FIELD CONDITIONS ALLOW. SEE DETAIL FOR NEW FENCE POST FOUNDATION IN EXISTING PCC PAVEMENT.
- 4. COSTS OF PAVEMENT AND FOUNDATION REMOVAL, NEW PAVEMENT, SAW CUTTING, CLEANUP AND DISPOSAL, SHALL BE CONSIDERED INCIDENTAL TO AR162900 REMOVE CLASS E FENCE, AR162905 REMOVE GATE AND AR162908 REMOVE ELECTRIC GATE.
- 5. SAME DETAIL IS TO BE USED IF NEW POST HOLES ARE REQUIRED IN EXISTING PCC PAVEMENT, NOT INCLUDING THE REMOVAL PORTION (COST INCIDENTAL TO CONTRACT).
- 6. CONTRACTOR CAN PROPOSE ALTERNATIVE METHOD(S) FOR FENCE POST/GATE POST REMOVAL FOR REVIEW AND APPROVAL BY THE RESIDENT ENGINEER.



FENCE POST/GATE POST REMOVAL AND REPLACEMENT IN HMA PAVEMENT

N.T.S.

NOTES:

- 1. HMA PAVEMENT TO BE REMOVED FULL DEPTH.
- 2. BASE COURSE AND/OR SUBGRADE TO BE REMOVED SUCH THAT THE DEPTH "H" IS A MINIMUM OF 6 INCHES.
- 3. NEW FENCE SHALL REUSE EXISTING POST HOLES AS FIELD CONDITIONS ALLOW. SEE DETAIL FOR NEW FENCE POST FOUNDATION IN EXISTING HMA PAVEMENT.
- 4. COSTS OF PAVEMENT AND FOUNDATION REMOVAL, NEW PAVEMENT, SAW CUTTING, CLEANUP AND DISPOSAL, SHALL BE CONSIDERED INCIDENTAL TO AR162900 REMOVE CLASS E FENCE, AR162905 REMOVE GATE AND AR162908 REMOVE ELECTRIC GATE.
- 5. AT THE CONTRACTOR'S OPTION AND AT NO ADDITIONAL COST TO THE CONTRACT, THE CONTRACTOR MAY REMOVE A "STRIP" OF ASPHALT PAVEMENT ALONG THE FENCELINE, TO BE REPLACED IN KIND AFTER FENCELINE REMOVAL AND REPLACEMENT.
- 6. SAME DETAIL IS TO BE USED IF NEW POST HOLES ARE REQUIRED IN EXISTING HMA PAVEMENT, NOT INCLUDING THE REMOVAL PORTION (COST INCIDENTAL TO CONTRACT).



NOTES:





IL. CONTRACT: DK065 IL. LETTING ITEM: 01A IL. PROJECT: DKB-5118 S.B.G. PROJECT: 3-17-SBGP-TBD			
SURVEY BOO	K # BOO	OK#	
NUMBER	BY		DATE
		_	
0	1		2
THIS AT F	BAR IS EC	UAL TO E (34X22	2" 2).
DEKALB TAYLOR MUNICIPAL AIRPORT DEKALB, ILLINOIS	REPLACE PERIMETER FENCING, PHASE 1		ELECTRIC GATE DETAILS
CAMPERT CATILY, INC.	CONSULTING ENGINEERS License No. 184-000613	× NMEL	DEKALB TAYLOR MUNICIPAL AIRPORT
DESIGN BY:		AB	М
DRAWN BY:	Y:	JR	0
APPROVED BY: ABM			
DATE:		3/1/20	24
JUB NO: 23005748.00			
SHEET	15 OF	16	SHEETS

STORM WATER POLLUTION PREVENTION PLAN

THE FOLLOWING PLAN IS ESTABLISHED AND INCORPORATED IN THE PROJECT TO DIRECT THE CONTRACTOR IN THE PLACEMENT OF TEMPORARY EROSION CONTROL SYSTEMS AND TO PROVIDE A STORM WATER POLLUTION PREVENTION PLAN FOR COMPLIANCI WITH NPDES.

THE PURPOSE OF THIS PLAN IS TO MINIMIZE FROSION WITHIN THE CONSTRUCTION SITE AND TO LIMIT SEDIMENTS FROM LEAVING THE SITE BY UTILIZING PROPER TEMPORARY EROSION CONTROL SYSTEMS AND PROVIDING GROUND COVER WITHIN REASONABLE AMOUNT OF TIME.

CERTAIN EROSION CONTROL FACILITIES SHALL BE INSTALLED BY THE CONTRACTOR AT THE BEGINNING OF CONSTRUCTION OTHER ITEMS SHALL BE INSTALLED BY THE CONTRACTOR AS DIRECTED BY THE ENGINEER ON A CASE BY CASE SITUATION DEPENDING ON THE CONTRACTOR'S SEQUENCE OF ACTIVITIES. TIME OF YEAR, AND EXPECTED WEATHER CONDITIONS

THE CONTRACTOR SHALL INSTALL PERMANENT EROSION CONTROL SYSTEMS AND SEEDING WITHIN A TIMEFRAME SPECIFIED HEREIN AND AS DIRECTED BY THE ENGINEER, THEREFORE MINIMIZING THE AMOUNT OF AREA SUSCEPTIBLE TO EROSION AND BEDUCING THE AMOUNT OF TEMPORARY SEEDING. WHICH WILL BE THE CONTRACTOR'S COST. THE ENGINEER WILL DETERMINE IF ANY TEMPORARY EROSION CONTROL SYSTEMS SHOWN IN THE PLAN CAN BE DELETED AND IF ANY ADDITIONAL TEMPORARY EROSION CONTROL SYSTEMS, WHICH ARE NOT INCLUDED IN THIS PLAN, SHALL BE ADDED. THE CONTRACTOR SHALL PERFORM ALL WORK AS DIRECTED BY THE ENGINEER AND AS SHOWN ON THE PLANS.

SITE DESCRIPTION

THE FOLLOWING IS A DESCRIPTION OF THE CONSTRUCTION ACTIVITY WHICH IS THE SUBJECT OF THIS PLAN:

THIS PROJECT CONSISTS OF CONSTRUCTING A NEW 10' SECURITY FENCE AT DEKALB TAYLOR MUNICIPAL AIRPORT

THE FOLLOWING IS A DESCRIPTION OF THE INTENDED SEQUENCE OF MAJOR ACTIVITIES WHICH WILL DISTURB SOILS FOR MAJOR PORTIONS OF THE CONSTRUCTION SITE, SUCH AS EXCAVATION AND GRADING

1 COMPLETE CLEARING AND GRUBBING

- REMOVE EXISTING FENCE
- 3. INSTALL THE NEW FENCE POSTS.
- 4. INSTALL NEW FENCE IMPROVEMENTS
- 5. FINAL GRADING AND OTHER MISCELLANEOUS ITEMS.
- 6. PLACEMENT OF PERMANENT EROSION CONTROL, SUCH AS SEEDING AND MULCHING.

AREA OF CONSTRUCTION SITE

THE TOTAL AREA OF THE CONSTRUCTION SITE IS ESTIMATED TO BE 1.5 ACRES WHICH WILL BE DISTURBED BY EXCAVATION, GRADING AND OTHER ACTIVITIES.

OTHER REPORTS, STUDIES AND PLANS WHICH AID IN THE DEVELOPMENT OF THE STORM WATER POLLUTION PREVENTION PLAN AS REFERENCED DOCUMENTS:

- 1. INFORMATION OF THE SOILS AND TERRAIN WITHIN THE SITE WAS OBTAINED FROM TOPOGRAPHIC SURVEYS AND SOIL BORINGS THAT WERE UTILIZED FOR THE DEVELOPMENT OF THE PROPOSED TEMPORARY EROSION CONTROL SYSTEMS.
- 2. PROJECT PLAN DOCUMENTS, SPECIFICATION AND SPECIAL PROVISIONS, AND PLAN DRAWINGS INDICATING DRAINAGE PATTERNS AND APPROXIMATE SLOPES ANTICIPATED AFTER GRADING ACTIVITIES WERE UTILIZED FOR THE PROPOSED PLACEMENT OF THE TEMPORARY EROSION CONTROL SYSTEMS.

DRAINAGE TRIBUTARIES AND SENSITIVE AREAS RECEIVING RUNOFF FROM THIS CONSTRUCTION SITE

THE CONSTRUCTION SITE DRAINS INTO A STORM SEWER SYSTEM

SEDIMENTATION AND EROSION CONTROL NOTES

THE SOIL EROSION AND SEDIMENT CONTROL PRACTICES WILL BE INSPECTED WEEKLY AND AFTER 1/2 INCH OF RAIN OR MORE BY THE RESIDENT ENGINEER

ALL SOIL EROSION AND SEDIMENT CONTROL PRACTICES ARE REFERENCED FROM THE ILLINOIS URBAN MANUAL, UNLESS OTHERWISE STATED

THE DRAWINGS SPECIFICATIONS AND SPECIAL PROVISIONS WILL ENSURE THAT EXISTING VEGETATION IS PRESERVED WHERE ATTAINABLE AND DISTURBED PORTIONS OF THE SITE WILL BE STABILIZED. STABILIZATION PRACTICES INCLUDE SEEDING AND MULCHING AS DIRECTED BY THE ENGINEER. STABILIZATION MEASURES SHALL BE INITIATED AS SOON AS POSSIBLE IN PORTIONS OF THE SITE WHERE CONSTRUCTION ACTIVITIES HAVE TEMPORARILY OR PERMANENTLY CEASED, BUT IN NO CASE MORE THAN 7 DAYS AFTER THE CONSTRUCTION ACTIVITY IN THAT PORTION OF THE SITE HAS TEMPORARILY OR PERMANENTLY CEASED

AS SOON AS REASONABLE ACCESS IS AVAILABLE TO ALL LOCATIONS WHERE WATER DRAINS AWAY FROM THE PROJECT, INLET ECTION AND PERIMETER SILT FENCE SHALL BE INSTALLED AS CALLED OUT IN THE PLANS OR AS DIRECTED BY THE ENGINEER.

THIS PLAN HAS BEEN PREPARED TO COMPLY WITH THE PROVISIONS OF THE NPDES PERMIT NUMBER ILR10, ISSUED BY THE ILLINOIS ENVIRONMENTAL PROTECTION AGENCY FOR STORM WATER DISCHARGES FROM CONSTRUCTION SITE ACTIVITIES

DESCRIPTION OF STABILIZATION PRACTICES DURING CONSTRUCTION:

DURING CONSTRUCTION AREAS OUTSIDE THE CONSTRUCTION LIMITS AS OUTUINED PREVIOUSLY HEREIN SHALL BE PROTECTED. THE CONTRACTOR SHALL NOT USE THIS AREA FOR STAGING (EXCEPT AS DESCRIBED ON THE PLANS AND DIRECTED BY THE ENGINEER), PARKING OF VEHICLES OR CONSTRUCTION EQUIPMENT, STORAGE OF MATERIALS, OR OTHER CONSTRUCTION **BELATED ACTIVITIES.**

- WITHIN THE CONSTRUCTION LIMITS, AREAS WHICH MAY BE SUSCEPTIBLE TO EROSION AS DETERMINED BY THE ENGINEER SHALL REMAIN UNDISTURBED UNTIL FULL SCALE CONSTRUCTION IS UNDERWAY TO PREVENT UNNECESSARY SOIL EROSION
- 2. EARTH STOCKPILES SHALL BE TEMPORARILY SEEDED, AT THE CONTRACTORS EXPENSE, IF THEY ARE TO REMAIN UNUSED FOR MORE THAN FOURTEEN DAYS.
- 3. AS CONSTRUCTION PROCEEDS, THE CONTRACTOR SHALL INSTITUTE THE FOLLOWING AS DIRECTED BY THE ENGINEER:
- A. PLACE TEMPORARY EROSION CONTROL FACILITIES AT LOCATIONS SHOWN ON THE PLANS.
- B. EXCAVATED AREAS AND EMBANKMENT AREAS SHALL BE PERMANENTLY SEEDED IMMEDIATELY AFTER FINAL GRADING. IF NOT, THEY SHALL BE TEMPORARILY SEEDED, AT THE CONTRACTOR'S COST, IF NO CONSTRUCTION ACTIVITY IN THE AREA IS PLANNED FOR SEVEN DAYS.
- 4. CONSTRUCTION EQUIPMENT SHALL BE STORED AND FUELED ONLY AT DESIGNATED LOCATIONS, ALL NECESSARY MEASURES SHALL BE TAKEN TO CONTAIN ANY FUEL OR POLILITANT IN ACCORDANCE WITH FPA WATER QUALITY REGULATIONS. LEAKING EQUIPMENT OR SUPPLIES SHALL BE IMMEDIATELY REPAIRED OR REMOVED FROM THE SITE

- 5. SEDIMENT COLLECTED DUBING CONSTRUCTION OF THE VARIOUS TEMPORARY EROSION CONTROL SYSTEMS SHALL BE DISPOSED OF ON SITE ON A REGULAR BASIS AS DIRECTED BY THE ENGINEER. THE COST OF THIS MAINTENANCE SHALL BE INCLUDED IN THE UNIT BID PRICE FOR UNCLASSIFIED EXCAVATION AND EROSION CONTROL ITEMS.
- THE TEMPORARY FROSION CONTROL SYSTEMS SHALL BE REMOVED AS DIRECTED BY THE ENGINEER AFTER USE IS NO FOR VARIOUS TEMPORARY EROSION CONTROL PAY ITEMS.

DESCRIPTION OF STRUCTURAL PRACTICES AFTER FINAL GRADING:

TEMPORARY EROSION CONTROL SYSTEMS SHALL BE LEFT IN PLACE WITH PROPER MAINTENANCE UNTIL PERMANENT EROSION CONTROL IS IN PLACE AND WORKING PROPERLY AND ALL PROPOSED TURF AREAS ARE SEEDED AND ESTABLISHED.

ONCE PERMANENT EROSION CONTROL SYSTEMS AS PROPOSED IN THE PLANS ARE FUNCTIONAL AND ESTABLISHED, TEMPORARY ITEMS SHALL BE REMOVED, CLEANED UP, AND DISTURBED TURF RESEEDED.

MAINTENANCE AFTER CONSTRUCTION

CONSTRUCTION IS COMPLETE AFTER FINAL ACCEPTANCE BY THE ILLINOIS DIVISION OF AERONAUTICS. MAINTENANCE UP TO THIS DATE WILL BE REQUIRED BY THE CONTRACTOR.

CONTRACTORS

THE STORM WATER POLLUTION PREVENTION PLAN MUST CLEARLY IDENTIFY FOR EACH MEASURE IDENTIFIED IN THE PLAN, THE CONTRACTOR(S) OR SUBCONTRACTOR(S) THAT WILL IMPLEMENT THE MEASURE. ALL CONTRACTORS AND SUBCONTRACTORS IDENTIFIED IN THE PLAN MUST SIGN A COPY OF THE CERTIFICATION STATEMENT IN PARAGRAPH 2 BELOW IN ACCORDANCE WITH PART VI.G (SIGNATORY REQUIREMENTS) OF THIS PERMIT. ALL CERTIFICATIONS MUST BE INCLUDED IN THE STORM WATER POLLUTION PREVENTION PLAN EXCEPT FOR OWNERS THAT ARE ACTING AS CONTRACTOR

CERTIFICATION STATEMENT. ALL CONTRACTORS AND SUBCONTRACTORS IDENTIFIED IN A STORM WATER POLLUTION PREVENTION PLAN IN ACCORDANCE WITH PARAGRAPH 1 ABOVE SHALL SIGN A COPY OF THE FOLLOWING CERTIFICATION STATEMENT BEFORE CONDUCTING ANY PROFESSIONAL SERVICE AT THE SITE IDENTIFIED IN THE STORM WATER 2. POLLUTION PREVENTION PLAN

"I CERTIFY UNDER PENALTY OF LAW THAT I UNDERSTAND THE TERMS AND CONDITIONS OF THE GENERAL NATIONAL POLITUTANT DISCHARGE FLIMINATION SYSTEM (NPDES) PERMIT (1) R10) THAT AUTHORIZES THE STORM WATER DISCHARGES ASSOCIATED WITH INDUSTRIAL ACTIVITY FROM THE CONSTRUCTION SITE IDENTIFIED AS PART OF THIS CERTIFICATION

THE CERTIFICATION MUST INCLUDE THE NAME AND TITLE OF THE PERSON PROVIDING THE SIGNATURE IN ACCORDANCE WITH PART VI.G OF THIS PERMIT: THE NAME, ADDRESS AND TELEPHONE NUMBER OF THE CONTRACTING FIRM; THE ADDRESS (OR OTHER IDENTIFYING DESCRIPTION) OF THE SITE: AND THE DATE THE CERTIFICATION IS MADE.

CONTRACTOR CERTIFICATION STATEMENT

THIS CERTIFICATION STATEMENT IS A PART OF THE STORM WATER POLLUTION PREVENTION PLAN FOR THE PROJECT DESCRIBED BELOW IN ACCORDANCE WITH NPDES PERMIT NO. ILR10 ISSUED BY THE ILLINOIS ENVIRONMENTAL PROTECTION AGENC

PROJECT INFORMATION

COUNTY: DEKALB

ROUTE: DEKALB TAYLOR MUNICIPAL AIRPORT MARKED: REPLACE PERIMETER FENCE - PHASE 1

PROJECT NUMBER: DKB-5118 SECTION: 17, 18 AND 19

CONTRACT NUMBER: 3-17-SBGP-XXX

I CERTIFY UNDER PENALTY OF LAW THAT I UNDERSTAND THE TERMS AND CONDITIONS OF THE GENERAL NATIONAL POLLUTION DISCHARGE ELIMINATION SYSTEM (NPDES) PERMIT (ILR10) THAT AUTHORIZES THE STORM WATER DISCHARGES ASSOCIATED WITH INDUSTRIAL ACTIVITY FROM THE CONSTRUCTION SITE IDENTIFIED AS PART OF THIS CERTIFICATION.

SIGNATURE:	DATE:

NAME OF FIRM

STREET ADDRESS:

CITY, STATE, ZIP

PHONE NUMBER

THE INFORMATION WITHIN THIS BOX SHALL BE COMPLETED BY THE CONTRACTOR AFTER THE AWARD OF THE CONTRACT TO OBTAIN THE REQUIRED NPDES PERMIT FROM IEPA. COMPLETION OF THIS IS A CONTRACT REQUIREMENT

ADDITIONAL NOTES

- 1 LINEESS OTHERWISE INDICATED ALL VEGETATIVE AND STRUCTURAL EROSION AND SEDIMENT CONTROL PRACTICES SHALL BE CONSTRUCTED ACCORDING TO MINIMUM STANDARDS AND SPECIFICATIONS IN THE ILLINOIS URBAN MANUAL CURRENT EDITION FOUND AT ILLINOISMANUAL.ORG
- 2 WINTER SHUTDOWN SHALL BE ADDRESSED FABLY IN THE FALL GROWING SEASON SO THAT SLOPES AND OTHER BARE EARTH AREAS MAY BE STABILIZED WITH TEMPORARY AND OR PERMANENT VEGETATIVE COVER FOR PROPER EROSION AND SEDIMENT CONTROL. TEMPORARY SEEDING (156) SHALL BE PAID FOR ONLY WHEN NEEDED FOR WINTERIZATION OF THE SITE AT THE LOCATIONS NOTED BY THE ENGINEER. ALL OTHER APPLICATIONS OF TEMPORARY SEED NEEDED FOR COMPLIANCE FOR THE NPDES PERMIT SHALL BE INCIDENTAL TO THE CONTRACT.

	I
LIGHT-DUTY HYDRAULIC	A

F NUTRIE NITRO PHOSPHORL POTASSIU

	SEED TABLE	=	
CLASS - TYPE	SEED MIXTURE	RATE (LB/ACRE)	APPLICATION WINDOW
IDOT AERONAUTICS (PERMANENT SEEDING)	TALL FESCUE ANNUAL RYEGRASS RED FESCUE HARD FESCUE	60 20 30 30	APRIL 1 THRU JUNE 1 SEPTEMBER 1 THRU NOVEMBER 1
TEMPORARY EROSION CONTROL SEEDING I	OATS	100 LB/ACRE	MARCH 1 THRU JULY 31 *
TEMPORARY EROSION CONTROL SEEDING II	WINTER WHEAT	100 LB/ACRE	AUGUST 1 THRU NOVEMBER 15*

HYDRAULIC MULCH, AS NECESSARY, TO MINIMIZE EROSION.

AD2006		
	10'	Min 🚽
10 ⁰ Min		
WIL POLY		6" WIRE STAP (ANCHOR EVEN
	PLAN	VIEW
etters 6"	Min. Height —	
•		0



MULCH TYPE

APPLIED PER MANUFACTURER'S RECOMMENDATION (2000 LB/ACRE MINIMUM)

ERTILIZER MIX		
NT	PLAT (LB/ACRE)	
EN	90	
IS (P205)	90	
d (K20)	90	

* NOTE: WHEN TEMPORARY SEEDING CAN NOT BE COMPLETED DUE TO APPLICATION WINDOW RESTRICTIONS CONTRACTOR SHALL APPLY A LIGHT-DUTY HYDRAULIC MULCH (1000 LB/ACRE MINIMUM) IN ITS PLACE. CONTRACTOR SHALL REAPPLY

