LETTING ITEM NO. 07A IDOT LETTING APRIL 26, 2024

WAUKEGAN PORT DISTRICT WAUKEGAN, LAKE COUNTY, ILLINOIS

CONSTRUCTION PLANS FOR WAUKEGAN NATIONAL AIRPORT

REHABILITATE MAIN PARKING LOT

ILLINOIS PROJECT: UGN-5119 S.B.G. PROJECT: 3-17-SBGP-TBD

MARCH 1, 2024



WISCONSIN

LAKE

ILLINOIS

PROJECT

LOCATION

SITE PLAN

	811 Know	what's below. I ll before you dig.	J.U.L.I.E. JOINT UTILITY LOCAT INFORMATION FOR EX www.illinois1call.com	ING XCAVATORS
THE LOCATION, SIZE AND TYPE OF MATERIAL OF EXISTING UND UTILITIES INDICATED ON THE PLANS IS NOT REPRESENTED AS BEIN SUFFICIENT OR COMPLETE IT SHALL BE THE CONTRACTOR'S RESP DETERMINE ACTUAL LOCATIONS OF ALL SUCH FACILITIES, INCLUE CONTRACTOR SHALL NOTIFY UTILITY COMPANIES OF HIS OPERAT OBTAIN FROM RESPECTIVE UTILITY COMPANIES OF HIS OPERAT OBTAIN FROM RESPECTIVE UTILITY COMPANIES DETAILED INFOR ASSISTANCE RELATIVE TO THE LOCATION OF THEIR FACILITIES AND SCHEDULE OF THE COMPANIES FOR REMOVAL OR ADJUSTMENT WH IN THE EVENT AN UNEXPECTED UTILITY INTERFERENCE IS ENCOUN CONSTRUCTION, THE CONTRACTOR SHALL IMMEDIATELY NOTIFY COMPANY OF JURISDICTION AND THE ONE-CAN UNTIL'Y OR SETM. SHALL ALS DE EIMMEDIATELY NOTIFIED. ANY SUCH UTIL'TY ORS RESTORED TO SERVICE AT ONCE AND PAID FOR BY THE CONTRAC ADDITIONAL COST TO THE CONTRACT.				AGROUND 3 ACCURATE, NSIBILITY TO VG SERVICE CTION, THE NAL PLANS, IATION AND THE WORKING RE REQUIRED. RED DURING HE UTILITY HE ENGINEER CES SHALL BE TOR AT NO
	CALL	J.U.L.I.E. FOR UTILI	TY INFORMATION AT 81	1.
		AUKEGAN ATIONAL IRPORT	WAUKEGAN NATI WAUKEGAN POR 2601 Plane Rest D Waukegan, Illinois Telephone: 847.24 Fax: 847.244.3813	DIAL AIRPORT DISTRICT Vrive 60087 4.0055
	APPROVED BY		Mip Des geneer Manager	
			MARCH 1	0004

WA080 TOTAL SHEETS = 11



CALL J.U.L.I.E. BEFORE EXCAVATING AT 811 WAUKEGAN NATIONAL AIRPORT

TOWNSHIP: 46 NORTH RANGE: 12 EAST SECTION: 31 AND 32 COUNTY: LAKE TOWNSHIP: BENTON

(Copyright CMT, Inc.	22004938.00
CRAWFORD, MURPHY & TILI CONSULTING ENGINEERS License No. 184-000613	LY, INC.	
	A	/
SUBMITTED BY	CBAIG LOUDEN, P.E.	
DATE	MARCH 1	2024

INDEX TO SHEETS

- 1 COVER SHEET
- 2 INDEX TO SHEETS / SUMMARY OF QUANTITIES
- 3 SITE PLAN AND PROJECT CONTROL PLAN
- 4 CONSTRUCTION ACTIVITY PLAN
- 5 CONSTRUCTION ACTIVITY PLAN NOTES
- 6 CONSTRUCTION ACTIVITY PLAN DETAILS
- 7 EXISTING CONDITIONS / PROPOSED REMOVALS
- 8 PROPOSED IMPROVEMENTS
- 9 TYPICAL SECTIONS
- 10 EROSION CONTROL NOTES AND DETAILS
- 11 GEOTECHNICAL ENGINEERING INFORMATION
- 12 LIGHTING PLAN ADDITIVE ALTERNATE NO. 1
- 13 ELECTRICAL DETAILS ADDITIVE ALTERNATE NO. 1

SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES						
	BASE BID					
ITEM	DESCRIPTION	UNIT	ESTIMATED QUANTITY	RECORD QUANTITY		
AR150510	ENGINEER'S FIELD OFFICE	L SUM	1			
AR150520	MOBILIZATION	L SUM	1			
AR152511	SUBGRADE REPAIR	SQ YD	270			
AR156520	INLET PROTECTION	EACH	1			
AR201663	SAND MIX CRACK REPAIR	FOOT	575			
AR401610	BITUMINOUS SURFACE COURSE	TON	615			
AR401650	BITUMINOUS PAVEMENT MILLING	SQ YD	5,260			
AR401916	REM & REP BIT PAVEMENT - TYPE B	SQ YD	520			
AR501600	PCC SIDEWALK	SQ FT	190			
AR501690	PCC SIDEWALK REMOVAL	SQ FT	190			
AR603510	BITUMINOUS TACK COAT	GALLON	635			
AR620520	PAVEMENT MARKING-WATERBORNE	SQ FT	1,655			
AR620900	PAVEMENT MARKING REMOVAL	SQ FT	40			
AR754900	REMOVE CONCRETE CURB	FOOT	145			
AR754920	REPLACE CONCRETE CURB	FOOT	145			
	ADDITIVE ALTE	RNATE #1				
ITEM	DESCRIPTION	UNIT	ESTIMATED QUANTITY	RECORD QUANTITY		

ITEM	DESCRIPTION	UNIT	ESTIMATED QUANTITY
AS110202	2" PVC DUCT - DIRECT BURY	FOOT	20
AS110900	REMOVE DUCT	FOOT	20
AS401916	REM & REP BIT PAVEMENT - TYPE B	SQ YD	24
AS800082	2-1/C #10 XLP-USE, 1/C #10 GND	FOOT	575
AS800083	2-1/C #8 XLP-USE, 1/C #10 GND	FOOT	875
AS910100	ROADWAY LIGHT POLE	EACH	6
AS910900	REMOVE ROADWAY LIGHT POLE	EACH	6

IL PROJECT: UGN-5119 IL LETTING ITEM: 07A IL CONTRACT: WA080
REHABILITATE MAIN PARKING LOT
FINAL MARCH 1, 2024
OWNER
WAUKEGAN NATIONAL AIRPORT
MARK DATE DESCRIPTION
CMT PROJECT NO: 22004938.00
DESIGNED BY: LB
DRAWN BY: JRO
CHECKED BY: CAL
COPYRIGHT:
INDEX TO SHEETS/ SUMMARY OF QUANTITIES
SHEET 2 OF 13



- IN A SATISFACTORY CONDITION.
- 3. THE CONTRACTOR SHALL TAKE THE NECESSARY PRECAUTIONS TO PROTECT

(ILLINOIS STATE PLANE, NAD 83 / NAVD 88)				
POINT	DESCRIPTION	NORTHING	EASTING	ELEVATIO
CP-1	IRON ROD IN TURF	2095116.747	1109696.413	-
CP-3	CROSS CUT ON CURB	2095293.275	1109912.215	-
UGN-E	PACS	2095587.450	1109729.570	705.070





SUGGESTED SEQUENCE OF CONSTRUCTION (EACH WORK AREA)

LOW PROFILE BARRICADES

CONTRACTOR'S HAUL ROUTE

AIRCRAFT MOVEMENT AREA

- PLACE TRAFFIC CONTROL
- LOCATE ALL UTILITIES.
- COMPLETE REMOVAL ITEMS, ADJUSTMENT ITEMS AND MILLING.
- CLEAN PAVEMENT.
- REMOVE BARRICADES AND OPEN PAVEMENT TO VEHICLES.

- INCIDENTAL TO THE CONTRACT
- DURING CONSTRUCTION OPERATION.
- PHASE 1 AND 2 SHALL NOT BE COMPLETED AT THE SAME TIME FIRST COAT OF PAVEMENT MARKING SHALL BE APPLIED AT THE END OF EACH PHASE. IN ORDER TO OPEN
- 6. CONTRACTOR TO MAINTAIN PEDESTRIAN ACCESS TO ALL BUILDINGS AT ALL TIMES.
- 7. WORK AREAS 1 AND 2 CANNOT BE COMBINED WITHOUT AUTHORIZATION FROM AIRPORT MANAGEMENT.
- 8. CONTRACTOR SHALL PROTECT OPEN EXCAVATIONS FROM PEDESTRIANS AT ALL TIMES.

INT	APPROXIMATE ELEVATION OF GROUND (FT)	ANTICIPATED EQUIPMENT AND HEIGHT			
1	708	SEMI/DUMP TRUCK - 25'			
2	708	SEMI/DUMP TRUCK - 25'			
3	708	SEMI/DUMP TRUCK - 25'			
1	708	SEMI/DUMP TRUCK - 25'			
5	708	SEMI/DUMP TRUCK - 25'			
6	708	SEMI/DUMP TRUCK - 25'			
	IT SHALL BE CONTRACTOR'S RESPONSIBILI AIRPORT-OWNED UTILITIES WITHIN THE CO ELECTRICAL CABLES, STORM SEWER, DRAI SANITARY SEWER AND WATERMAIN				
THE CONTRACTOR SHALL BE IN CONFORMANC SPECIFICATIONS FOR CONSTRUCTION OF AIR TRANSPORTATION, DIVISION OF AERONAUTICS PROVISIONS SECTIONS 40-05 MAINTENANCE C THE WORK TO TRAFFIC, 70-16 CONTRACTORS FACILITIES OF OTHERS, 70-25 CONTRACTORS CONSTRUCTION AND 80-13 WORK AREA, STOR					



GENERAL

- THE CONTRACTOR AND ALL SUBCONTRACTORS SHALL FOLLOW THE REQUIREMENTS OF THE AIRPORT'S APPROVED CONSTRUCTION SAFETY AND PHASING PLAN (CSPP), FAA AC 150/5370-2G OR LATEST EDITION, AND ALL PORT SAFETY AND SECURITY REQUIREMENTS.
- PRIOR TO THE NOTICE TO PROCEED. THE CONTRACTOR SHALL SUBMIT TO 2. THE AIRPORT THROUGH THE RESIDENT ENGINEER, FOR APPROVAL A SAFETY PLAN COMPLIANCE DOCUMENT (SPCD) IN ACCORDANCE WITH FAA AC 150/5370-2G OR LATEST EDITION. NO CONSTRUCTION ACTIVITY SHALL BEGIN UNTIL THE AIRPORT HAS APPROVED THE SPCD.
- THE CSPP COVERS OPERATIONAL SAFETY. THE CONTRACTOR SHALL BE 3. RESPONSIBLE FOR THE INDIVIDUAL SAFETY OF HIS/HER PERSONNEL AND MEETING OSHA REQUIREMENTS.
- A MINIMUM OF 10 DAYS PRIOR TO THE NOTICE TO PROCEED THE 4. CONTRACTOR SHALL PROVIDE A LIST OF SUBCONTRACTORS AND MATERIAL SUPPLIERS
- ALL CONTRACTOR COSTS ASSOCIATED WITH THE REQUIREMENTS LISTED 5. ON THIS SHEET SHALL BE CONSIDERED INCIDENTAL TO THE CONTRACT.

1. COORDINATION

- PRIOR TO THE START OF CONSTRUCTION THE CONTRACTOR SHALL ATTEND A PRE-CONSTRUCTION CONFERENCE WITH THE AIPORT, RESIDENT ENGINEER, AND ILLINOIS DIVISION OF AERONAUTICS (IDA). THE COST OF PREPARING FOR AND ATTENDING THE PRE-CONSTRUCTION CONFERENCE SHALL BE INCIDENTAL TO THE CONTRACT.
- ON OR BEFORE THE PRE-CONSTRUCTION CONFERENCE, THE CONTRACTOR SHALL SUBMIT A PROPOSED SCHEDULE FOR THE PROJECT. THE SCHEDULE SHALL INCLUDE A START AND COMPLETION DATE FOR EACH ITEM OF WORK. THE SCHEDULE SHALL BE UPDATED ON A WEEKLY BASIS. ALL COSTS ASSOCIATED WITH THE SCHEDULE SHALL BE INCIDENTAL TO THE CONTRACT.
- DURING CONSTRUCTION THE CONTRACTOR SHALL ATTEND A WEEKLY COORDINATION MEETING WITH THE AIRPORT STAFF AND RESIDENT ENGINEER. ALL COSTS ASSOCIATED WITH ATTENDING THE WEEKLY MEETING SHALL BE INCIDENTAL TO THE CONTRACT.

2. PHASING

- TOTAL CONTRACT TIME SHALL BE 27 CALENDAR DAYS FOR BASE BID AND 16 ADDITIONAL CALENDAR DAYS FOR ADDITIVE ALTERNATE #1. 1.
- WORK SHALL BE COMPLETED IN TWO SUB-PHASES AS SHOWN ON THE EQUENCE OF CONSTRUCTION PLAN SHEETS.

3. AREAS AND OPERATIONS AFFECTED BY THE CONSTRUCTION ACTIVITY

- ALL RUNWAYS, TAXIWAYS AND APRONS SHALL BE KEPT OPEN TO AIRCRAFT TRAFFIC DURING CONSTRUCTION EXCEPT AS NOTED ON THE
- WHEN CONFLICTS ARISE BETWEEN CONSTRUCTION ACTIVITIES AND 2. AIRCRAFT OPERATIONS AND SAFETY, AIRCRAFT OPERATIONS AND SAFETY SHALL TAKE PRECEDENCE AND SHALL GOVERN. FINAL AUTHORITY IN THE APPROVAL OF CONSTRUCTION SEQUENCING LIES WITH THE AIRPORT
- ALL CONSTRUCTION TRAFFIC SHALL IMMEDIATELY YIELD TO ONCOMING З. AIRCRAFT AT ALL TIMES.

4. NAVAIDS THAT COULD BE AFFECTED

- THE CONTRACTOR MUST COORDINATE WITH AIRPORT OPERATIONS/ENGINEER IN ADVANCE FOR ANY WORK WITHIN A NAVAID CRITICAL AREA OR AFFECTING THE VISUAL, TRANSMITTED SIGNAL OR POWER SUPPLY OF A NAVAID.
- 2. EDGE LIGHTS, THRESHOLD LIGHTS, VISUAL AIDS AND ALL ILS EQUIPMENT SHALL BE SHUT OFF FOR THE DURATION OF A CLOSURE PERIOD ON ANY ASSOCIATED AIRFIELD PAVEMENTS. IF THE LIGHTING CIRCUIT MUST BE ON FOR OPEN PAVEMENT AREAS, CLOSED PAVEMENT AREA LIGHTS SHALL BE COVERED COMPLETELY.
- 3. EXCEPT WHERE NOTED IN THE PLANS, EXISTING COMMUNICATIONS EQUIPMENT AND NAVIGATIONAL AIDS (NAVAIDS) SHALL NOT BE DISTURBED BY THE CONTRACTOR AND SHALL BE PROTECTED FROM DAMAGE.
- 4. PRIOR TO BEGINNING SITE WORK, CONTRACTOR SHALL COORDINATE THROUGH AIRPORT OPERATIONS TO LOCATE, AND THE CONTRACTOR TO MARK ALL UNDERGROUND COMMUNICATIONS CABLES AND FACILITIES, WITHIN THE PROJECT AREA.
- 5. IF CONTRACTOR CAUSES INTERRUPTION OF POWER OR COMMUNICATIONS TO A NAVAID CONTRACTOR SHALL REPAIR WITHIN 24 HOURS AT THE CONTRACTOR'S COST. CONTRACTOR MUST COORDINATE REPAIR WITH AIRPORT OPERATIONS BEFORE ANY REPAIR IS MADE

- 5. CONTRACTOR ACCESS
- CONTRACTOR ACCESS SHALL BE AS NOTED BELOW AND AS SHOWN ON THE SITE PLAN AND CONSTRUCTION ACTIVITY PLAN SHEETS, ALL COSTS BELATING TO CONTRACTOR'S ACCESS AND SECURITY SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR
- THE CONTRACTOR IS TO ACCESS THE SITE USING THE ROUTES 2. AND GATE(S) SHOWN, THE CONTRACTOR SHALL BE RESPONSIBLE FOR KEEPING THE ACCESS GATE CLOSED DURING WORK HOURS.
- CONTRACTOR SHALL OBTAIN ALL NECESSARY PERMITS AND TEMPORARY EASEMENTS FOR THE PUBLIC ACCESS ROAD(S) SHOWN AND SHALL COMPLY WITH ALL REQUIREMENTS, LOAD RESTRICTIONS. & TRAFFIC CONTROL SIGNAGE REQUIRED BY THE CITY, COUNTY, TOWNSHIP, OR I.D.O.T.
- CONTRACTOR'S VEHICLES AND EQUIPMENT SHALL BE MARKED 4. AND FLAGGED PER SECTION 40-05 OF THE STANDARD SPECIFICATIONS AND SECTION 40-10 OF THE SPECIAL PROVISIONS. MAXIMUM HEIGHT OF CONTRACTOR'S EQUIPMENT WILL BE 25'.
- CONTRACTOR WORK CREWS MUST MAINTAIN RADIO CONTACT WITH THE WAUKEGAN AIR TRAFFIC CONTROL TOWER GROUND CONTROL (121.65 MHZ) AT ALL TIMES WHEN INSIDE THE AIRPORT OPERATIONS AREA (AOA). THE CONTRACTOR SHALL SUPPLY ALL APPROPRIATE RADIOS NEEDED FOR COMMUNICATIONS AND ONLY HIS PERSONNEL WHO HAVE SUCCESSFULLY SATISFIED THE AIRPORT OF THEIR COMPETENCE MAY OPERATE THESE RADIOS.
- THE CONTRACTORS STORAGE AND STAGING AREAS WILL BE AS SHOWN ON THE CONSTRUCTION ACTIVITY PLAN.
- THE CONTRACTOR SHALL KEEP A RECORD OF THE NAMES OF ALL EMPLOYEES ENTERING THE JOB SITE ON A DAILY BASIS. A RECORD OF EACH SUBCONTRACTOR ENTERING THE JOB SITE SHALL ALSO BE KEPT BY THE CONTRACTOR.
- WHEN THE CONTRACTOR IS NOT WORKING, EQUIPMENT SHALL BE 9. STORED AT THE STAGING AREAS.

DURING ADVERSE WEATHER THE CONTRACTOR SHALL MAINTAIN ACCESS TO THE WORK AT NO ADDITIONAL COST TO THE CONTRACT. NO EXTENSION OF THE CONTRACT TIME WILL BE CONSIDERED FOR DELAYS DUE TO LACK OF ADEQUATE ACCESS TO THE WORK SITE.

THE CONTRACTOR WILL BE PERMITTED TO STORE EQUIPMENT AND MATERIALS ONLY AT THE LOCATIONS SHOWN. PARKED EQUIPMENT AND MATERIAL STOCKPILES SHALL NOT PENETRATE

- SURFACES DEFINED BY F.A.R. TITLE 14 PART 77 OBJECTS AFFECTING NAVIGABLE AIRSPACE. EXISTING TURF AREAS 10. DISTURBED BY THE CONTRACTOR'S OPERATIONS SHALL BE RESTORED BY HIM AT HIS EXPENSE TO THE SATISFACTION OF THE RESIDENT ENGINEER AND THE AIRPORT.
- ALL CONSTRUCTION TRAFFIC OPERATING ON, OR CROSSING RUNWAYS, TAXIWAYS AND APRONS OPEN TO AIRCRAFT TRAFFIC SHALL BE LINDER CONTROL BY A FLAGMAN OR ESCORT IN BADIO CONTACT WITH THE COMMON TRAFFIC ADVISORY FREQUENCY. THE CONTRACTOR SHALL PROVIDE HIS OWN FLAGMEN.
- THE CONTRACTOR SHALL THOROUGHLY CLEAN ALL CONSTRUCTION AREAS AND HAUL ROUTES WHICH WILL BE OPENED TO VEHICLE AND AIR TRAFFIC TO THE SATISFACTION OF AIRPORT 12. OPERATIONS OR THE RESIDENT ENGINEER. A POWER BROOM AND OPERATOR SHALL BE ON SITE AT ALL TIMES WHEN ACTIVE PAVEMENTS ARE UTILIZED FOR CONSTRUCTION TRAFFIC.
- ALL PAVEMENTS, DRIVES OR ANY OTHER AREAS UTILIZED BY THE CONTRACTOR FOR HAUL ROADS OR STORAGE AREAS SHALL BE MAINTAINED AND REPAIRED TO THE SAME CONDITION OR BETTER 13. THAN THEY WERE PRIOR TO BEGINNING CONSTRUCTION, NO ADDITIONAL COMPENSATION WILL BE MADE TO THE CONTRACTOR FOR THIS WORK.
- 14. ALL VEHICLE AND EQUIPMENT OPERATORS USED BY THE CONTRACTOR SHALL BE PROPERLY TRAINED BY THE CONTRACTOR
- THE CONTRACTOR SHALL NOTIFY THE AIRPORT IF CONSTRUCTION ACTIVITY WILL REQUIRE THE BLOCKAGE OF EMERGENCY ACCESS 15. TO THE AIRPORT.

6. WILDLIFE MANAGEMENT

- THE CONTRACTOR SHALL NOTIFY THE AIRPORT OR THE RESIDENT. ENGINEER IF ANY WILDLIFE IS SEEN ENTERING THE AIRPORT
- CONTRACTOR ACCESS GATES SHALL REMAIN CLOSED WHEN THE CONTRACTOR IS NOT WORKING.
- THE CONTRACTOR SHALL DISPOSE OF ALL TRASH INCLUDING 3. FOOD SCRAPS IN APPROVED CONTRACTOR PROVIDED CONTAINERS

7. FOREIGN OBJECT DEBRIS (FOD) MANAGEMENT

- THE CONTRACTOR SHALL PICK UP ANY FOREIGN OBJECT DEBRIS (FOD) SEEN ON THE AIRFIELD PAVEMENTS.
- THE CONTRACTOR SHALL SECURE ALL LOOSE ITEMS FROM FHICLES PRIOR TO DRIVING ON AIRFIELD PAVEMENTS.

- 8. HAZARDOUS MATERIALS (HAZMAT) MANAGEMENT THE CONTRACTOR SHALL DEVELOP A HAZMAT MANAGEMENT PLAN AND KEEP COPIES ON THE JOBSITE OF MATERIAL SAFETY DATA
- SHEETS (MSDS) FOR ALL MATERIALS HANDLED ON THE JOBSITE.

9. NOTIFICATION OF CONSTRUCTION ACTIVITIES

- THE CONTRACTOR SHALL PROVIDE A 24 HOUR EMERGENCY CONTACT PERSON AND PHONE NUMBER.
- THE CONTRACTOR SHALL GIVE A MINIMUM OF 10 DAYS NOTICE TO THE FAA AND AIRPORT PRIOR TO THE CLOSURE OF ANY RUNWAY SO THAT THE FAA MAY DEACTIVATE THE FAA - OWNED NAVAIDS.
- THE CONTRACTOR SHALL GIVE A MINIMUM 30 DAYS NOTICE TO THE AIRPORT, AND PRIOR TO THE PRE-CONSTRUCTION CONFERENCE, PRIOR TO CLOSING ANY RUNWAY OR TAXIWAY PAVEMENT SO THAT THE PROPER NOTAMS MAY BE ISSUED BY THE AIRPORT FOR COORDINATION WITH THE AIRPORT TENANTS
- FOR ANY EQUIPMENT USED BY THE CONTRACTOR WITH A HEIGHT GREATER THAN 25', THE CONTRACTOR SHALL PROVIDE TO THE AIRPORT THE TYPE OF EQUIPMENT, TOTAL HEIGHT, AND LOCATION WHERE THE EQUIPMENT WILL BE USED. THE CONTRACTOR WILL SUBMIT FAA FORM 7460-1 TO THE FAA FOR AN AIRSPACE STUDY. NO EQUIPMENT WITH A HEIGHT GREATER THAN 25' SHALL BE USED UNTIL A DETERMINATION FROM FAA IS RECEIVED.
- IN THE EVENT OF AN EMERGENCY, THE CONTRACTOR SHALL CALL 911.

10. INSPECTION REQUIREMENTS

- THE CONTRACTOR SHALL INSPECT THE JOBSITE DAILY TO ENSURE COMPLIANCE WITH THE CSPP. THE CHECKLIST FOUND IN APPENDIX C OF FAA AC 150/5370-2G OR LATEST EDITION MAY BE USED TO AID IN THE INSPECTIONS.
- THE CONTRACTOR SHALL REQUEST OPERATIONAL INSPECTION OF EACH PHASE WORK AREA PRIOR THE AREA BEING REOPENED. THE AIRPORT WILL DETERMINE IF THE WORK AREA IS ALLOWED TO BE OPENED.

11. UNDERGROUND UTILITIES

- IT WILL BE NECESSARY FOR THE CONTRACTOR TO MAKE HIS OWN 1. FIELD INVESTIGATION TO DETERMINE THE EXACT LOCATION OF THE UNDERGROUND UTILITIES AT CRITICAL POINTS. THE LOCATION OF UNDERGROUND UTILITIES AS INDICATED ON THE PLANS HAS BEEN OBTAINED FROM EXISTING RECORDS, NEITHER THE OWNER NOR THE UNIVERSITIES AND A CONTRACT AND A ELECTRICAL CABLE AND LIGHTS, DAMAGED BY THE CONTRACTOR SHALL BE REPAIRED BY HIM AT HIS OWN EXPENSE IN A MANNER WHICH IS SATISFACTORY TO THE ENGINEER AND TO THE OWNER OF THE UTILITY. ANY REPAIRS THAT MUST BE MADE BY THE OWNER OF THE UTILITY SHALL HAVE THE COST REIMBURSED TO THE UTILITY BY THE CONTRACTOR. AIRFIELD LIGHTING CABLES DAMAGED BY THE CONTRACTOR SHALL BE REPAIRED BY A QUALIFIED ELECTRICIAN WITH THE COSTS TO BE BORNE BY THE
- BEFORE INITIATING ANY DIGGING, DRILLING OR EXCAVATING ON 2 THE AIRPORT PROPERTY, THE CONTRACTOR SHALL CALL J.U.L.I.E. AND CONTACT THE LOCAL FAA OFFICE TO ARRANGE FOR UTILITY LOCATES. SEE SECTION 70-16 OF THE SPECIAL PROVISIONS FOR UTILITY CONTACT INFORMATION.

12. PENALTIES

NONCOMPLIANCE BY THE CONTRACTOR WITH AIRPORT RULES AND REGULATIONS OR FAILURE TO COMPLY WITH THE AIRPORTS APPROVED CSPP AND THE CONTRACTOR'S APPROVED SPCD MAY RESULT IN FINES AS ALLOWED BY LAW

13. SPECIAL CONDITIONS

ADJACENT CONSTRUCTION MAY IMPACT THE OPERATIONS OF THE CONTRACTOR. SEE THE COORDINATION NOTES FOR ADDITIONAL

14. RUNWAY AND TAXIWAY VISUAL AIDS

- ALL BUNWAYS, TAXIWAYS, AND APBONS SHALL BE KEPT OPEN TO AIRPORT TRAFFIC DURING CONSTRUCTION EXCEPT AS NOTED IN THE CONSTRUCTION ACTIVITY PLAN.
- IF ANY RUNWAY OR TAXIWAY CLOSURES ARE REQUESTED BY THE CONTRACTOR AND APPROVED BY THE AIRPORT, THE CONTRACTOR SHALL USE MARKING, LIGHTING AND SIGNS THAT FOLLOWING THE REQUIREMENTS OF FAA AC 150/5370-2G OR LATEST EDITION.

15. MARKING AND SIGNS FOR ACCESS ROUTES

BARRICADES AND SIGNS SHALL BE USED ALONG THE CONTRACTOR'S ACCESS ROUTE AS DETAILED ON THE CONSTRUCTION ACTIVITY PLAN SHEETS.

16. HAZARD MARKING AND LIGHTING

- THE CONTRACTOR SHALL FURNISH, ERECT, AND MAINTAIN MARKINGS AND ASSOCIATED LIGHTING OF OPEN TRENCHES, EXCAVATIONS, TEMPORARY STOCKPILES, AND HIS/HER CONSTRUCTION EQUIPMENT
- ALL CONSTRUCTION EQUIPMENT SHALL BE FLAGGED AND/OR LIGHTED IN 2. ACCORDANCE WITH FAA ADVISORY CIRCULAR 150/5370-2G AND 150/5210-5C OR LATEST EDITION AT ALL TIMES WHILE OPERATING ON AIRPORT PROPERTY. THE MAXIMUM EQUIPMENT HEIGHT IS 25'.
- BARBICADES SHALL BE PLACED AT THE LOCATIONS SHOWN ON THE 3 CONSTRUCTION ACTIVITY PLAN SHEET OR AS DIRECTED BY THE
- THE CONTRACTOR SHALL INSPECT THE BARRICADES ONCE DURING EACH WORK DAY TO INSURE PROPER PLACEMENT AND PROPER OPERATION OF THE RED LIGHTS AND FLAG PLACEMENT

17. WORK ZONE LIGHTING FOR NIGHTTIME CONSTRUCTION

18. COOPERATION BETWEEN CONTRACTORS

- ALLOWED
- - REHAB EAST APRON

19. PROTECTION

1. ALL WORK REQUIRED INSIDE OF A RUNWAY SAFETY AREA, WILL REQUIRE THE RUNWAY TO BE CLOSED.

20. OTHER LIMITATIONS ON CONSTRUCTION

UNLESS OTHERWISE SPECIFIED.

COMPLETE

21. AIRFIELD EDGE LIGHTS AND SIGNS

- ENGINEER TO RE-ENERGIZE THE RUNWAY/TAXIWAY CIRCUIT

WORK PERFORMED BY THE CONTRACTOR OUTSIDE OF DAYLIGHT HOURS SHALL BE DONE UNDER SUFFICIENT ARTIFICIAL AREA LIGHTING TO ALLOW FOR PROPER CONSTRUCTION METHODS AND INSPECTION.

LIGHTS SHALL CONSIST OF VEHICLE OR MOVABLE POLE MOUNTED FLOODLIGHTS AND/OR SPOTLIGHTS OF SUFFICIENT NUMBER TO ILLUMINATE THE WORK AREA. VEHICLE HEADLIGHTS WILL BE ALLOWED ONLY IN ADDITION TO OTHER LIGHTS MENTIONED ABOVE, LIGHTING SHALL NOT INTERFERE WITH AIR OPERATIONS, ANY WORK BEING PERFORMED UNDER INSUFFICIENT ARTIFICIAL LIGHTING, IN THE RESIDENT ENGINEER'S JUDGEMENT, SHALL BE STOPPED UNTIL SUCH TIME AS ADDITIONAL LIGHTING IS PROVIDED. ALL WORK PERFORMED DURING THAT TIME WILL NOT BE ACCEPTABLE UNTIL PROPER INSPECTION AND TESTING CAN BE MADE.

THE AIRPORT RESERVES THE RIGHT TO CONTRACT FOR AND PERFORM OTHER OR ADDITIONAL WORK ON OR NEAR THE WORK COVERED BY THIS CONTRACT

OTHER CONTRACTS MAY BE UNDER CONSTRUCTION CONCURRENTLY RESULTING IN MORE THAN ONE CONTRACTOR WORKING ON THE AIRPORT AT

THE CONTRACTOR SHALL PLAN AND CONDUCT HIS/HER WORK SO AS NOT TO INTERFERE OR HINDER THE PROGRESS OR WORK BEING PERFORMED BY OTHER CONTRACTORS. THE TIMELY PROSECUTION OF THE OVERALL PROJECT IS DEPENDENT UPON THE PROPER COORDINATION BETWEEN CONTRACTORS, IT IS TO BE FULLY UNDERSTOOD BY THE CONTRACTOR THAT THE PROSECUTION OF THE OVERALL PROJECTS AND THE SAFETY AND CONVENIENCE OF THE AVIATION PUBLIC ARE THE GOVERNING CRITERIA FOR RESOLVING CONFLICTS WHICH MAY ARISE BETWEEN HISHER SCHEDULE AND THE SCHEDULE OF OTHER CONTRACTORS. WHEN CONFLICTS ARISE, RESOLUTION OF SUCH CONFLICTS WILL BE MADE BY THE AIRPORT MANAGEMENT THROUGH THE AIRPORT'S PROJECT REPRESENTATIVE IN THE BEST INTEREST OF THE AIRPORT, DELAYS CHANGES IN SCHEDULING, OR EXPEDITION OF WORK UNDER THIS CONTRACT TO COORDINATE THE TIMELY PROSECUTION OF WORK WILL BE CONSIDERED INCIDENTAL TO THE CONTRACT AND NO ADDITIONAL COMPENSATION WILL BE

THE PRIME CONTRACTOR WILL BE RESPONSIBLE TO COORDINATE CONSTRUCTION ACTIVITIES AND ACCESS BETWEEN ALL ON-SITE CONTRACTORS AND SUBCONTRACTORS. IT IS ANTICIPATED THE FOLLOWING PROJECTS MAY BE UNDER CONSTRUCTION CONCURRENTLY WITH THIS PROJECT. NO ADDITIONAL COMPENSATION SHALL BE CONSIDERED FOR ANY EFFORTS TO COORDINATE AND GAIN ACCESS TO THE SITE DUE TO ADJACENT CONSTRUCTION.

REHAB SOUTH HANGAR PAVEMENTS PHASE 1 AND 2.

CONSTRUCT PERIMETER FENCING - PHASE 5.

2. ALL WORK REQUIRED ON AN ACTIVE TAXIWAY OR INSIDE OF AN ACTIVE TAXIWAY OBJECT FREE AREA, WILL REQUIRE THE TAXIWAY TO BE CLOSED.

IF, DURING CONSTRUCTION, AN EMERGENCY IS DECLARED BY THE AIRPORT THE CONTRACTOR SHALL IMMEDIATELY CLEAR THE PAVEMENT OF ALL VEHICLES PERSONNEL AND FOUIPMENT IF DIRECTED BY THE AIRPORT

BROKEN CONCRETE, BROKEN ASPHALT, RUBBISH FROM DEMO, AND OTHER MISCELLANEOUS DEBRIS SHALL BE DISPOSED OF OFF AIRPORT PROPERTY,

THE CONTRACTOR WILL BE RESPONSIBLE FOR COORDINATING THE AIRSPACE FOR THE CONSTRUCTION EQUIPMENT THAT IS TALLER THAN THAT SPECIFIED ON THE PLANS WITH THE FAA. THIS PROCESS MAY TAKE UP TO 12 WEEKS TO

THE CONTRACTOR SHALL BE RESPONSIBLE FOR MEGGAR TESTING ALL EXISTING CIRCUITS PRIOR TO CONSTRUCTION AND FOLLOWING CONSTRUCTION AS SPECIFIED IN THE CONTRACT DOCUMENTS.

CONTRACTOR SHALL COVER ALL AIRFIELD SIGNS AND TAXIWAY LIGHTS ON CLOSED TAXIWAYS UNTIL THE TAXIWAY IS RE-OPENED FOR AIRCRAFT USE. TH METHOD AND MATERIALS USED TO COVER THE SIGNS AND LIGHTS SHALL MEET THE ENGINEER'S AND AIRPORT'S APPROVAL. COST INCIDENTAL TO TH CONTRACT. REMOVING LAMPS FROM ENERGIZED FIXTURES AS A MEANS TO REMOVE THE LIGHTS OR FIXTURES FROM SERVICE SHALL NOT BE ACCEPTABLE.

CONTRACTOR SHALL TURN OFF RUNWAY/TAXIWAY EDGE LIGHTING REGULATOR AND LOCK-OUT/TAG-OUT CIRCUIT BREAKER AND CUT OUT INSIDE THE ELECTRICAL VAULT. DURING ALL RUNWAY/TAXIWAY CLOSURES. CONTRACTOR SHALL COORDINATE ACCESS TO THE VAULT WITH THE AIRPORT MANAGER/RESIDENT ENGINEER PRIOR TO RE-OPENING THE RUNWAY/TAXIWAY, THE CONTRACTOR SHALL COORDINATE WITH AIRPORT MANAGER/RESIDENT



CONSULTANTS

IL PROJECT: UGN-5119 IL LETTING ITEM: 07A IL CONTRACT: WA080

REHABILITATE MAIN PARKING LOT

FINAL MARCH 1, 2024

OWNER



MARK DATE DESCRIPTION

CMT PROJECT NO:	22004938.00
CAD DWG FILE:	
DESIGNED BY:	LB
DRAWN BY:	JRO
CHECKED BY:	CAL
APPROVED BY:	DKP
CORVEIGHT	

SHEET TITLE

CONSTRUCTION **ACTIVITY PLAN** NOTES

5

SHEET

OF

13





BARRICADE NOTES

- FLASHER OR STEADY BURN LIGHTS SHALL BE BATTERY OPERATED. 1. LENS SHALL BE RED AND BE ABLE TO ROTATE 90°.
- 2. FACING OF BARRICADE SHALL BE COVERED WITH REFLECTIVE TAPE OR PAINT.
- 3. BARRICADES TO BE PLACED WITH A MAXIMUM OF 4' SPACING END TO END UP TO THE EDGE OF PAVEMENT ALONG OPERATIONAL PAVEMENT ADJACENT TO CONSTRUCTION AS DIRECTED BY THE RESIDENT ENGINEER. ALTERNATE FLASHER OR STEADY BURN LENSES SO THAT EVERY OTHER LENS IS ROTATED 90°.
- 4. FLASHER OR STEADY BURN LIGHTS SHALL BE SECURED TO THE BARRICADES, AS APPROVED BY THE RESIDENT ENGINEER.
- BARRICADES SHALL BE OF LOW MASS, EASILY COLLAPSIBLE UPON 5. CONTACT WITH AN AIRCRAFT OR ANY OF IT COMPONENTS, AND WEIGHTED TO AVOID BEING BLOWN OVER.
- 6. BARRICADES SHALL BE OF A COMMERCIAL DESIGN AND SHALL MEET CURRENT FAA REQUIREMENTS.
- 7. PLACE ALL BARRICADES OUTSIDE RUNWAY SAFETY AREAS AND OUTSIDE TAXIWAY OBJECT FREE AREAS.
- 8. ALL COST ASSOCIATED WITH THE LOW PROFILE BARRICADES SHALL BE CONSIDERED INCIDENTAL TO THE CONTRACT.

GROUND CONTROL FREQUENCY: 121.65 MHz

MAXIMUM ANTICIPATED HEIGHT OF CONSTRUCTION EQUIPMENT: DUMP TRUCK IN DUMP POSITION - 25'

IN THE EVENT THE CONTRACTOR PROPOSES TO UTILIZE CONSTRUCTION EQUIPMENT THAT IS TALLER THAN WHAT IS LISTED, THE CONTRACTOR WILL BE RESPONSIBLE TO SUBMIT FAA FORM 7460-1 FOR AIRSPACE APPROVAL, THE RESIDENT ENGINEER WILL PROVIDE BASE AIRPORT INFORMATION FOR THE CONTRACTOR'S USE.



NOT TO SCALE



TYPICAL PROFILE F.A.R. PART 77 IMAGINARY SURFACES

NO SCALE				
RUNWAY END	ELEVATION	APPROACH SLOPE		
5	724.7	34:1		
23	723.1	50:1		
14	727.6	20.1		

712.1

20:1

32



F.A.R. PART 77 IMAGINARY SURFACES

NO SCALE

NOTE:

IMAGINARY SURFACE REQUIREMENTS FOR EXISTING ACTIVE RUNWAYS (R/W) ARE SIMILAR EXCEPT PRIMARY SURFACE (PS) DIMENSIONS VARY RUNWAY 14-32 250' PS (125' LT & RT OF CENTERLINE) RUNWAY 5-23 1000' PS (500' LT & RT OF CENTERLINE)

20" X 20" NYLON FLAG WITH 12 GA. DIAGONAL WIRE STIFFENER. TWO FLAGS TOTAL (ONE ORANGE AND ONE WHITE FLAG). FLAGS SHALL BE REMOVABLE.





CONSULTANTS

IL PROJECT: UGN-5119 IL LETTING ITEM: 07A IL CONTRACT: WA080

REHABILITATE MAIN PARKING LOT

FINAL MARCH 1, 2024

OWNER



MARK	DATE	DESCRIP	TION		
CMT PROJECT NO: 22004938.00					
CAD DWG FILE:					
DESIGNED BY:			LB		
DRAWN BY:			JRO		
CHECKED BY:			CAL		

APPROVED BY: DKP COPYRIGHT SHEET TITLE

CONSTRUCTION **ACTIVITY PLAN** DETAILS

SHEET 6 OF 13







STORM WATER POLLUTION PREVENTION NOTES:

THE FOLLOWING IS TO ESTABLISHED BEST MANAGEMENT PRACTICES TO BE INCORPORATED IN THE PROJECT TO DIRECT THE CONTRACTOR IN THE PLACEMENT OF TEMPORARY EROSION CONTROL SYSTEMS AND TO PROVIDE A STORM WATER POLLUTION PREVENTION PLAN FOR COMPLIANCE WITH NPDES

THE PURPOSE OF THIS PLAN IS TO MINIMIZE EROSION WITHIN THE CONSTRUCTION SITE AND TO LIMIT SEDIMENTS FROM LEAVING THE SITE BY UTILIZING PROPER TEMPORARY EROSION CONTROL SYSTEMS AND PROVIDING GROUND COVER WITHIN A REASONABLE AMOUNT OF TIME

CERTAIN EROSION CONTROL FACILITIES SHALL BE INSTALLED BY THE CONTRACTOR AT THE BEGINNING OF CONSTRUCTION. OTHER ITEMS SHALL BE INSTALLED BY THE CONTRACTOR AS DIRECTED BY THE ENGINEER ON A CASE BY CASE SITUATION DEPENDING ON THE CONTRACTOR'S SEQUENCE OF ACTIVITIES, TIME OF YEAR, AND EXPECTED WEATHER CONDITIONS

THE CONTRACTOR SHALL INSTALL PERMANENT AND TEMPORARY EROSION CONTROL SYSTEMS AND SEEDING WITHIN A TIMEERAME REDUCING THE AMOUNT OF TEMPORARY SEEDING, WHICH WILL BE THE CONTRACTOR'S COST. THE ENGINEER WILL DETERMINE IF ANY TEMPORARY FROSION CONTROL SYSTEMS SHOWN IN THE PLAN CAN BE DELETED AND IF ANY ADDITIONAL TEMPORARY FROSION CONTROL SYSTEMS, WHICH ARE NOT INCLUDED IN THIS PLAN, SHALL BE ADDED. THE CONTRACTOR SHALL PERFORM ALL WORK AS DIRECTED BY THE ENGINEER AND AS SHOWN ON THE PLANS.

SITE DESCRIPTION

THE FOLLOWING IS A DESCRIPTION OF THE CONSTRUCTION ACTIVITY WHICH IS THE SUBJECT OF THIS PLAN:

THIS PROJECT CONSISTS OF CONSTRUCTING A MILL AND OVERLAY ON THE MAIN PARKING LOT AT WAUKEGAN NATIONAL AIRPORT. THE PROJECT INCLUDES PAVEMENT REHABILITATION, FULL DEPTH EARTH REMOVAL AND REPLACEMENT AND OTHER MISCELLANEOUS CONSTRUCTION WORK

THE FOLLOWING IS A DESCRIPTION OF THE INTENDED SEQUENCE OF MAJOR ACTIVITIES:

- INSTALL TEMPORARY EROSION CONTROL MEASURES
- 2. PAVEMENT MILLING AND REMOVAL
- 3. FULL DEPTH PATCH REMOVAL AND REPLACEMENT
- 4. CONSTRUCT NEW OVERLAYS
- 5. REMOVAL AND DISPOSAL OF TEMPORARY EROSION CONTROL MEASURES.

AREA OF CONSTRUCTION SITE

THE TOTAL AREA OF THE CONSTRUCTION SITE THAT WILL BE DISTURBED BY EXCAVATION, GRADING AND OTHER ACTIVITIES IS LESS THAN ONE (1) ACRE

DRAINAGE TRIBUTARIES AND SENSITIVE AREAS RECEIVING RUNOFF FROM THIS CONSTRUCTION SITE:

THE CONSTRUCTION IS LOCATED IN THE DES PLAINES RIVER WATERSHED. THE SITE DRAINS THROUGH A SERIES OF OVERLAND FLOW ROUTES/STORM SEWER INTO THE SUBURBAN COUNTRY CLUB TRIBUTARY THAT OUTLETS INTO ULTIMATELY THE DES PLAINES RIVER

SEDIMENTATION AND EROSION CONTROL NOTES

THE RESIDENT ENGINEER WILL PERFORM PERIODIC INSPECTION OF THE SITE TO IDENTIFY POTENTIAL SEDIMENT AND EROSION ISSUES.

ALL SOIL EROSION AND SEDIMENT CONTROL PRACTICES ARE REFERENCED FROM THE ILLINOIS URBAN MANUAL, UNLESS OTHERWISE STATED.

THE DRAWINGS, SPECIFICATIONS AND SPECIAL PROVISIONS WILL ENSURE THAT EXISTING VEGETATION IS PRESERVED WHERE ATTAINABLE AND DISTUBBED PORTIONS OF THE SITE WILL BE STABILIZED. STABILIZATION PRACTICES INCLUDE SEEDING AND MULCHING AS DIRECTED BY THE ENGINEER. STABILIZATION MEASURES SHALL BE INITIATED WITHIN SEVEN (7) DAYS OF DISTURBANCE.

DESCRIPTION OF STABILIZATION PRACTICES DURING CONSTRUCTION:

DURING CONSTRUCTION, AREAS OUTSIDE THE CONSTRUCTION LIMITS AS OUTLINED PREVIOUSLY HEREIN SHALL BE PROTECTED. THE CONTRACTOR SHALL NOT USE THIS AREA FOR STAGING (EXCEPT AS DESCRIBED ON THE PLANS AND DIRECTED BY THE ENGINEER), PARKING OF VEHICLES OR CONSTRUCTION EQUIPMENT, STORAGE OF MATERIALS, OR OTHER CONSTRUCTION RELATED ACTIVITIES.

HIN THE CONSTRUCTION LIMITS, AREAS WHICH MAY BE SUSCEPTIBLE TO EROSION AS DETERMINED BY THE ENGINEER SHALL REMAIN UNDISTURBED UNTIL FULL SCALE CONSTRUCTION IS UNDERWAY TO PREVENT UNNECESSARY SOIL EROSION

EARTH STOCKPILES SHALL BE TEMPORARILY SEEDED, AT THE CONTRACTORS EXPENSE, IF THEY ARE TO REMAIN UNUSED FOR MORE THAN FOURTEEN DAYS.

AS CONSTRUCTION PROCEEDS, THE CONTRACTOR SHALL INSTITUTE THE FOLLOWING AS DIRECTED BY THE ENGINEER:

- PLACE TEMPORARY EROSION CONTROL FACILITIES AT LOCATIONS SHOWN ON THE PLANS.
- EXCAVATED ABEAS AND EMBANKMENT ABEAS SHALL BE PERMANENTLY SEEDED IMMEDIATELY AFTER FINAL GRADING. IF NOT, THEY SHALL BE TEMPORARILY SEEDED, AT THE CONTRACTOR'S COST, IF NO CONSTRUCTION ACTIVITY IN THE AREA IS PLANNED FOR SEVEN DAYS.
- CONSTRUCTION EQUIPMENT SHALL BE STORED AND FUELED ONLY AT DESIGNATED LOCATIONS. ALL NECESSARY MEASURES SHALL BE TAKEN TO CONTAIN ANY FUEL OR POLLUTANT IN ACCORDANCE WITH EPA WATER QUALITY REGULATIONS, LEAKING EQUIPMENT OR SUPPLIES SHALL BE IMMEDIATELY REPAIRED OR REMOVED FROM THE SITE
- SEDIMENT COLLECTED DURING CONSTRUCTION OF THE VARIOUS TEMPORARY EROSION CONTROL SYSTEMS SHALL BE 5. DISPOSED OF OFF SITE ON A REGULAR BASIS AS DIRECTED BY THE ENGINEER. THE COST OF THIS MAINTENANCE SHALL BE INCIDENTAL TO THE COST OF THE PROJECT.
- THE TEMPORARY EROSION CONTROL SYSTEMS SHALL BE REMOVED AS DIRECTED BY THE ENGINEER AFTER USE IS NO LONGER NEEDED OR NO LONGER FUNCTIONING. THE COST OF THIS REMOVAL SHALL BE INCIDENTAL TO THE CONTRACT

DESCRIPTION OF STRUCTURAL PRACTICES AFTER FINAL GRADING:

TEMPORARY EROSION CONTROL SYSTEMS SHALL BE LEFT IN PLACE WITH PROPER MAINTENANCE UNTIL PERMANENT EROSION CONTROL IS IN PLACE AND WORKING PROPERLY AND ALL PROPOSED TURF AREAS ARE SEEDED AND

ONCE PERMANENT EROSION CONTROL SYSTEMS AS PROPOSED IN THE PLANS ARE FUNCTIONAL AND ESTABLISHED. TEMPORARY ITEMS SHALL BE REMOVED, CLEANED UP, AND DISTURBED TURF RESEEDED.

MAINTENANCE AFTER CONSTRUCTION

Path: Date:

CONSTRUCTION IS COMPLETE AFTER FINAL ACCEPTANCE BY THE ILLINOIS DIVISION OF AERONAUTICS. MAINTENANCE UP TO THIS DATE WILL BE REQUIRED BY THE CONTRACTOR

SOIL EROSION AND SEDIMENT CONTROL NOTES:

- ALL TREE PROTECTION, SEDIMENT CONTROL MEASURES, AND PERMANENT AND TEMPORARY STORM WATER PRACTICES SHALL BE IN PLACE PRIOR TO STARTING CONSTRUCTION.
- NO WORK SHALL BE PERFORMED IN FLOWING WATER. WORK IN AND NEAR FLOWING WATER SHALL BE ISOLATED FROM CONCENTRATED FLOWS OR STREAM FLOWS AT ALL TIMES. THE USE OF EARTHEN MATERIAL FOR ISOLATION WILL NOT BE ACCEPTABLE.
- CONSTRUCTION MATERIALS AND/OR OTHER STOCKPILES SHALL NOT BE LOCATED ON STREAM BANKS NOR IN THE PATH OF STREAM FLOW
- TEMPORARY EROSION CONTROL DEVICES SHALL BE CONSTRUCTED AS SHOWN ON THE PLANS OR AS DIRECTED BY THE ENGINEER
- PERMANENT SEEDING SHALL BE USED WHENEVER POSSIBLE. UNDER NO CIRCUMSTANCES SHALL THE CONTRACTOR PROLONG GRADING OR SHAPING SO THAT THE ENTIRE PROJECT CAN BE PERMANENTLY SEEDED AT ONE TIME.
- THE CONTRACTOR SHALL INSPECT ADJACENT STREETS DAILY AND CLEAN ADJACENT STREETS WHEN NECESSARY. ADJACENT STREETS SHALL BE KEPT FREE OF SOIL AND DEBRIS.
- SHOULD IT BE NECESSARY TO REMOVE ANY EROSION CONTROL DEVICES FOR CONSTRUCTION REASONS, THE CONTRACTOR SHALL FIRST OBTAIN PERMISSION AND SHALL REPLACE AND/OR REPAIR THE REMOVED DEVICES THE SAME DAY. THE COST OF REMOVING AND REPLACING THE DEVICE SHALL BE CONSIDERED INCIDENTAL TO THE CONTRACT
- ALL OTHER SOIL EROSION AND SEDIMENT CONTROL DEVICES AND MEASURES DEEMED NECESSARY BY THE 8. RESIDENT ENGINEER. COOK COUNTY, CHICAGO EXECUTIVE AIRPORT, IDOT DIVISION OF AFRONAUTICS, AND THE IEPA SHALL BE IMPLEMENTED IMMEDIATELY UPON NOTIFICATION OF THE CONTRACTOR
- THE CONTRACTOR SHALL PROVIDE LOCATIONS FOR CONCRETE TRUCK WASHOUT, AS APPROVED BY THE HIGH SEARCH ANY CONCRETE POURS, THESE LOCATIONS SHALL NOT BE NEAR ANY STREAM OR BODY OF WATER. LOCATIONS SHALL BE APPROVED BY THE ENGINEER PRIOR TO ANY CONCRETE POURS. ADDITIONALLY THE CONTRACTOR SHALL PROVIDE ADEQUATE FACILITIES TO WASH OUT PAVING EQUIPMENT AND FINISHING TOOLS. ALL WASTE WATER AND EXCESS CONCRETE MATERIALS SHALL BE CONTAINED BY AN APPROVED CONCRETE WASHOUT FACILITY
- 10. THE CONTRACTOR SHALL COORDINATE CONSTRUCTION ACTIVITIES TO ENSURE THAT EROSION CONTROL MEASURES ARE CONSISTENT BETWEEN ALL PROJECT PHASES AND ALL SUB-CONTRACTORS
- 11. THE CONTRACTOR SHALL TAKE ALL PRECAUTIONS TO PROTECT WETLANDS TO REMAIN FROM DAMAGE BY SEDIMENT, CONSTRUCTION EQUIPMENT, OR BY HIS PERSONNEL. THE CONTRACTOR SHALL ASSURE THAT DEBRIS OR ANY CONSTRUCTION MATERIAL IS NOT DISPOSED OF IN THE WETLANDS
- 12. WATER PUMPED OR OTHERWISE DISCHARGED FROM THE SITE DURING CONSTRUCTION DEWATERING SHALL BE FILTERED BY AN APPROVED MEANS
- 13. SEDIMENT COLLECTED DURING CONSTRUCTION BY THE VARIOUS TEMPORARY EROSION CONTROL SYSTEMS SHALL BE DISPOSED OF ON A REGULAR BASIS, SEDIMENT SHALL BE REMOVED FROM FROSION CONTROL SYSTEMS WHEN THE HEIGHT OF THE SEDIMENT EXCEEDS ONE-HALF OF THE HEIGHT OF THE DEVICE OR AS RECOMMENDED BY THE MANUFACTURER, WHICHEVER IS LESS.
- 14. ALL EROSION CONTROL MEASURES SHALL BE KEPT OPERATIONAL AND MAINTAINED CONTINUOUSLY HROUGHOUT THE PERIOD OF LAND DISTURBANCE UNTIL PERMANENT SOIL EROSION AND SEDIMENT CONTROL MEASURES ARE OPERATIONAL
- 15. THE CONDITION OF THE CONSTRUCTION SITE FOR WINTER SHUTDOWN SHALL BE ADDRESSED EARLY IN THE FALL GROWING SEASON SO THAT SLOPES AND OTHER BARE EARTH AREAS MAY BE STABILIZED WITH TEMPORARY AND/OR PERMANENT VEGETATIVE COVER. ALL OPEN AREAS THAT ARE TO REMAIN IDLE THROUGHOUT THE WINTER SHALL BECEIVE TEMPORARY EROSION CONTROL MEASURES INCLUDING TEMPORARY SEEDING. MULICHING AND/OR EROSION CONTROL BLANKET PRIOR TO THE END OF THE FALL GROWING SEASON. THE AREAS TO BE WORKED BEYOND THE END OF THE GROWING SEASON MUST INCORPORATE SOIL STABILIZATION MEASURES THAT DO NOT RELY ON VEGETATIVE COVER SUCH AS EROSION CONTROL BLANKET AND HEAVY MULCHING
- 16. PERMANENT STABILIZATION SHALL BE COMPLETED WITHIN 7 DAYS FOR AREAS WHERE WORK IS COMPLETED.

STAGING AND PROTECTION NOTES

- THE CONTRACTOR SHALL BE REQUIRED TO PROVIDE STORM WATER POLLUTION PREVENTION DEVICES AT THE STAGING AREA. THESE DEVICES, INCLUDING INCLE PROTECTIONS, SILT FENCE, BALES, DITCH CHECKS STABILIZED CONSTRUCTION ENTRANCES, ETC., SHALL NOT BE PAID FOR, BUT SHALL BE CONSIDERED INCIDENTAL TO THE CONTRACT
- AT THE COMPLETION OF WORK, THE STAGING AREA SHALL BE RESTORED TO PRE-CONSTRUCTION CONDITIONS, AT NO ADDITIONAL COST TO THE CONTRACT. THIS WORK SHALL INCLUDE REMOVING ANY AND ALL STORM WATER POLITITION PREVENTION DEVICES RESTORING BUTTED AREAS SEEDING AND MULICHING
- IT IS THE CONTRACTOR'S RESPONSIBILITY TO MAINTAIN THE STAGING AREA(S) IN A MANNER TO PREVENT POLLUTION AND SILTATION OF THE EXISTING STORM SEWER SYSTEM.
- ALL EQUIPMENT FUELING AND GREASING SHALL BE COMPLETED AT THE STAGING AREA. SPILLS SHALL BE IMMEDIATELY CONTAINED AND THE AREA CLEANED AT NO ADDITIONAL COST THE CONTRACT.







MARK	DATE	DESCRIPTION	1	
CMT PROJECT NO: 22004938.00				

OAD DWGTTEE.	
DESIGNED BY:	LB
DRAWN BY:	JRO
CHECKED BY:	CAL
APPROVED BY:	DKP
COPYRIGHT:	

SHEET

OF

13

10





	LEGEN
	NEW PAVEN
,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,	EXISTING BU
⊕ _{C-1}	CORING/BO

THE INFORMATION SHOWN ON THESE PLANS HAS BEEN OBTAINED FROM AVAILABLE RECORDS. NEITHER THE OWNER NOR THE ENGINEER ASSUMES ANY RESPONSIBILITY WHATSOEVER IN RESPECT TO THE ACCURACY OR SUFFICIENCY OF THE INFORMATION AND THERE IS NO GUARANTEE EITHER EXPRESSED OR IMPLIED THAT THE CONDITIONS INDICATED ARE REPRESENTATIVE OF THOSE TO BE ENCOUNTERED IN THE FIELD. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO VISIT THE SITE AND ACQUAINT HIMSELF WITH THE EXISTING CONDITIONS.

THE GEOTECHNICAL INFORMATION (OR ANY PORTIONS THEREOF) ARE PROVIDED ONLY AS AVAILABLE INFORMATION. THE CONTRACTOR MAY DRAW HIS OWN CONCLUSIONS FROM THE DATA SHOWN. THE SOILS INFORMATION IS NOT REPRESENTATIVE OF ALL SOLWHICH MIGHT BE ENCOUNTERED WITHIN THE LIMITS OF THE PROJECT. THE CONTRACTOR SHALL BY HIS OWN MEANS, SATISFY HIMSELF AS TO THE EXISTING SITE AND GEOTECHNICAL CONDITIONS FOR DETERMINING COST, MEANS, METHODS, TECHNIQUES AND SEQUENCES OF CONSTRUCTION.





ND

MENT REHABILITATION

BUILDING/HANGAR

RING LOCATION



CONSULTANTS

IL PROJECT: UGN-5119 IL LETTING ITEM: 07A IL CONTRACT: WA080

REHABILITATE MAIN PARKING LOT

FINAL MARCH 1, 2024

OWNER



MARK	DATE	DESCRIPTION					
CMT PROJECT NO: 22004938.00							
CAD DWG FILE:							
DESIG	NED BY	: LB					
DRAW	/N BY:	JRO					
CHEC	KED BY:	CAL					
APPROVED BY:		: DKP					
COPYRIGHT:							
SHEET TITLE							

GEOTECHNICAL LAYOUT

11

OF 13

SHEET





CONSULTANTS

IL PROJECT: UGN-5119 IL LETTING ITEM: 07A IL CONTRACT: WA080

REHABILITATE MAIN PARKING LOT

FINAL MARCH 1, 2024

OWNER



MARK	DATE	DESCRIPTION					
CMT PROJECT NO: 2			22004938.00				
CAD DWG FILE:							
DESIGNED BY:			LB				
DRAWN BY:			JRO				
CHECKED BY:			CAL				
APPROVED BY:			DKP				
COPYRIGHT:							

SHEET TITLE

ELECTRICAL DETAILS ADDITIVE ALTERNATE NO. 1

SHEET 13

OF

13