

SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
94-F3000-05-BT	COOK	102	10
STA. TO STA.			
PROJECT NO. TE-D001 (610)			
CENTENNIAL TRAIL			

CONTRACT NO. 83859

TRAIL SIGNS

STATION	RT / LT	MESSAGE	MUTCD CODE	WIDTH (MM)	DEPTH (MM)	AREA (SQ M)	POST TYPE A or S (Shared)	Type A POST LENGTH (M)
0+018	RT	NO MOTOR VEHICLES	R5-3	600	600	0.360	A	3.200
2+420	LT	NO MOTOR VEHICLES	R5-3	600	600	0.360	A	3.200
2+422	RT	STOP	R1-1	450	450	0.203	A	3.050
2+434	LT	STOP	R1-1	450	450	0.203	A	3.050
2+434	RT	NO MOTOR VEHICLES	R5-3	600	600	0.360	A	3.200
2+485	RT	Intersection Warning	W2-1	450	450	0.203	A	3.050
2+487	LT	Curve Warning, left	W1-12L	450	450	0.203	A	3.050
2+498	LT	NO MOTOR VEHICLES	R5-3	600	600	0.360	A	3.200
2+510	RT	NO MOTOR VEHICLES	R5-3	600	600	0.360	A	3.200
2+523	LT	Intersection Warning	W2-1	450	450	0.203	A	3.050
2+640	RT	Curve Warning, shallow left	W1-2	450	450	0.203	A	3.050
2+725	LT	Curve Warning, shallow right	W1-2	450	450	0.203	A	3.050
2+803 BK	LT	NO MOTOR VEHICLES	R5-3	600	600	0.360	A	3.200
2+805 BK	RT	STOP	R1-1	450	450	0.203	A	3.050
4+436	RT	NO MOTOR VEHICLES	R5-3	600	600	0.360	A	3.200
4+437	LT	STOP	R1-1	450	450	0.203	A	3.050
8+522	RT	TO	M4-13	300	100	0.030	A	3.300
8+522	RT	BIKE ROUTE	D11-1	600	450	0.270	S	0.000
8+522	RT	<-- I&M CANAL TRAIL (special)	D1-1b(L)	600	150	0.090	S	0.000
8+527	RT	BIKE ROUTE	D11-1	600	450	0.270	A	3.425
8+527	RT	CENTENNIAL TRAIL (special)	D1-1c	600	150	0.090	S	0.000
8+527	RT	Double Arrow	M7-5	300	225	0.068	S	0.000
8+550	LT	TO	M4-13	300	100	0.030	A	3.300
8+550	LT	BIKE ROUTE	D11-1	600	450	0.270	S	0.000
8+550	LT	I&M CANAL TRAIL --> (special)	D1-1b(R)	600	150	0.090	S	0.000
14+780	LT	NO MOTOR VEHICLES	R5-3	600	600	0.360	A	3.200
				TOTAL		5.910		63.075

EARTHWORK SUMMARY

LOCATION CENTENNIAL TRAIL STAGE 1	SUITABLE EXCAVATION (EARTH EXCAVATION)	EARTH EXCAVATION ADJUSTED FOR 15% SHRINKAGE	SUITABLE EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-) (FURNISHED EXCAVATION)	UNSUITABLE EXCAVATION (REMOVAL & DISPOSAL OF UNSUITABLE MATERIAL)	UNSUITABLE EMBANKMENT	UNSUITABLE BALANCE WASTE (+) OR SHORTAGE (-)	TOPSOIL FURNISHED & PLACED 150 MM
STATION TO STATION	CU M	CU M	CU M	CU M	CU M	CU M	CU M	CU M
0+000 TO 2+811	3,887	3,304	2,931	373	5,656	0	5,656	1,380
3+900 TO 4+430	0	0	0	0	0	0	0	0
4+430 TO 8+355	0	0	2,340	-2,340	3,510	0	3,510	1,872
8+355 TO 8+505	0	0	102	-102	153	0	153	82
8+505 TO 9+200	417	355	0	355	0	0	0	0
9+200 TO 14+758	0	0	3,335	-3,335	5,003	0	5,003	2,668
TOTAL	4,304	3,659	8,708	-5,049	14,322	0	14,322	6,002

NOTE: FOR BIDDING PURPOSES REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL IS ESTIMATED AT 120% OF UNSUITABLE EXCAVATION.

URS 100 S. WACKER DR., SUITE 500 TEL (312)-939-1000
CHICAGO, IL 60606 FAX (312)-939-4198

FOREST PRESERVE DISTRICT OF COOK COUNTY
CENTENNIAL TRAIL
PROPOSED SIGN SCHEDULE
& EARTHWORK SUMMARY

REVISIONS		
NO.	NAME	DATE

DATE: 10/20/06 DRAWN BY: VAP
DESIGNED BY: DIH CHECKED BY: DDL