

CODE NO.	ITEM	UNIT	TOTAL QUANTITY
60500060	REMOVING INLETS	EACH	12
60603800	COMBINATION CURB AND GUTTER, TYPE B-6.12	FOOT	3823
* 61139800	STORM SEWERS (SPECIAL), 4"	FOOT	12
* 61139900	STORM SEWERS (SPECIAL), 6"	FOOT	14
* 66000460	SPECIAL WASTE PLANS AND REPORTS	LSUM	1
67100100	MOBILIZATION	L SUM	1
70101830	TRAFFIC CONTROL AND PROTECTION, STANDARD BLR 21	L SUM	1
70101835	TRAFFIC CONTROL AND PROTECTION, STANDARD BLR 22	L SUM	1
70300100	SHORT TERM PAVEMENT MARKING	FOOT	302
70300150	SHORT TERM PAVEMENT MARKING REMOVAL	SQ FT	172
△ 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	454
△ 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	84
* X0324078	CONFLICT MANHOLES	EACH	1
* X2080250	TRENCH BACKFILL, SPECIAL	CU YD	583

CODE NO.	ITEM	UNIT	TOTAL QUANTITY
* X4200408	PORTLAND CEMENT CONCRETE PAVEMENT 8", SPECIAL	SQ YD	6420
* X6023206	INLETS, TYPE A, TYPE 3 FRAME AND GRATE, SPECIAL	EACH	5
* X5510100	STORM SEWER REMOVAL	FOOT	689
* XX000372	TEMPORARY AGGREGATE	TON	78
Z0013798	CONSTRUCTION LAYOUT	L SUM	1
* Z0051500	REMOVING AND RESETTING STREET SIGNS	EACH	11
* LR420010	PORTLAND CEMENT CONCRETE PAVEMENT (SPECIAL)	SQ YD	642

* SPECIAL PROVISIONS △ SPECIALTY ITEMS

FILE NAME: P:\Civil\Mattoon\Marshall Ave Phase II\CD_Sheets\Marshall-PH2-sht-500.dgn	USER NAME: * StalB	DESIGNED: - ALB	REVISED: - 4/4/2018
PLOT SCALE: 2,0000' / 1" =	CHECKED: - MED	DRAWN: - SAE	REVISED: -
PLOT DATE: * 1/9/2018	DATE: - NOV, 3, 2017	REVISOR: -	REVISED: -

The Upchurch Group
123 North 15th Street Mattoon, Illinois 61938
Professional Design Firm Corporation License No. 154-003401

MARSHALL AVENUE RECONSTRUCTION - PHASE 2
9TH STREET TO 14TH STREET
CITY OF MATTOON, ILLINOIS 61938

SUMMARY OF QUANTITIES

SCALE:	PROJECT: 3115113-02	TOTAL SHEETS: 60	SHEET NO.: 4
--------	---------------------	------------------	--------------