



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

April 18, 2018

SUBJECT: FAP 332 (IL 1)
Section 15-00033-02-PV (Tilton)
Vermilion County
Contract No. 91562
Item 205
April 27, 2018 Letting
Addendum (B)

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

- 1. Revised the Schedule of Prices.**
- 2. Revised page iii of the Table of Contents.**
- 3. Added page 42A to the Special Provisions.**
- 4. Revised sheets 2 – 5, 16 & 20 of the Plans.**

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bid.

Very truly yours,

Jack A. Elston, P.E.
Acting Bureau Chief
Bureau of Design and Environment

A handwritten signature in black ink, reading "Ted B. Walschleger, P.E." with a stylized flourish at the end.

By: Ted B. Walschleger, P.E.
Engineer of Project Management

GULFBOX JUNCTION, COMPOSITE CONCRETE..... 37
ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 10..... 37
ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 6..... 37
LUMINAIRE, LED, SPECIAL 38
LUMINAIRE INSTALLATION, TYPE 1 38
LUMINAIRE INSTALLATION, TYPE 2 39
REMOVAL OF LIGHTING UNIT, SALVAGE 39
REMOVAL OF POLE FOUNDATION..... 40
RELOCATE EXISTING LIGHTING UNIT..... 40
REMOVAL OF LIGHTING LUMINAIRE, SALVAGE..... 41
JUNCTION BOX (SPECIAL)..... 41
LIGHT POLE FOUNDATION, SPECIAL 42
CONTROLLER SOFTWARE REQUIREMENTS..... 42
CONSTRUCTION LAYOUT 42A
STATUS OF UTILITY SHEETS..... 43
LR 107-4..... 45

CONSTRUCTION LAYOUT

General: The Village shall furnish or shall employ a Professional Land Surveyor to furnish and place construction layout stakes for this project providing adequate reference points to construct the work as shown in the Plans. The Village shall maintain all layout data and field notes. Stakes for line and grade will be set at sufficient station intervals to assure substantial conformance to plan line and grade.

The Village shall provide field forces, equipment, and material to set additional stakes for this project, which are needed to establish offset stakes, reference points, and any other horizontal or vertical controls, including supplementary bench marks, necessary to secure a correct layout of the work.

The Contractor shall be responsible for having the finished work conform to the lines, grades, elevations, and dimensions called for in the Plans. Inspection or checking of the layout shall be performed by the Contractor to secure the proper dimensions, grades and elevations of the work. The Contractor shall exercise care in the preservation of stakes and benchmarks. Contractor is responsible for re-staking due to damaged or lost stakes. No additional compensation will be provided for re-staking or for staking beyond that provided by the Village.

Basis of Payment: This work will be considered incidental to the contract and no compensation will be allowed.

Added 4/18/2018