LETTING ITEM NO. 06A APRIL 27, 2018 IDOT LETTING

INDEX TO SHEETS

SUMMARY OF QUANTITIES AND MISCELLANEOUS DETAILS/NOTES SITE PLAN AND PROJECT CONTROL PLAN

SEQUENCE OF CONSTRUCTION SEQUENCE OF CONSTRUCTION GENERAL NOTES AND DETAILS TYPICAL SECTIONS EXISTING CONDITIONS AND PROPOSED REMOVALS - SHEET EXISTING CONDITIONS AND PROPOSED REMOVALS - SHEET 2 STAKING AND MARKING PLAN

JULIE

JOINT UTILITY LOCATING

www.illinois1call.com

INFORMATION FOR EXCAVATORS

COVER SHEET

RANGE: 7 EAST

TOWNSHIP: 38 NORTH

w what's **below**.

Call before you dig.

2.

81

CITY OF AURORA AURORA, ILLINOIS

CONSTRUCTION PLANS FOR AURORA MUNICIPAL AIRPORT

OVERLAY SOUTHEAST QUADRANT PERIMETER ROADWAYS

ILLINOIS PROJECT: ARR-4636

MARCH 2, 2018



02-28-18









U.S. ROUTE 30

SUGAR GROVE TOWNSHIP

LOCATION MAP

SITE PLAN

AU068 TOTAL SHEETS: 9



	AURORA, ILLINOIS
APPROVED BY	2 20 2 K. Queles AIRPORT MANA
DATE	2(
	17285
CRAWFORD MURPHY & TILLY, INC. CONSULTING ENGINEERS	This D.

STORM WATER POLLUTION PREVENTION NOTES

THE FOLLOWING IS TO ESTABLISHED BEST MANAGEMENT PRACTICES TO BE INCORPORATED IN THE PROJECT TO DIRECT THE CONTRACTOR IN THE PLACEMENT OF TEMPORARY EROSION CONTROL SYSTEMS AND TO PROVIDE A STORM WATER POLLUTION REVENTION PLAN FOR COMPLIANCE WITH NPDES

THE PUBPOSE OF THIS PLAN IS TO MINIMIZE FROSION WITHIN THE CONSTRUCTION SITE AND TO LIMIT SEDIMENTS FROM LEAVING THE SITE BY UTILIZING PROPER TEMPORARY EROSION CONTROL SYSTEMS AND PROVIDING GROUND COVER WITHIN A REASONABLE AMOUNT

CERTAIN EROSION CONTROL FACILITIES SHALL BE INSTALLED BY THE CONTRACTOR AT THE BEGINNING OF CONSTRUCTION. OTHER ITEMS SHALL BE INSTALLED BY THE CONTRACTOR AS DIRECTED BY THE ENGINEER ON A CASE BY CASE SITUATION DEPENDING ON THE CONTRACTOR'S SEQUENCE OF ACTIVITIES, TIME OF YEAR, AND EXPECTED WEATHER CONDITIONS

THE CONTRACTOR SHALL INSTALL PERMANENT EROSION CONTROL SYSTEMS AND SEEDING WITHIN A TIMEFRAME SPECIFIED HEREIN AND AS DIRECTED BY THE ENGINEER, THEREFORE MINIMIZING THE AMOUNT OF AREA SUSCEPTIBLE TO EROSION AND REDUCING THE AMOUNT OF TEMPORARY SEEDING, WHICH WILL BE THE CONTRACTOR'S COST. THE ENGINEER WILL DETERMINE IF ANY TEMPORARY EROSION CONTROL SYSTEMS SHOWN IN THE PLAN CAN BE DELETED AND IF ANY ADDITIONAL TEMPORARY EROSION CONTROL SYSTEMS. VHICH ARE NOT INCLUDED IN THIS PLAN, SHALL BE ADDED. THE CONTRACTOR SHALL PERFORM ALL WORK AS DIRECTED BY THE ENGINEER AND AS SHOWN ON THE PLANS.

SITE DESCRIPTION

THE FOLLOWING IS A DESCRIPTION OF THE CONSTRUCTION ACTIVITY WHICH IS THE SUBJECT OF THIS PLAN:

THIS PROJECT CONSISTS OF CONSTRUCTING AN OVERLAY, PAVEMENT PATCHING, PAVEMENT MILLING AND CRACK REPAIR AT AURORA MUNICIPAL AIRPORT

THE FOLLOWING IS A DESCRIPTION OF THE INTENDED SEQUENCE OF MAJOR ACTIVITIES WHICH WILL DISTURB SOILS FOR MAJOR PORTIONS OF THE CONSTRUCTION SITE, SUCH AS EXCAVATION AND GRADING:

- 1. UNCLASSIFIED EXCAVATION
- 2. 4" AGGREGATE BASE FOR SHOULDERS

AREA OF CONSTRUCTION SITE

THE TOTAL AREA OF THE CONSTRUCTION SITE THAT WILL BE DISTURBED BY EXCAVATION AND OTHER ACTIVITIES IS LESS THAN ONE (1) ACRE.

DRAINAGE TRIBUTARIES AND SENSITIVE AREAS RECEIVING RUNOFF FROM THIS CONSTRUCTION SITE

THE CONSTRUCTION SITE DRAINS INTO STORM SEWERS THAT OUTLET INTO THE WELCH CREEP

SEDIMENTATION AND EROSION CONTROL NOTES

THE RESIDENT ENGINEER WILL PERFORM PERIODIC INSPECTION OF THE SITE TO IDENTIFY POTENTIAL SEDIMENT AND EROSION

ALL SOIL EROSION AND SEDIMENT CONTROL PRACTICES ARE REFERENCED FROM THE ILLINOIS URBAN MANUAL, UNLESS OTHERWISE STATED

THE DRAWINGS. SPECIFICATIONS AND SPECIAL PROVISIONS WILL ENSURE THAT EXISTING VEGETATION IS PRESERVED WHERE ATTAINABLE AND DISTURBED PORTIONS OF THE SITE WILL BE STABILIZED. STABILIZATION PRACTICES INCLUDE SEEDING AND MULCHING AS DIRECTED BY THE ENGINEER. STABILIZATION MEASURES SHALL BE INITIATED WITHIN SEVEN (7) DAYS OF DISTUBBANCE

DESCRIPTION OF STABILIZATION PRACTICES DURING CONSTRUCTION:

DURING CONSTRUCTION, AREAS OUTSIDE THE CONSTRUCTION LIMITS AS OUTLINED PREVIOUSLY HEREIN SHALL BE PROTECTED. THE CONTRACTOR SHALL NOT USE THIS AREA FOR STAGING (EXCEPT AS DESCRIBED ON THE PLANS AND DIRECTED BY THE ENGINEER), PARKING OF VEHICLES OR CONSTRUCTION EQUIPMENT, STORAGE OF MATERIALS, OR OTHER CONSTRUCTION BELATED ACTIVITIES

- 1. WITHIN THE CONSTRUCTION LIMITS, AREAS WHICH MAY BE SUSCEPTIBLE TO EROSION AS DETERMINED BY THE ENGINEER SHALL REMAIN UNDISTURBED UNTIL FULL SCALE CONSTRUCTION IS UNDERWAY TO PREVENT UNNECESSARY SOIL EROSIOF
- 2. FARTH STOCKPILES SHALL BE TEMPORABILY SEEDED, AT THE CONTRACTORS EXPENSE. IF THEY ARE TO REMAIN LINUSED FOR MORE THAN FOURTEEN DAYS
- 3. AS CONSTRUCTION PROCEEDS, THE CONTRACTOR SHALL INSTITUTE THE FOLLOWING AS DIRECTED BY THE ENGINEER:
- A. PLACE TEMPORARY EROSION CONTROL FACILITIES AT LOCATIONS SHOWN ON THE PLANS
- B. EXCAVATED AREAS AND EMBANKMENT AREAS SHALL BE PERMANENTLY SEEDED IMMEDIATELY AFTER FINAL GRADING. IF NOT, THEY SHALL BE TEMPORARILY SEEDED, AT THE CONTRACTOR'S COST, IF NO CONSTRUCTION ACTIVITY IN THE AREA IS PLANNED FOR SEVEN DAYS
- 4. CONSTRUCTION FOUIPMENT SHALL BE STORED AND FUELED ONLY AT DESIGNATED LOCATIONS, ALL NECESSARY MEASURES SHALL BE TAKEN TO CONTAIN ANY FUEL OR POLLED INTENT IN ACCORDANCE WITH EPA WATER QUALITY REGULATIONS, LEAKING EQUIPMENT OR SUPPLIES SHALL BE IMMEDIATELY REPAIRED OR REMOVED FROM THE SITE.
- 5. SEDIMENT COLLECTED DURING CONSTRUCTION OF THE VARIOUS TEMPORARY EROSION CONTROL SYSTEMS SHALL BE DISPOSED OF OFF SITE ON A REGULAR BASIS AS DIRECTED BY THE ENGINEER. THE COST OF THIS MAINTENANCE SHALL
- 6. THE TEMPORARY EROSION CONTROL SYSTEMS SHALL BE REMOVED AS DIRECTED BY THE ENGINEER AFTER USE IS NO LONGER NEEDED OR NO LONGER FUNCTIONING. THE COST OF THIS REMOVAL SHALL BE INCIDENTAL TO THE CONTI

DESCRIPTION OF STRUCTURAL PRACTICES AFTER FINAL GRADING:

TEMPORARY EROSION CONTROL SYSTEMS SHALL BE LEFT IN PLACE WITH PROPER MAINTENANCE UNTIL PERMANENT EROSION CONTROL IS IN PLACE AND WORKING PROPERLY AND ALL PROPOSED TURF AREAS ARE SEEDED AND ESTABLISHED.

ONCE PERMANENT EROSION CONTROL SYSTEMS AS PROPOSED IN THE PLANS ARE FUNCTIONAL AND ESTABLISHED, TEMPORARY ITEMS SHALL BE REMOVED, CLEANED UP, AND DISTURBED TURF RESEEDED.

MAINTENANCE AFTER CONSTRUCTION

CONSTRUCTION IS COMPLETE AFTER FINAL ACCEPTANCE BY THE ILLINOIS DIVISION OF AERONAUTICS. MAINTENANCE UP TO THIS DATE WILL BE REQUIRED BY THE CONTRACTOR.

	SUMMARY OF QUA	NTITIES		
BASE BID - C	VERLAY SOUTHEAST QUADRANT PERIMETER ROADWA	AYS		
ITEM NO.	DESCRIPTION	UNIT	ESTIMATED QUANTITY	RECORD QUANTITY
AR150510	ENGINEERS FIELD OFFICE	LS	1	
AR152410	UNCLASSIFIED EXCAVATION	CY	525	
AR152540	SOIL STABILIZATION FABRIC	SY	455	
AR156520	INLET PROTECTION	EACH	6	
AR162570	DETECTOR LOOP	LS	1	
AR201661	CLEAN & SEAL BITUMINOUS CRACKS	LF	3550	
AR201663	SAND MIX CRACK REPAIR	LF	970	
AR208515	POROUS GRANULAR EMBANKMENT	CY	152	
AR208604	4" AGGREGATE BASE COURSE	SY	1440	
AR208610	10" AGGREGATE BASE COURSE	SY	755	
AR401610	BITUMINOUS SURFACE COURSE	TON	670	
AR401650	BITUMINOUS PAVEMENT MILLING	SY	6050	
AR401900	REMOVE BITUMINOUS PAVEMENT	SY	610	
AR401915	REM & REP BIT PAVEMENT - TYPE A	SY	320	
AR401916	REM & REP BIT PAVEMENT - TYPE B	SY	455	
AR403610	BITUMINOUS BASE COURSE	TON	140	
AR602510	BITUMINOUS PRIME COAT	GAL	200	
AR603510	BITUMINOUS TACK COAT	GAL	965	
AR620520	PAVEMENT MARKING - WATERBORNE	SF	275	
ADDITIVE AL	TERNATE 1 - PAVEMENT RECONSTRUCTION OF A POR	TION OF EAST	ACCESS ROAD	
ITEM NO.	DESCRIPTION	UNIT	ESTIMATED QUANTITY	RECORD QUANTITY
AS152410	UNCLASSIFIED EXCAVATION	CY	411	
AS152540	SOIL STABILIZATION FABRIC	SY	672	
AS208515	POROUS GRANULAR EMBANKMENT	CY	224	
AS208610	10" AGGREGATE BASE COURSE	SY	672	
AS401610	BITUMINOUS SURFACE COURSE	TON	70	
AS401900	REMOVE BITUMINOUS PAVEMENT	SY	610	
AS403610	BITUMINOUS BASE COURSE	TON	140	
AS602510	BITUMINOUS PRIME COAT	GAL	200	
AS603510	BITUMINOUS TACK COAT	GAL	185	

REPLACE EXISTING DETECTOR LOOP NEW CABLES IN EXISTING 3/4" GRS CONDUIT (NO. & SIZE OF CABLES AS REQUIRED BY THE GATE DRIVER MANUFACTURER) CONNECT CABLES INSIDE GATE DRIVER EXISTING FENCE EXISTING DISCONNECT EXISTING CONDUIT DIRECT BURY FOR POWER AND COMMUNICATION EXISTING GATE DRIVER

- NOTES

NOTES:

- 1. LOOP LEADS ARE LIMITED TO 100 FEET.
- 2. LOOP LEADS MUST HAVE FOUR (4) TWISTS PER FOOT
- LEADS FROM OTHER LOOPS.

CAUTION

- DO NOT SPLICE WIRE

TYPICAL LAYOUT FOR LOOP:

SPECIFIED LOOP DIMENSIONS PLUS SLOT FOR LEAD CONDUIT



INLET PROTECTION (END SECTION)

NOT TO SCALE

IDOT STANDARD 280001-07



INLET PROTECTION (INLET/MANHOLES - IN TURF)

NOT TO SCALE IDOT STANDARD 280001-07

NOTES FOR INLET PROTECTION DETAILS

- FILTER WRAP TO BE PLACED IN ALL SLOPE BOX INLETS, INLETS, MANHOLES, TRENCH DRAINS AND CATCH BASINS LOCATED IN PAVED AREAS AND NONPAVED AREAS.
- FABRIC SHALL BE IN CONFORMANCE WITH ARTICLE 1080.03 OF THE IDOT STANDARD 2. SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION 2016.
- FABRIC SHALL OVERLAY FRAME BY 2" (MIN.). 3.
- CONTRACTOR SHALL CLEAR DEBRIS AND SILT AS REQUIRED FROM FABRIC TO MAINTAIN DRAINAGE THROUGH THE STRUCTURE.
- FABRIC SHALL REMAIN IN PLACE UNTIL COMPLETION OF PAVEMENT REHABILITATION. 5.
- COST OF FILTER WRAP AND MAINTENANCE SHALL BE CONSIDERED INCIDENTAL TO THE CONTRACT. 6.







GENERAL NOTES

- THE SUGGESTED SEQUENCE OF CONSTRUCTION SHOWN IS INTENDED TO ALLOW FOR THE ORDERLY CONSTRUCTION OF THE PROPOSED IMPROVEMENTS WHILE MAINTAINING VEHICLE ACCESS AT ALL TIMES. THE PHASING SHOWN IS A SUGGESTED SEQUENCE OF CONSTRUCTION ONLY. THIS SEQUENCE MAY BE MODIFIED HOWEVER, ALTERNATE STAGING PLANS MUST MAINTAIN AIRPORT OPERATIONS TO THE SATISFACTION OF THE AIRPORT MANAGER AND RESIDENT ENGINEER AND BE APPROVED BY IDOT AERONAUTICS AND FEDERAL AVIATION ADMINISTRATION
- 2. ALL OPERATIONS SHALL BE IN CONFORMANCE WITH AC 150/5370-2 (LATEST EDITION) "OPERATIONAL SAFETY ON
- CONTRACTOR'S EQUIPMENT SHALL BE STORED IN THE EQUIPMENT AND MATERIAL STORAGE/STAGING AREA WHEN CONSTRUCTION IS NOT IN PROGRESS. NO EXCEPTIONS FOR SLOW MOVING EQUIPMENT SHALL BE ALLOWED
- THE AIRPORT MANAGER SHALL HAVE FINAL SAY IN THE APPROVAL OF THE CONSTRUCTION OPERATING PHASING AND SEQUENCE AS IT RELATES TO PEDESTRIAN AND VEHICULAR SAFETY
- ALL EXISTING PAVEMENTS, DRIVES OR ANY OTHER AREAS USED AS A HAUL ROAD OR STORAGE AREA BY THE CONTRACTOR SHALL BE RESTORED IN KIND TO THEIR PRE-CONSTRUCTION CONDITION OR TO THE SATISFACTION OF THE RESIDENT ENGINEE THE AND AIRPORT MANAGER. THE COST OF MAINTAINING, REPARING OR CONSTRUCTING THESE PAVEMENTS AND AREAS SHALL BE INCIDENTAL TO THE CONTRACT. EXISTING AREAS OUTSIDE THE PROJECT LIMITS WHICH ARE DISTURBED BY THE CONTRACTOR'S OPERATIONS SHALL BE RESTORED BY HIM AT HIS EXPENSE TO THE SATISFACTION OF THE RESIDENT ENGINEER AND THE AIRPORT MANAGER.
- THE CONTRACTOR SHALL KEEP ALL TRUCKS, EQUIPMENT AND MATERIALS OFF OF THE TENANT PARKING LOTS AND DRIVEWAYS OUTSIDE OF THE PROJECT LIMITS EXCEPT AS SHOWN OR WITH THE PRIOR PERMISSION OF THE ENGINEER AND AIRPORT
- WORK PERFORMED BY THE CONTRACTOR OUTSIDE OF DAYLIGHT HOURS SHALL BE DONE UNDER SUFFICIENT ARTIFICIAL LIGHTING TO ALLOW FOR PROPER CONSTRUCTION METHODS AND INSPECTIONS. LIGHT SHALL CONSIST OF MOVABLE POLE MOUNTED FLOODLIGHTS AND/OR SPOTLIGHTS OF SUFFICIENT NUMBER TO ILLUMINATE THE WORK AREA. VEHICLE HEADLIGHTS WILL BE ALLOWED ONLY IN ADDITION TO OTHER LIGHTS MENTIONED ABOVE LIGHTING SHALL BE AS APPROVED BY THE ENGINEER AND SHALL NOT BE USED IF THEY AFFECT FLIGHT SAFETY. CONTRACTOR'S WORK HOURS SHALL BE IN ACCORDANCE WITH LOCAL ORDINANCES.
- 8. THE CONTRACTOR WILL BE REQUIRED TO HAVE A SWEEPER AVAILABLE FOR USE AT ALL TIMES. MATERIAL TRACKED ON TO THE PAVEMENT SHALL BE CONTINUALLY REMOVED WITH SAID SWEEPER. THIS SWEEPING SHALL NOT BE PAID FOR SEPARATELY BUT SHALL BE CONSIDERED INCIDENTAL TO THE CONTRACT
- 9. MATERIALS REMOVED FROM THE PROJECT WILL BECOME PROPERTY OF THE CONTRACTOR AND SHALL BE DISPOSED OF OFF AIRPORT PROPERTY, UNLESS NOTED OTHERWISE
- 10. PAYMENT FOR TRAFFIC CONTROL INCLUDING, BUT NOT LIMITED TO BARRICADES, CONSTRUCTION FENCE, SIGNING, , ETC. SHALL NOT BE PAID SEPARATELY, BUT SHALL BE CONSIDERED INCIDENTAL TO THE CONTRACT. BARRICADES SHALL HAVE FLASHING LIGHT(S) AND CONFORM TO IDOT STANDARD 701901-07, TYPE II AND TYPE III SIGNS SHALL BE CONSIDERED INCIDENTAL TO THE CONTRACT
- 11. THE CONTRACTOR SHALL CONTACT THE AIRPORT MANAGER THROUGH THE RESIDENT ENGINEER TEN (10) WORKING DAYS IN ADVANCE OF THE START OF CONSTRUCTION SO THAT THE APPROPRIATE NOTAMS MAY BE ISSUED
- 12. IN THE CASE OF AN EMERGENCY, CONTRACTOR SHALL NOTIFY AIRPORT MANAGER AND THE RESIDENT ENGINEER IMMEDIATELY.
- 13. DURING ADVERSE WEATHER. THE CONTRACTOR SHALL MAKE PROVISIONS FOR ACCESS TO THE WORK AT NO ADDITIONAL COST TO THE CONTRACT. NO EXTENSION OF CONTRACT TIME WILL BE CONSIDERED FOR DELAYS DUE TO LACK OF ADEQUATE ACCESS TO THE WORK
- 14. AURORA MUNICIPAL AIRPORT WILL BE IN OPERATION DURING THE CONSTRUCTION OF THIS PROJECT. COORDINATION OF WORK WITH THE AIRPORT IS MANDATORY SO AS TO MINIMIZE IMPACTS ON AIRPORT OPERATIONS
- 15. APPROXIMATE LOCATION OF HAUL ROUTES ON THE AIRPORT SITE ARE SHOWN ON THE GENERAL PROJECT LAYOUT AND THE PHASING PLANS. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO COORDINATE OFF-SITE HAUL ROUTES (STATE HIGHWAYS, COUNTY ROADS OR CITY STREETS) WITH THE APROPRIATE OWNER WHO HAS JURISDICTION OVER THE AFFECTED ROUTE. ON-SITE ROADS USED AS HAUL ROUTES SHALL BE MAINTAINED BY THE CONTRACTOR AND SHALL BE RESTORED AT THE CONTRACTOR'S EXPENSE TO THEIR ORIGINAL CONDITION UPON COMPLETION OF BEING USED AS A HAUL BOUTE. THE BEFORE AND AFTER CONDITION OF ON-SITE HAUL BOUTES SHALL BE JOINTLY INSPECTED AND DETERMINED BY THE CONTRACTOR AND THE ENGINEER. FENCING, DRAINAGE, GRADING AND OTHER MISCELLANEOUS CONSTRUCTION REQUIRED TO CONSTRUCT TEMPORARY HAUL ROUTES OR ACCESS POINTS ON THE AIRPORT WILL BE THE CONTRACTOR'S TOTAL RESPONSIBILITY AND SHALL BE APPROVED BY THE ENGINEER PRIOR TO THE WORK. ALL ON-SITE ACCESS ROADS TO AIRPORT FACILITIES SHALL REMAIN OPEN AND MAINTAINED AT ALL TIMES.
- 16. MOBILIZATION/EQUIPMENT STORAGE AREA WILL BE MADE AVAILABLE FOR CONTRACTOR'S MOBILIZATION AND STORAGE AS SHOWN ON THE PLANS. THIS AREA SHALL BE RESTORED TO THE ORIGINAL CONDITION UPON COMPLETION OF THE PROJECT AT THE CONTRACTOR'S EXPENSE
- 17. LOCATION OF KNOWN EXISTING AIRPORT UNDERGROUND CABLES ARE SHOWN ON THE PLANS AND MUST BE VERIFIED BY THE CONTRACTOR. REPAIR OF DAMAGED CABLE MUST BE STARTED IMMEDIATELY AND CONTINUED UNTIL COMPLETED. ALL SUCH REPAIRS SHALL BE IN ACCORDANCE WITH THE SPECIFICATIONS, OR AS DIRECTED BY THE OWNER OF THE CABLE OR FACILITY, AND SHALL BE IN ACCORDANCE WITH ITS PECIFICATIONS, ON AS DIRECTED BY THE OWNER OF THE CARLE OF FACILITY, AND SHALL BE AT THE CONTRACTOR'S EXPENSE. IF FAA CABLES ARE DAMAGED, REPAIRS SHALL BE DONE FROM PREVIOUS EXISTING TERMINATION POINT TO PREVIOUS EXISTING TERMINATION POINT IN ACCORDANCE WITH FAA REQUIREMENTS AND IN THE PRESENCE OF A FAA REPRESENTATIVE. THE OWNER MAY ELECT TO HAVE THE REPAIR PERFORMED BY OTHERS IN WHICH CASE THE CONTRACTOR SHALL BE RESPONSIBLE FOR PAYING THE INCURRED COSTS OF
- 18. COORDINATION MEETINGS THE CONTRACTOR SHALL CONDUCT WEEKLY COORDINATION MEETINGS TO DISCUSS WORK AREAS AND SCHEDULING, ETC. WITH THE ENGINEER, AIRPORT OPERATIONS, FAA, AND OTHER APPROPRIATE OFFICIALS. MINUTES FROM THE WEEKLY MEETINGS SHALL BE PREPARED BY THE CONTRACTOR, FURNISHED TO ALL ATTENDEES PRIOR TO THE SUBSEQUENT MEETING, AND KEPT ON FILE AT THE FIELD OFFICE. THE COORDINATION MEETING COSTS SHALL BE CONSIDERED INCIDENTAL TO THE PROJECT.
- 19. THE CONTRACTOR SHALL PROVIDE THE PHONE NUMBERS OF THREE PERSONNEL, INCLUDING THE PROJECT SUPERINTENDENT, WHO MAY BE CONTACTED IN AN EMERGENCY. PERSONNEL SHALL BE ON CALL 24 HOURS PER DAY FOR MAINTAINING AIRPORT HAZARD LIGHTING AND BARRICADES.
- 20. COORDINATION BY THE CONTRACTOR WITH THE EXISTING UTILITIES SHALL BE COMPLETED BEFORE CONSTRUCTION IS STARTED. CONTRACTOR IS REFERRED TO SECTION 50-17 OF THE SPECIAL PROVISIONS FOR SPECIFIC REQUIREMENTS. THE LOCATION OF UNDERGROUND UTILITIES AS INDICATED ON THE PLANS HAS BEEN OBTAINED FROM EXISTING RECORDS. NEITHER THE OWNER OR THE DESIGN ENGINEER ASSUME ANY RESPONSIBILITY WHATSOEVER IN RESPECT TO THE ACCURACY, COMPLETENESS OR SUFFICIENCY OF THE INFORMATION. THERE IS NO GUARANTEE, EITHER EXPRESSED OR IMPLIED THAT THE LOCATIONS, SIZE AND TYPE MATERIAL OF EXISTING UNDERGROUND UTILITIES AS INDICATED ARE REPRESENTATIVE OF THOSE TO BE ENCOUNTERED DURING CONSTRUCTION. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO DETERMINE THE ACTUAL LOCATION OF ALL SUCH FACILITIES, INCLUDING SERVICE CONNECTIONS TO UNDERGROUND UTILITIES. PRIOR TO CONSTRUCTION, THE CONTRACTOR SHALL NOTIFY THE UTILITY COMPANY OF HIS OPERATIONAL PLANS. THE CONTRACTOR SHALL MAKE ARRANGEMENTS FOR DETAILED INFORMATION AND ASSISTANCE IN LOCATING UTILITIES. IN THE EVENT AN UNEXPECTED UTILITY INTERFERENCE IS ENCOUNTERED DURING CONSTRUCTION, THE CONTRACTOR SHALL IMMEDIATELY NOTIFY THE UTILITY COMPANY, THE RESIDENT ENGINEER AND THE AIRPORT MANAGER. ANY SUCH MAINS AND/OR SERVICES DISTURBED BY THE CONTRACTOR'S OPERATIONS SHALL BE RESTORED IMMEDIATELY AT HIS EXPENSE TO THE SATISFACTION OF THE RESIDENT ENGINEER AND AIRPORT MANAGER

	TABLE 1 - CRITICAL POINTS				
POINT	APPROXIMATE ELEVATION OF GROUND (NAV 83)	ANTICIPATED EQUIPMENT AND HEIGHT	APPROXIMATE ELEVATION OF EQUIPMENT (NAV 83)	LATITUDE (NAD 83)	LONGITUDE (NAD 83)
CP1	704.4	SEMI/DUMP TRUCK - 25'	729.4	41°46'06.03"	88°27'46.90"
CP2	699.9	SEMI/DUMP TRUCK - 25'	724.9	41°45'57.17"	88°27'58.80"



21. CCONTRACTOR WILL BE REQUIRED TO PUT AIRPORT FLAGS OR A WORKING BEACON IGHT ON ALL FOUIPMENT AT ALL TIMES DUBING CONSTRUCTION. SEE FLAG DETAIL

22. PREPARE A SAFETY PLAN COMPLIANCE DOCUMENT. THE SAFETY PLAN COMPLIANCE DOCUMENT (SPCD) DETAILS HOW THE CONTRACTOR WILL COMPLY WITH THE CSPF ALSO, IT WILL NOT BE POSSIBLE TO DETERMINE ALL SAFETY PLAN DETAILS (FOR EXAMPLE SPECIFIC HAZARD EQUIPMENT AND LIGHTING, CONTRACTOR'S POINTS OF CONTACT, CONSTRUCTION EQUIPMENT HEIGHTS) DURING THE DEVELOPMENT OF THE CSPP. THE SUCCESSEUL CONTRACTOR MUST DEFINE SUCH DETAILS BY PREPARING AND SPCD THAT THE AIRPORT OPERATOR REVIEWS FOR APPROVAL PRIOR TO ISSUANCE OF A NOTICE-TO-PROCEED. THE SPCD IS A SUBSET OF THE CSPP. SIMILAR TO HOW A SHOP DRAWING REVIEW IS A SUBSET TO THE TECHNICAL SPECIFICATIONS.

CONTRACTOR SHALL PLAN AND PERFORM HIS WORK SO AS NOT TO INTERFERE ON THACTOR SHALL PLAN AND PERFORM HIS WORK SO AS NOT TO INTERFERE OR HINDER THE PROGRESS, WORK OR HAUL ROAD ACCESS OF OTHER CONTRACTORS. THE PRIME CONTRACTOR WILL BE RESPONSIBLE TO COORDINATE CONSTRUCTION ACTIVITIES AND ACCESS BETWEEN ALL ON-SITE CONTRACTORS SUBCONTRACTORS. IT IS ANTICIPATED THE FOLLOWING PROJECTS MAY BE UNDER CONSTRUCTION CONCURRENTLY WITH THIS PROJECT. NO ADDITIONAL COMPENSATION SHALL BE CONSIDERED FOR ANY EFFORTS TO COORDINATE AND ACCESS THE SITE DUE TO ADJACENT CONSTRUCTION

INSTALL AIRFIELD LIGHTING CONTROL AND MONITORING SYSTEM (ALCMS) INCLUDING REMOVING EXISTING SYSTEM REHABILITATE SOUTHWEST AUTO PARKING LOT AT SOUTH APRON



CONSTRUCTION EQUIPMENT AND TRUCK SIGNAL FLAG

NOT TO SCAL

IL IL IL S.	IL. CONTRACT: AU068 IL. LETTING ITEM: 06A IL. PROJECT: ARR-4636 S.B.G. PROJECT: N/A				
su	SURVEY BOOK #				
N	UMBER	REVIS	SIONS BY	DATE	
	0		1	2	
	THIS B. AT FU	AR IS LL SC/	EQUAL ALE (34	TO 2" 4X22).	
		OVERLAT SOUTHEAST QUADRANT PERIMETER RUADWATS	SEQUENCE OF CONSTRUCTION	GENERAL NOTES AND DETAILS	
Copyright CMT, Inc.	CANT CRAWFORD, MURPHY & TILLY, NC.	CONSUL I ING ENGINEERS License No. 184-000613		AURORA MUNICIPAL AIRPORT	
DE	SIGN BY:		•	KWS	
DF	RAWN BY:	IY:		JRO KWS	
AF	PROVED	BY:		DKP	
DA	DATE: 03/02/2018				
JC	JOB No: 17285-03-00				
	FINAL				
SI	HEET	5 O	F 9	SHEETS	



UPDATE BY: Kris Salv LAYOUT: Lavout1

Monday, March 26, 2018 12:23:16 PM





EXISTING ELECTRICAL/STORM/SANITARY/TELEPHONE MANHOLE OR EXISTING WATER VALVE VAULT

EXISTING ELECTRICAL HANDHOLE

EXISTING FLARED END SECTION

EXISTING FLUSH MOUNTED FIRE HYDRANT

EXISTING WATER VALVE

EXISTING UTILITY PEDESTAL

PAVEMENT CORE/BORE AND NUMBER

REMOVE BITUMINOUS PAVEMENT (AR401900)

REM & REP BIT PAVEMENT - TYPE A (AR401915) AND TYPE B (AR401916)

1. THE INFORMATION SHOWN ON THESE PLANS HAS BEEN OBTAINED FROM AVAILABLE RECORDS. NEITHER THE OWNER NOR THE ENGINEER ASSUMES ANY RESPONSIBILITY WHATSOEVER IN RESPECT TO THE ACCURACY OR SUFFICIENCY OF THE INFORMATION AND THERE IS NO GUARANTEE EITHER EXPRESSED OR IMPLIED THAT THE CONDITIONS INDICATED ARE REPRESENTATIVE OF THOSE TO BE ENCOUNTERED IN THE FIELD. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO VISIT THE SITE AND ACQUAINT HIMSELF WITH THE EXISTING CONDITIONS.

2. THE EXISTING BITUMINOUS PAVEMENT SHALL BE SAWCUT AT THE MILLING LIMITS TO PROVIDE A CLEAN VERTICAL FACE. COST FOR SAWCUT SHALL BE INCLUDED IN

3. PRIOR TO PAVING OPERATIONS, THE FINAL MILLED SURFACE SHALL BE SWEEPED CLEAN AND THE CONTRACTOR AND THE RESIDENT ENGINEER SHALL INSPECT THE FINAL SURFACE. ALL LOOSE PIECES SHALL BE REMOVED. ALL CRACKS TO BE WIDER THAN 1" SHALL BE REPAIRED UNDER ITEM AR201663, SAND MIX CRACK REPAIR. OTHER CRACKS AS NOTED DURING THE INSPECTION SHALL BE SEALED UNDER ITEM AR201661, CLEAN AND SEAL BITUMINOUS CRACKS.

4. EXACT LIMITS OF REMOVE AND REPLACE BITUMINOUS PAVEMENT - TYPE A AND TYPE B SHALL BE DETERMINED IN THE FIELD WITH THE APPROVAL OF THE RESIDENT ENGINEER. MINIMUM WIDTH OF REPAIRS SHALL BE NO LESS THAN 3'.

5. REMOVE AND REPLACE AGGREGATE BASE SHALL BE INSTALLED ONLY AS DIRECTED BY THE ENGINEER FOR CONSTRUCTION OF REMOVE AND REPLACE

PAVEMENT THICKNESS INFORMATION FROM CORES COMPLETED NOVEMBER 2017

BORING B-1 7" BITUMINOUS MATERIALS (201) 8" AGGREGATE BASE COURSE (CRUSHED STONE) 12" CLAYEY SANDY SILT

AGGREGATE BASE COURSE (CRUSHED STONE) CLAYEY SANDY SILT

6" BITUMINOUS MATERIALS (201) 8" AGGREGATE BASE COURSE (CRUSHED STONE) 0" CLAYEY SANDY SILT

6.75" BITUMINOUS MATERIALS (201) 7.25" AGGREGATE BASE COURSE (CRUSHED STONE)

4.25" BITUMINOUS MATERIAL 7.25" AGGREGATE BASE COURSE (CRUSHED STONE) 12" CLAYEY SANDY SILT

IL. CONTRACT: AU068 IL. LETTING ITEM: 06A IL. PROJECT: ARR-4636 S.B.G. PROJECT: N/A				
	REVIS	SIONS	;	
NUMBER	B	ΙY	DATE	
0		1	2	
THIS B. AT FU	AR IS LL SCA	EQUAL ALE (34	TO 2" 4X22).	
Aurora Municipal Airport Aurora, Illinois Overlay Southeast Quadrant Perimeter Roadways		EXISTING CONDITIONS AND PROPOSED REMOVALS SHEET 2		
CIANT CONTRACTION OF CONTRACTION.	LUNSUL ING ENGINEERS License No. 184-000613		AURORA MUNICIPAL AIRPORT	
DESIGN BY: KWS				
DRAWN BY:			JRO	
APPROVED	BY:		DKP	
DATE: 03/02/2018				
JOB No: 17285-03-00				
FINAL				

