

SUMMARY OF QUANTITIES

← URBAN →

CODE NUMBER	PAY ITEMS	UNIT	TOTAL QUANTITY	ROADWAY	TRAFFIC	LIGHTING	SIDEWALK	EMERGENCY
				FED 80%	SIGNALS FED 80%		STATE 50%	PREEMPTION
				STATE 20%	STATE 15% CITY 5%		CITY 100%	CITY 100%
				J000-2A	Y031-1F	Y030-1E	SFTY-1B	Y031-3D
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	466		466			
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	406		406			
20200100	EARTH EXCAVATION	C. Y.	7,757	7,757				
20400800	FURNISHED EXCAVATION	C. Y.	21	21				
20800150	TRENCH BACKFILL	C. Y.	1,274	1,274				
21101625	TOPSOIL FURNISH AND PLACE 6"	S. Y.	8,179	8,179				
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	152	152				
25000500	PHOSPHOROUS FERTILIZER NUTRIENT	POUND	152	152				
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	152	152				
25000910	SEEDING, CLASS 1 (MODIFIED)	ACRE	1.7	1.7				
25100115	MULCH, METHOD 2	ACRE	2.1	2.1				
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	37	37				
28000300	TEMPORARY DITCH CHECKS	EACH	11	11				
28000400	PERIMETER EROSION BARRIER	FOOT	1,174	1,174				
28000500	INLET AND PIPE PROTECTION	EACH	55	55				
31100500	SUB-BASE GRANULAR MATERIAL, TYPE A 6"	S. Y.	605	605				
31102100	SUB-BASE GRANULAR MATERIAL, TYPE C 4"	S. Y.	658	658				
35100300	AGGREGATE BASE COURSE, TYPE A 4"	S. Y.	933	933				
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GAL.	487	487				
42000100	PORTLAND CEMENT CONCRETE PAVEMENT 6"	S. Y.	459	459				
42000411	PORTLAND CEMENT CONCRETE PAVEMENT 9 1/2" (JOINTED)	S. Y.	6,813	6,813				
42001200	PAVEMENT FABRIC	S. Y.	225	225				
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	S. Y.	775	775				
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	S. F.	10,659				10,659	
44000075	BITUMINOUS SURFACE REMOVAL (COLD MILLING)	S. Y.	5,195	5,195				
44000100	PAVEMENT REMOVAL	S. Y.	4,808	4,808				
44000200	DRIVEWAY PAVEMENT REMOVAL	S. Y.	1,473	1,473				
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	2,046	2,046				
44000600	SIDEWALK REMOVAL	S. F.	6,773	6,773				
44201476	CLASS C PATCHES, TYPE II	S. Y.	33	33				
44201480	CLASS C PATCHES, TYPE IV	S. Y.	28	28				
44201980	CLASS D PATCHES, TYPE IV	S. Y.	53	53				
54215547	METAL END SECTIONS 12"	EACH	2	2				
5421D012	PIPE CULVERTS, CLASS D, TYPE 1 12" (TEMPORARY)	FOOT	77	77				
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	376	376				
550A0070	STORM SEWERS, CLASS A, TYPE 1 15"	FOOT	23	23				
550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	619	619				
550A0360	STORM SEWERS, CLASS A, TYPE 2 15"	FOOT	122	122				
550A0380	STORM SEWERS, CLASS A, TYPE 2 18"	FOOT	150	150				

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	LASALLE	95	4
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

* FAP ROUTE 653 (ROUTE 18 COUPLE)
** SECTION (7)R, RS-2; (8)R, RS-1

2/24/2006 I:\temporary\Streator 2-24-06\05393CVR3.dgn