

# SCHEDULE OF QUANTITIES

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	**	LASALLE	95	14
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

\* FAP ROUTE 653 (ROUTE 18 COUPLE)  
\*\* SECTION (7)R, RS-2; (8)R, RS-1

<p>70300220 TEMPORARY PAVEMENT MARKING-LINE 4" (CONT)</p> <p>YELLOW WEST MAINLINE STAGE 2 RT. STA. 97+02-113+91</p> <p>BRIDGE STREET AT WASSON STAGE 2 11'-0" LT. STA. 2200+08-2203+67</p> <p>MAIN STREET AT WASSON STAGE 1 8'-0" LT. STA. 404+59-407+44 (DOUBLE YELLOW)</p> <p style="text-align: right;">SUB-TOTAL 3,129.4</p> <p style="text-align: right;">TOTAL 4,356.2</p>	FOOT	<p>78003110 PREFORMED PLASTIC PAVEMENT MARKING, TYPE B-LINE 4"</p> <p>SKIP-DASHED WHITE (2' STRIP-6' SKIP) WEST MAIN STREET CONNECTOR RT. STA. 999+00 (TURN LANE TAPER)</p> <p>SOLID WHITE MAIN STREET AT WASSON 12'-12" LT. STA. 401+28+403+98</p> <p>SOLID YELLOW WEST MAINLINE RT. STA. 100+90-103+ (AROUND ISLAND)</p> <p>WASSON STREET LT. STA. 2402+90-2403+37.5 (CORNER ISLAND) RT. STA. 2407+87-2408+26 (CORNER ISLAND)</p> <p>MAIN STREET AT WASSON 4'-0" RT. STA. 404+95-408+00 (DOUBLE YELLOW)</p> <p>3'X1.5' SOLID WHITE MAIN STREET AT WASSON RT. STA. 401+13.6-403+47.8 (PARKING STALLS)</p>	FOOT	<p>78003140 PREFORMED PLASTIC PAVEMENT MARKING, TYPE B-LINE 8"</p> <p>SOLID WHITE WEST MAIN STREET CONNECTOR CL LT. STA. 999+04-1000+24.3</p> <p>BRIDGE STREET AT WASSON CL STA. 2202+86-2204+63.8</p> <p>WASSON STREET 1' LT. STA. 2406+85.6-2408+09 11' RT. STA. 2406+85.6-2407+86.8</p> <p style="text-align: right;">TOTAL 546.0</p> <p>78003150 PREFORMED PLASTIC PAVEMENT MARKING, TYPE B-LINE 12"</p> <p>SOLID YELLOW WEST MAINLINE LT. STA. 100+90-103+ (ISLAND DIAGONALS)</p> <p>WASSON STREET LT. STA. 2402+90-2403+37 (ISLAND DIAGONALS) RT. STA. 2407+87-2408+26 (ISLAND DIAGONALS)</p> <p>MAIN STREET AT WASSON LT. STA. 401+28-403+64 (TAPER DIAGONALS)</p> <p style="text-align: right;">TOTAL 536.2</p> <p>78003180 PREFORMED PLASTIC PAVEMENT MARKING, TYPE B-LINE 24"</p> <p>WEST MAIN STREET CONNECTOR RT. STA. 1000+54 (STOP BAR)</p> <p>WEST BRIDGE STREET CONNECTOR RT. STA. 1102+20 (STOP BAR)</p> <p>ALLEY LT. STA. 500+29 (STOP BAR)</p> <p>MURDOCK STREET RT. STA. 303+46.9 (STOP BAR)</p> <p>WASSON STREET 47.7' RT. STA. 2403+00 (STOP BAR) RT. STA. 2407+98 (STOP BAR) LT. &amp; RT. STA. 2408+09 (STOP BAR) LT. STA. 2408+82 (STOP BAR)</p> <p>MAIN STREET AT WASSON LT. &amp; RT. STA. 404+93.4</p> <p style="text-align: right;">TOTAL 197.5</p>	FOOT
<p>70300250 TEMPORARY PAVEMENT MARKING-LINE 8"</p> <p>WHITE WASSON STREET STAGE 2 12' RT. STA. 2406+91-2408+26.7</p> <p>YELLOW WASSON STREET STAGE 2 12'-45" RT. STA. 2407+83-2408+25</p> <p style="text-align: right;">TOTAL 192.2</p>	FOOT	<p>78003130 PREFORMED PLASTIC PAVEMENT MARKING, TYPE B-LINE 6"</p> <p>SKIP-DASHED WHITE (10' DASH-30' SKIP) WEST MAINLINE CL STA. 100+35-100+90 CL STA. 103+11-113+16</p> <p>WEST BRIDGE STREET CONNECTOR CL STA. 1100+06-1102+19</p> <p>BRIDGE STREET AT WASSON CL STA. 2200+00-2202+86</p> <p>WASSON STREET CL STA. 2403+37-2406+86</p> <p>MAIN STREET AT WASSON 0'-8.7' LT. STA. 400+88-400+98 8.7' LT. STA. 404+94-407+10</p> <p>SKIP-DASHED YELLOW (10' DASH-30' SKIP) 1ST AVENUE CL BETWEEN WEST MAINLINE AND BRIDGE STREET</p> <p>SOLID WHITE WASSON STREET LT. &amp; RT. STA. 2408+18 (CROSSWALK) RT. STA. 2408+06 (CROSSWALK) LT. &amp; RT. STA. 2408+74 (CROSSWALK)</p> <p>MAIN STREET AT WASSON LT. &amp; RT. STA. 404+02 (CROSSWALK) LT. &amp; RT. STA. 404+86 (CROSSWALK)</p>	FOOT	<p>78100300 PRISMATIC CURB REFLECTOR</p> <p>WEST MAINLINE LT. STA. 103+00 (CORNER ISLAND)</p> <p>WASSON STREET LT. STA. 2403+00 (CORNER ISLAND) RT. STREETA 2408+20 (CORNER ISLAND)</p> <p style="text-align: right;">TOTAL 24</p> <p>78300100 PAVEMENT MARKING REMOVAL</p> <p>BRIDGE STREET (BETWEEN 1ST AVE. &amp; MURDOCK ST.) STAGE 1 EXISTING CL SKIP DASH</p> <p>1ST AVE. (BETWEEN WEST MAINLINE AND BRIDGE ST.) STAGE 2 EXISTING CL SKIP DASH WEST MAINLINE STA. 103+43 TO BRIDGE ST.</p> <p>WASSON STREET STAGE 1 EXISTING CL SKIP DASH STA. 2403+40-2406+41</p> <p style="text-align: right;">TOTAL 25.1</p>	FOOT
<p>70300280 TEMPORARY PAVEMENT MARKING-LINE 24"</p> <p>WHITE WASSON STREET STAGE 2 RT. STA. 2408+22 (STOP BAR) RT. STA. 2408+09 (STOP BAR) STAGE 3 LT. STA. 2408+13 (STOP BAR)</p> <p style="text-align: right;">TOTAL 57.1</p>	FOOT	<p>78003100 PREFORMED PLASTIC PAVEMENT MARKING, TYPE B-LETTERS AND SYMBOLS</p> <p>WHITE WEST MAINLINE CONNECTOR LT. STA. 999+24 (LEFT TURN ARROW) LT. STA. 1000+26 (LEFT TURN ARROW)</p> <p>BRIDGE STREET AT WASSON LT. STA. 2203+11 (LEFT TURN ARROW) LT. STA. 2203+61 (LEFT TURN ARROW) LT. STA. 2204+11 (LEFT TURN ARROW)</p> <p>WASSON STREET LT. STA. 2406+05 (LEFT TURN ARROW) RT. STA. 2406+05 (RIGHT TURN ARROW) RT. STA. 2406+79 (RIGHT TURN ARROW) LT. STA. 2406+88 (LEFT TURN ARROW)</p> <p style="text-align: right;">TOTAL 140.4</p>	FOOT	<p>78003100 PREFORMED PLASTIC PAVEMENT MARKING, TYPE B-LETTERS AND SYMBOLS</p> <p>WHITE WEST MAINLINE CONNECTOR LT. STA. 999+24 (LEFT TURN ARROW) LT. STA. 1000+26 (LEFT TURN ARROW)</p> <p>BRIDGE STREET AT WASSON LT. STA. 2203+11 (LEFT TURN ARROW) LT. STA. 2203+61 (LEFT TURN ARROW) LT. STA. 2204+11 (LEFT TURN ARROW)</p> <p>WASSON STREET LT. STA. 2406+05 (LEFT TURN ARROW) RT. STA. 2406+05 (RIGHT TURN ARROW) RT. STA. 2406+79 (RIGHT TURN ARROW) LT. STA. 2406+88 (LEFT TURN ARROW)</p> <p style="text-align: right;">TOTAL 140.4</p>	FOOT