

EARTHWORK SCHEDULES

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	LASALLE	95	17
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

- * FAP ROUTE 653 (ROUTE 18 COUPLE)
- ** SECTION (7)R, RS-2; (8)R, RS-1

LOCATION	EARTH EXCAVATION (C.Y.)	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE (25%) (C.Y.)	EMBANKMENT (C.Y.)	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-) (C.Y.)
WEST MAINLINE				
STAGE 1 TEMP STA. RT 97+50 - 10300	388	291	0	291
STAGE 1 TEMP STA. RT 111+11 - 113+50	120	90	0	90
SUB TOTAL:	508	381	0	381
STAGE 1 LT & RT STA. 103+47.26+00 - 109+00				
	2,263	1,697	427	1,270
SUB TOTAL:	2,263	1,697	427	1,270
STAGE 2 LT STA. 100+35.18 - 103+00				
	256	192	9	183
STAGE 2 LT STA. 109+50 - 113+01.30	692	519	0	519
SUB TOTAL:	948	711	9	702
STAGE 3 RT STA. 97+50 - 113+01.30				
	2,055	1,541	366	1,175
SUB TOTAL:	2,055	1,541	366	1,175
WEST MAINLINE CONNECTOR				
STAGE 2 STA. 999+71.19 - 1000+78	260	195	0	195
SUB TOTAL:	260	195	0	195
ALLEY				
STAGE 1 LT & RT STA. 500+50 - 501+68.2	114	86	6	80
SUB TOTAL:	114	86	6	80
WEST BRIDGE CONNECTOR				
STAGE 3 LT & RT STA. 1100+06 - 1102+00	809	607	0	607
SUB TOTAL:	809	607	0	607
WASSON STREET				
STAGE 1 RT STA. 2403+50 - 2408+25.26	445	334	0	334
SUB TOTAL:	445	334	0	334
STAGE 2 LT STA. 2403+05.66 - 2408+25.26	296	222	7	215
SUB TOTAL:	296	222	7	215
STAGE 3 RT STA. 2403+05.66 - 2406+00	59	44	65	-21
SUB TOTAL:	59	44	65	-21

CODE NUMBER	20200100	20400800
LOCATION	EARTH EXCAVATION (C.Y.)	FURNISHED EXCAVATION (C.Y.)
WEST MAINLINE STAGE 1 TEMP	508	0
WEST MAINLINE STAGE 1	2,263	0
WEST MAINLINE STAGE 2	948	0
WEST MAINLINE STAGE 3	2,055	0
WEST MAINLINE CONNECTOR	260	0
ALLEY STAGE 1	114	0
WEST BRIDGE CONNECTOR STAGE 3	809	0
WASSON STREET STAGE 1	445	0
WASSON STREET STAGE 2	296	0
WASSON STREET STAGE 3	59	21
GRAND TOTAL:	7,757	21

2/24/2006 I:\Temporary\Streator 2-24-06\05393CVR3.dgn