

SUMMARY OF QUANTITIES

F. A. A. NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
313	103N-1, TS	WARREN		9
STA.	TO STA.			
FED. ROAD DIST. NO. 4	ALLIANCE	FED. AID PROJECT		

SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT		FED - STATE 90 - 10 1000-1A	CITY 100% Y030-1E	SFTY - 3N IMPACT ATT. 90% FED 10% ST.	FED-STATE-CITY 90 - 5 - 5 Y031-1F	
20200100	EARTH EXCAVATION	CU YD	540	540				
20400800	FURNISHED EXCAVATION	CU YD	12	12				
20900110	POROUS GRANULAR BACKFILL	CU YD	23.7	23.7				
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	938.8	938.8				
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	2078	2078				
25000210	SEEDING, CLASS 2A	ACRE	0.4	0.4				
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	26	26				
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	26	26				
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	26	26				
25100115	MULCH, METHOD 2	ACRE	0.4	0.4				
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	129	129				
28000300	TEMPORARY DITCH CHECKS	EACH	7	7				
28000400	PERIMETER EROSION BARRIER	FOOT	800	800				
28000500	INLET AND PIPE PROTECTION	EACH	3	3				
28000510	INLET FILTERS	EACH	3	3				
28100105	STONE RIPRAP, CLASS A3	SQ YD	3.5	3.5				
28200200	FILTER FABRIC	SQ YD	3.5	3.5				
28500100	FABRIC FORMED CONCRETE REVETMENT MATS	SQ YD	8.1	8.1				
31100300	SUB-BASE GRANULAR MATERIAL, TYPE A 4"	SQ YD	392	392				
31100700	SUB-BASE GRANULAR MATERIAL, TYPE A 8"	SQ YD	1018	1018				

*SPECIALTY ITEMS