CONTRACT NO. 68356

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
313	103N-1,TS	WARREN		17
STA.		TO STA.		
FED. ROAD DIST. NO. 4	ILLINOIS	FED. AID PROJECT		

DRAINAGE SCHEDULE

LOCATION	28500100-FABRIC FORMED REVET-MENT MAT	550A0090-STORM SEWER CL. A, TY 1, 18"	550A0120-STORM SEWER CL. A, TY 1, 24"	550A0140-STORM SEWER CL. A, TY 1, 30"	54248515-CONC. COLLAR	54246205-INLET BOX, STD. 542526	54215979-REINF. CONC. PIPE ELBOW, 24"	54215985-REINF. CONC. PIPE ELBOW, 30"	#4001673 - INLET-MANHOLE, TY G-1, 8' DIA., SPECIAL	60219000-MANHOLES, TY A, 4' DIA., TY 8 GRATE	60221100-MANHOLE, TY A, 5' DIA., TY 1 FRAME CLOSED LID
	SQ YD	FOOT	FOOT	FOOT	EACH	EACH	EACH	EACH	EACH	EACH	EACH
US 34 @ 6TH STREET											
72.4' RT. STA. 425+54.3 - 82.1' RT. STA. 426+07.2			54								
84.7' RT. STA. 426+08.63 - 58.9' LT STA. 8+89.2			42.4								
62.9' RT. STA. 425+24.3 - 63.5' RT. STA. 425+32.28	8.1										
RT. STA. 425+29.48 - 425+54.92						1					
STA. 426+08.16		15.2			1						1
6TH STREET											
38.3' RT. STA. 11+07.84 - 29.3' RT. STA. 11+10.6			9.5								
40.8' RT. STA. 11+09.08 - 31.5' RT. STA. 11+41.89				34.1							
LT. STA. 8+88.37										1	
38' RT. STA. 11+05									1		
LT. STA. 11+15.17											
27.1' RT. STA. 11+04.84		10.8			1						
25.1' RT. STA. 11+13.24					1		1				
30.5' RT. STA. 11+47.09					1			1			
TOTALS	8.1	26	106	34.1	4	1	1	1	1	1	1

*NOTE: The Trench Backfill quantities are for drainage located only underneath the roadway.

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES DRAINAGE

SCALE: VERT. HORIZ.

DATE

DRAWN BY

CHECKED BY

PLOT DATE = 2/10/2006
FILE NAME = c:\projects\nonsouth2\misc\sheets.dgn
PLOT SCALE = 100.0000 ' / IN.
USER NAME = wagerja