

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
313	103N-1,TS	WARREN		18
STA.			TO STA.	
FED. ROAD DIST. NO. 4 ILLINOIS FED. AID PROJECT				

78100100 - RAISED REFLECTIVE PAVEMENT MARKER	
LOCATION	EACH
U.S. 34 - RT. TURNLANES	
LT. STA. 427+61 - 429+86	5
6TH ST. - ISLANDS	
NW QUADRANT	10
SW QUADRANT	10
SE QUADRANT	9
NE QUADRANT	10
LANE LINES	
STA. 8+54 - 9+42	2
STA. 10+69 - 11+94	5
STA. 11+16 - 12+30	4
STA. 7+48 - 9+32 (DOUBLE)	2
STA. 10+69 - 11+94 (DOUBLE)	4
<b>TOTAL</b>	<b>61</b>

78005110 - EPOXY PAV'T MRKG., 4'	
LOCATION	FEET
6TH ST.	
SINGLE YELLOW	
RT. STA. 8+54 - 9+42	88.6
LT. STA. 10+69 - 11+94	125
DOUBLE YELLOW	
STA. 7+52 - 9+32 (CENTERLINE)	362
STA. 10+69 - 11+94 (CENTERLINE)	250
<b>TOTAL</b>	<b>826</b>

78005180 - EPOXY PAV'T MRKG., 24'	
LOCATION	FEET
6TH ST.	
STA. 9+32	12
55' LT. STA. 9+36	16.4
STA. 9+42	11.5
40' LT. STA. 10+82	16.2
STA. 9+69	24
U.S. 34	
19.4' RT STA. 426+24	35.3
20' LT STA. 427+37	37.9
<b>TOTAL</b>	<b>153.3</b>

78005100 - EPOXY PAV'T MRKG - LETTERS & SYMBOLS				
Location	Offset	Rt. Turn Arrow	Lt. Turn Arrow	Thru Arrow
		SQ FT	SQ FT	SQ FT
U.S. 34				
Rt. Sta. 423+15	16.6'		1	
Rt. Sta. 424+53	16.9'		1	
Rt. Sta. 425+91	17.3'		1	
Rt. Sta. 426+09	25.5'			1
Rt. Sta. 426+09	37.4'			1
Lt. Sta. 427+55	26.4'			1
Lt. Sta. 427+55	35.9'			1
Lt. Sta. 427+70	16.7'		1	
Lt. Sta. 429+00	17'		1	
Lt. Sta. 430+31	17.8'		1	
6th St.				
Sta. 8+54	0'		1	
Sta. 9+03	0'		1	
Rt. Sta. 9+03	8.9'			1
Rt. Sta. 9+03	21.9'	1		
Lt. Sta. 9+54	104.8'	1		
Lt. Sta. 10+99	5.8'		1	
Lt. Sta. 10+99	15.9'			1
Lt. Sta. 11+16	28.9'	1		
Lt. Sta. 11+74	7.3'		1	
Lt. Sta. 11+74	15.1'			1
Lt. Sta. 11+99	25'	1		
Sub-Total		62.4	156	80.5
<b>TOTAL</b>			<b>299</b>	

78005140 - EPOXY PAV'T MRKG., 8'	
LOCATION	FEET
TURNLANE TRANSITION - (SKIP DASH)	
LT. STA. 429+86 - 432+16	76.7
US 34 (SOLID)	
RT. STA. 423+99 - 426+24	325.4
LT. STA. 427+37 - 430+48	310.9
LT. STA. 427+61 - 429+86	225
ISLANDS - (SOLID) @ 6TH ST.	
NW QUADRANT	180.1
NE QUADRANT	208.9
SE QUADRANT	158.5
SW QUADRANT	236.1
6TH ST. - (SOLID)	
STA. 11+16 - 12+30	114.8
50' RT. STA 426+51 - 51' LT. STA. 426+48(CROSS WALK)	150.1
50' RT. STA 426+59 - 51' LT. STA. 426+56(CROSS WALK)	151.1
<b>TOTAL</b>	<b>2138</b>

70300100 - SHORT-TERM PAV'T MRKG.	
LOCATION	FEET
6TH ST.	
DOUBLE YELLOW	
(SOUTH) STA. 7+52 - 9+32	40
(NORTH) STA. 10+69 - 11+94	32
SINGLE YELLOW	
(SOUTH) STA. 7+67 - 9+42	16
(NORTH) STA. 10+69 - 12+30	16
STA. 11+16 - 12+30	16
US 34	
STA. 427+55 - 429+86	24
STA. 428+16 - 432+16	16
<b>TOTAL</b>	<b>160</b>

78005150 - EPOXY PAV'T MRKG., 12'	
LOCATION	FEET
ISLANDS - (CHEVRONS) @ 6TH	
NE QUADRANT	149
SE QUADRANT	85.1
SW QUADRANT	187.6
NW QUADRANT	108.5
<b>TOTAL</b>	<b>530</b>

70300200 - TEMPORARY PAV'T MRKG. 70300210 - TEMP. PAV'T MRKG. LTRS & SYMBOLS		
LOCATION	FEET	SQ FT
PAY ITEM #		
78005100		299
78005180	153.3	
78005110	826	
78005140	1357	
78005150	530.2	
<b>TOTAL</b>	<b>2867</b>	<b>299</b>

PLOT DATE = 2/10/2006  
 FILE NAME = c:\arc\mca\arc\mca\mca\mca\mca\dgn  
 PLOT SCALE = 1/8"=1'-0"  
 USER NAME = wjg-jp

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

**SCHEDULE OF QUANTITIES PAVEMENT MARKINGS**

SCALE: VERT. HORIZ.  
DATE

DRAWN BY  
CHECKED BY