

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
72	186-101RS-2	SCOTT	52	10
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL	CONSTRUCTION TYPE
				CODE - I000 <i>90% Fed. 10% State</i>
X4066765	LEVELING BINDER (MACHINE METHOD), SUPERPAVE N50	TON	743.5	743.5
X4066915	POLYMERIZED LEVELING BINDER (MACHINE METHOD), SUPERPAVE N90	TON	791	791
X0322729	MATERIAL TRANSFER DEVICE	TON	13980.3	13980.3
X0322950	MEDIAN INLET REPAIR	EACH	1	1
X2503000	MAINTENANCE MOWING	ACRE	1	1
X3560010	BITUMINOUS BASE COURSE WIDENING, SUPERPAVE	TON	167.1	167.1
Z0017202	DOWEL BARS 1 1/2"	EACH	516	516
Z0021600	EXPANSION JOINT 4"	FOOT	48	48
Z0033600	LONGITUDINAL JOINT REPAIR	FOOT	8900	8900

⊙

PLOT DATE = 2/22/2008
FILE NAME = c:\p\proj\scott\651503\soq.dgn
PLOT SCALE = 1/8"=1'-0" / IN.
REFERENCE = REF#

⊙ NON-PARTICIPATING

Rev.

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
FAP 72
SECTION 186-101RS-2
SCOTT COUNTY
SCALE: VERT. : NOT TO SCALE
DATE : NOVEMBER, 2003
DRAWN BY JJB
CHECKED BY VJM