

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
75	81L,TS,I-D	SANGAMON	29	7
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

SUMMARY OF QUANTITIES - IL RTE. 29 @ HILLTOP ROAD

PAY CODE	PAY ITEM DESCRIPTION	UNIT	100% STATE TOTAL QUANTITY	CONSTRUCTION TYPE CODE		
				1000 RESURFACING QUANTITY	Y031-1F SIGNALS QUANTITY	Y030-1E LIGHTING QUANTITY
81400100	HANDHOLE	EACH	4		4	
81400300	DOUBLE HANDHOLE	EACH	1		1	
81500200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	4010		2833	1177
81600115	UD 2 *10 XLP, 1*10 XLPG 3/4 P	FOOT	1402			1402
82102250	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 250 WATT	EACH	7			7
82103250	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, PHOTO-CELL CONTROL 250 WATT	EACH	2		2	
82500510	LIGHTING CONTROLLER CB -RCS-60-240	EACH	1			1
83003600	LIGHT POLE ALUMINUM 45' MH, 15' DAVIT ARM	EACH	7			7
83600300	LIGHT POLE FOUNDATION, 30" DIAMETER	FOOT	46			46
83800205	BREAKAWAY DEVICE, TRANSFORMER BASE, 15" BOLT CIRCLE	EACH	7			7
85700300	FULL ACTUATED CONTROLLER AND TYPE V CABINET	EACH	1		1	
85800100	FLASHER CONTROLLER	EACH	1		1	
86000100	MASTER CONTROLLER	EACH	1		1	
86400100	TRANSCEIVER - FIBER OPTIC	EACH	1		1	

PLOT DATE : 2/19/2006
 FILE NAME : c:\pwworkspace\110525006\110525006.dwg
 USER NAME : bshelton

Rev.

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
IL 29 @ HILLTOP ROAD
SANGAMON COUNTY

SCALE: VERT. _____
 HORIZ. _____
 DATE _____

DRAWN BY _____
 CHECKED BY _____