

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
75	8IL,TS,I-D	SANGAMON	29	8
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

SUMMARY OF QUANTITIES - IL RTE. 29 @ HILLTOP ROAD

PAY CODE	PAY ITEM DESCRIPTION	UNIT	100% STATE	CONSTRUCTION TYPE CODE		
			TOTAL QUANTITY	1000	Y031-1F	Y030-1E
				RESURFACING QUANTITY	SIGNALS QUANTITY	LIGHTING QUANTITY
87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14, 2C	FOOT	2966		2966	
87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14, 5C	FOOT	1234		1234	
87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14, 7C	FOOT	819		819	
87301265	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14, 9C	FOOT	177		177	
87301515	ELECTRIC CABLE IN CONDUIT, LEAD-IN NO. 18, 3 PAIR	FOOT	2018		2018	
87301525	ELECTRIC CABLE IN CONDUIT, LEAD-IN NO. 18, 6 PAIR	FOOT	160		160	
87301815	ELECTRIC CABLE IN CONDUIT, SERVICE NO. 6, 3C	FOOT	19		19	
87502680	TRAFFIC SIGNAL POST, ALUMINUM, 14'	EACH	2		2	
87502700	TRAFFIC SIGNAL POST, ALUMINUM, 16'	EACH	4		4	
87702930	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE, 40'	EACH	1		1	
87702970	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE, 48'	EACH	1		1	
87800100	CONCRETE FOUNDATION, TYPE A	FOOT	18		18	
87800415	CONCRETE FOUNDATION, TYPE E, 36" DIA.	FOOT	26		26	
88020160	SIGNAL HEAD, POLYCARBONATE, LED 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	2		2	

PLOT DATE : 2/17/2006  
 FILE NAME : g:\projects\050606\auto\06p1.dwg  
 USER : hrb\jrb  
 USER NAME : jrb

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SUMMARY OF QUANTITIES  
 IL 29 @ HILLTOP ROAD  
 SANGAMON COUNTY

SCALE: VERT. \_\_\_\_\_  
 DATE: \_\_\_\_\_ HORIZ. \_\_\_\_\_

DRAWN BY \_\_\_\_\_  
 CHECKED BY \_\_\_\_\_