

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
75	BL. TS. 1-1	SANGAMON	29	11
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

BITUMINOUS REMOVAL (V. D.) SCHEDULE		
LOCATION	STATION	AREA (SQ. YD.)
SBL - IL 29	86+13.47 - 93+62.29 RT	1890
NBL - IL 29	91+48.64 - 98+60.67 LT	1792
NBL - TURN LANE	92+93.37 - 98+10.67 LT	432
SBL - TURN LANE	86+63.43 - 91+13.46 RT	381
X - OVER	91+98.86 - 93+10.92 LT/RT	353
HILL TOP ROAD	47+45.22 - 49+50.99	1256
TOTAL		6104.0

BITUMINOUS SHOULDERS				
LOCATION	STATION	(TON)	AGGREGATE	BITUMINOUS
			PRIME COAT	PRIME COAT
			(TON)	(TON)
NBL - INSIDE	91+48.64 - 92+15.52 LT	4	0	0.01
SBL - INSIDE	86+13.47 - 92+15.53 RT	31	1	0.11
NBL - OUTSIDE	91+48.64 - 98+60.67 LT	89	2	0.30
NBL - INSIDE	92+90.22 - 98+60.67 LT	29	1	0.10
SBL - INSIDE	92+90.22 - 93+62.29 RT	4	0	0.01
SBL - OUTSIDE	93+23.37 - 93+62.29 RT	3	0	0.01
HILLTOP ROAD	47+45.22 - 48+95.97 RT	10	0	0.03
HILLTOP ROAD	47+45.22 - 48+24.36 LT	5	0	0.02
HILLTOP ROAD	48+37.16 - 49+85.72 LT	9	0	0.03
SBL - OUTSIDE	87+48.55 - 91+13.57 RT	18	0	0.06
SBL - OUTSIDE	86+63.43 - 87+48.55 RT	95	2	0.32
SBL - OUTSIDE	86+13.47 - 86+63.43 RT	6	0	0.02
TOTAL		303	5	1.0

BITUMINOUS SURFACE REMOVAL - BUTT JOINTS			
LOCATION	STATION	BUTT JOINT	TEMPORARY
		RAMP AREA	RAMP
		(SQ. YD.)	(SQ. YD.)
NBL	91+48.64	107	18
NBL	98+60.67	107	18
SBL	86+13.47	107	18
SBL	93+62.29	107	18
HILLTOP ROAD	47+55.22	113	19
HILLTOP ROAD/S.R.	48+37.16	96	18
TOTAL		636	108

Aggregate Shoulder Schedule		
LOCATION	STATION	AGGREGATE
		SHOULDER, TY. B
		(TON)
SBL - OUTSIDE	86+13.47 - 91+20.41 RT	10
SBL - INSIDE	86+13.47 - 92+07.42 RT	23
SBL - INSIDE	93+10.25 - 93+62.29 RT	1
SBL - OUTSIDE	93+21.77 - 93+62.29 RT	1
NBL - INSIDE	92+93.05 - 98+60.67 LT	11
NBL - OUTSIDE	91+48.64 - 98+60.67 LT	14
NBL - INSIDE	91+48.64 - 91+98.77 LT	1
TOTAL		59

BITUMINOUS SCHEDULE				
LOCATION	STATION	AGGREGATE	BITUMINOUS	POL. BIT. CONC. SURF. CSE.
		PRIME COAT	PRIME COAT	SUPERP. MIX "D", N70
		(TON)	(TON)	(TON)
SBL - IL 29	86+13.47 - 93+62.29 RT	4	0.8	224
NBL - IL 29	91+48.64 - 98+60.67 LT	4	0.7	213
NBL - T.L.	92+93.37 - 98+10.67 LT	1	0.2	60
SBL - T.L.	86+63.43 - 91+13.46 RT	1	0.2	55
X-OVER	91+98.96 - 93+10.92	1	0.1	40
HILLTOP RD.	47+45.22 - 49+50.99	3	0.6	164
TOTALS		13	2.6	755

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE OF QUANTITIES
IL 29 @ HILLTOP ROAD
SANGAMON COUNTY

SCALE: VERT. _____
 HORIZ. _____
 DATE _____
 DRAWN BY: _____
 CHECKED BY: _____