

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
75	BIL. TS. 1-1	SANGAMON	29	12
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

PAVEMENT REMOVAL		
LOCATION	STATION	AREA (SQ YD)
IL 29 / HILLTOP RD	92+00 RT	35.0
	TOTAL	35.0

CONCRETE CURB AND GUTTER			
LOCATION	TYPE	STATION	TOTAL LENGTH (FOOT)
IL 29 / HILLTOP RD	M-6.06	92+00 RT	22
IL 29 / HILLTOP RD	M-6.24	92+00 RT	40

SUB-BASE GRANULAR MATERIAL, TYPE B		
LOCATION	STATION	TOTAL (TONS)
IL 29 / HILLTOP RD	92+00 RT	18
	TOTAL	18

PERFORMED PLASTIC PAVEMENT MARKING, TYPE B				
LOCATION	STATION	WHITE LINE 5"	YELLOW LINE 5"	
		(FOOT)	(FOOT)	
NBL - OUTSIDE	91+48.64 - 98+60.67 LT	712		LINE
NBL - INSIDE	91+48.64 - 92+00.70 LT		52	LINE
X-OVER	92+00.70 - 92+18.52 LT		53	LINE
X-OVER	92+87.20 - 93+10.47 LT		44	LINE
NBL - INSIDE	92+92.88 - 98+60.67 LT		568	LINE
SBL - INSIDE	93+10.47 - 93+62.29 RT		52	LINE
SBL - INSIDE	86+13.47 - 92+08.81 RT		595	LINE
SBL - OUTSIDE	86+13.47 - 91+13.52 RT	500		LINE
HILLTOP ROAD	48+47.11 - 49+88.42 LT	198		LINE
HILLTOP ROAD	47+45.16 - 48+26.89 LT	111		LINE
HILLTOP ROAD	47+45.29 - 48+86.31 RT	253		LINE
SBL - RIGHT T. L.	89+12.84 - 91+52.62 RT	240		LINE
NBL - LEFT T. L.	92+99.34 - 95+40.02 LT	241		LINE
SBL - RIGHT T. L.	86+63.43 - 89+12.84 RT	62		SKIP - DASH
NBL - LEFT T. L.	95+40.02 - 98+09.83 LT	67		SKIP - DASH
HILLTOP ROAD	48+47.75 - 49+16.33 CL		71	LINE
HILLTOP ROAD	47+45.22 - 48+47.75 CL		26	SKIP - DASH
NBL	91+48.64 - 91+98.51 LT	12		SKIP - DASH
NBL	92+99.34 - 98+60.67 LT	140		SKIP - DASH
SBL	86+13.47 - 91+95.24 RT	145		SKIP - DASH
SBL	93+10.92 - 93+62.29 RT	13		SKIP - DASH
	TOTAL	2696	1460	

PERFORMED PLASTIC PAVEMENT MARKING, TYPE B		
LOCATION	STATION	LINE 8" WHITE
		(FOOT)
SBL / HILLTOP RD	91+52.62 - 92+29.05 RT	201
	TOTAL	201

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE OF QUANTITIES
IL 29 @ HILLTOP ROAD
SANGAMON COUNTY
 SCALE: VERT. _____
 HORIZ. _____
 DATE _____
 DRAWN BY: _____
 CHECKED BY: _____