CONTRACT NO. 74089

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	***	5	3
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

* FAU ROUTE 8413 & FAP ROUTE 2796
** D7 FLASHING BEACON 2006-1
*** FAYETTE & EFFINGHAM

FAS 2796 (US 40) & IL 128 IN ALTAMONT

SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	TOTAL QUANTITIES	URBAN CONSTRUCTION TYPE CODE 90% FED./10% STATE Y031-1F FAYETTE CO.	RURAL CONSTRUCTION TYPE CODE 90% FED./10% STATE Y031-1F EFFINGHAM CO.
67100100	MOBILIZATION	L SUM	1	0.5	0.5
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	0.5	0.5
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	0.5	0.5
80500100	SERVICE INSTALLATION, TYPE A	EACH	1	1	
80500200	SERVICE INSTALLATION, TYPE B	EACH	1		1
80803590	TRAFFIC SIGNAL WOOD POLE, 35 FT., CLASS 3	EACH	3	1	2
80803630	TRAFFIC SIGNAL WOOD POLE, 40 FT., CLASS 3	EACH	1	1	
81100500	CONDUIT ATTACHED TO STRUCTURE, 1 1/2" DIA., GALVANIZED STEEL	FOOT	35	18	17
85800100	FLASHER CONTROLLER	EACH	2	1	1
87200400	SPAN WIRE	FOOT	200	115	85
87200500	TETHER WIRE	FOOT	200	115	85
87302245	ELECTRIC CABLE AERIAL SUSPENDED, SIGNAL, NO. 14 5C	FOOT	149	83	66
89502400	REMOVE EXISTING FLASHING BEACON INSTALLATION COMPLETE	EACH	2	1	1
X8801505	SIGNAL HEAD ,POLYCARBONATE, LED, 4-FACE, 1-SECTION, SPAN WIRE MOUNTED	EACH	4	2	2

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: VERT. HORIZ.
DATE

DRAWN BY
CHECKED BY

PLOT DATE = 2/10/2006
FILE NAME = $$FILE$$
PLOT SCALE = $$SCALE$$
USER NAME = district