

SUMMARY OF QUANTITIES

VARIOUS COUNTIES  
1000

|             |         |         |              |           |
|-------------|---------|---------|--------------|-----------|
| F.A.P. RATE | SECTION | COUNTY  | TOTAL SHEETS | SHEET NO. |
| VAR         |         | VARIOUS | 23           | 3         |

\* 0-9 CONT. MAINT. FY 06-3

| CODE NUMBER | ITEM DESCRIPTION<br>CONSTRUCTION TYPE CODE                  | UNIT  | TOTAL QUANTITY | LOC #1                       | LOC #2                        | LOC #3                        | LOC #4                     |
|-------------|---|-------|----------------|------------------------------|-------------------------------|-------------------------------|----------------------------|
|             |   |       |                | SALINE CO. RURAL 100 % STATE | PULASKI CO. RURAL 100 % STATE | JOHNSON CO. RURAL 100 % STATE | POPE CO. RURAL 100 % STATE |
| 20200100    | EARTH EXCAVATION  | CU YD | 439            | 155                          | 284                           |                               |                            |
| 20201200    | REMOVAL AND DISPOSAL OF UNSUITABLE MATERIALS                | CU YD | 6              |                              |                               |                               | 6                          |
| 20400800    | FURNISHED EXCAVATION  | CU YD | 371            |                              |                               |                               | 371                        |
| 25000350    | SEEDING, CLASS 7  | ACRE  | 0.5            |                              |                               |                               | 0.5                        |
| 25000400    | NITROGEN FERTILIZER NUTRIENT                                | POUND | 75             |                              |                               |                               | 75                         |
| 25000500    | PHOSPHORUS FERTILIZER NUTRIENT                              | POUND | 56             |                              |                               |                               | 56                         |
| 25000600    | POTASSIUM FERTILIZER NUTRIENT                               | POUND | 56             |                              |                               |                               | 56                         |
| 25000700    | AGRICULTURAL GROUND LIMESTONE                               | TON   | 1              |                              |                               |                               | 1                          |
| 25001010    | SEEDING, CLASS 2 MODIFIED                                   | ACRE  | 0.5            |                              |                               |                               | 0.5                        |
| 25100115    | MULCH, METHOD 2   | ACRE  | 0.5            |                              |                               |                               | 0.5                        |
| 28000250    | TEMPORARY EROSION CONTROL SEEDING                           | POUND | 140            |                              |                               |                               | 140                        |
| 28000400    | PERIMETER EROSION BARRIER                                   | FOOT  | 2,600          |                              |                               |                               | 2,600                      |
| 35101100    | AGGREGATE BASE COURSE, TYPE A, 12 INCH                      | SQ YD | 463            | 463                          |                               |                               |                            |
| 40600100    | BITUMINOUS MATERIALS (PRIME COAT)                           | GAL   | 1,954          | 148                          | 714                           | 138                           | 580                        |
| 40600300    | AGGREGATE (PRIME COAT)                                      | TON   | 32             | 1                            | 12                            | 2                             | 10                         |
| 40600990    | TEMPORARY RAMP  | SQ YD | 148            |                              | 24                            | 28                            | 70                         |
| 44000006    | BITUMINOUS SURFACE REMOVAL - 1 1/2"                         | SQ YD | 20,063         |                              | 7,934                         | 1,528                         | 6,445                      |
| 44000100    | PAVEMENT REMOVAL  | SQ YD | 463            | 463                          |                               |                               |                            |
| 44200116    | PAVEMENT PATCHING, TYPE I, 10 INCH                          | SQ YD | 2              | 2                            |                               |                               |                            |
| 44200120    | PAVEMENT PATCHING, TYPE II, 10 INCH                         | SQ YD | 109            | 109                          |                               |                               |                            |
| 44200126    | PAVEMENT PATCHING, TYPE IV, 10 INCH                         | SQ YD | 223            | 223                          |                               |                               |                            |
| 44200140    | PAVEMENT PATCHING, TYPE I, 12 INCH                          | SQ YD | 139            |                              | 139                           |                               |                            |
| 44200144    | PAVEMENT PATCHING, TYPE II, 12 INCH                         | SQ YD | 7              |                              | 7                             |                               |                            |
| 44200174    | PAVEMENT PATCHING, TYPE IV, 14 INCH                         | SQ YD | 106            |                              |                               |                               | 106                        |
| 44213200    | SAW CUTS  | FOOT  | 7,840          | 1,040                        | 6,800                         |                               |                            |
| 44300200    | STRIP REFLECTIVE CRACK CONTROL TREATMENT                    | FOOT  | 13,323         |                              | 6,800                         | 250                           | 6,273                      |
| 48101200    | AGGREGATE SHOULDERS, TYPE B                                 | TON   | 87             |                              | 87                            |                               |                            |
| 50800105    | REINFORCEMENT BARS  | POUND | 1,727          |                              |                               |                               | 1,727                      |
| 54001000    | BOX CULVERT END SECTION                                     | EACH  | 2              |                              |                               |                               | 2                          |
| 54002020    | EXPANSION BOLTS 3/4"  | EACH  | 40             |                              |                               |                               | 40                         |
| 54003000    | CONCRETE BOX CULVERTS                                       | CU YD | 8.6            |                              |                               |                               | 8.6                        |
| 67100100    | MOBILIZATION  | L SUM | 1              | 0.1                          | 0.3                           | 0.1                           | 0.4                        |
| 70100460    | TRAFFIC CONTROL AND PROTECTION, STANDARD 701306             | L SUM | 1              | 0.1                          | 0.3                           | 0.1                           | 0.4                        |
| 70100600    | TRAFFIC CONTROL AND PROTECTION, STANDARD 701336             | L SUM | 1              | 0.1                          | 0.3                           | 0.1                           | 0.4                        |
| 70300100    | SHORT TERM PAVEMENT MARKING                                 | FOOT  | 1,020          |                              | 680                           |                               | 340                        |
| 70300220    | TEMPORARY PAVEMENT MARKING - LINE 4"                        | FOOT  | 19,038         | 1,040                        | 7,650                         | 1,250                         | 5,273                      |
| 70301000    | WORK ZONE PAVEMENT MARKING REMOVAL                          | SQ FT | 6,688          | 347                          | 2,777                         | 417                           | 1,758                      |
| * 78001110  | PAINT PAVEMENT MARKING - LINE 4"                            | FOOT  | 19,038         | 1,040                        | 7,650                         | 1,250                         | 5,273                      |
| 78300200    | RAISED REFLECTIVE PAVEMENT MARKER REMOVAL                   | EACH  | 65             |                              | 43                            |                               | 22                         |
| X3560130    | BITUMINOUS CONCRETE BASE COURSE WIDENING, SUPERPAVE 9 INCH  | SQ YD | 1,134          |                              | 1,134                         |                               |                            |
| X3560140    | BITUMINOUS CONCRETE BASE COURSE WIDENING, SUPERPAVE 10 INCH | SQ YD | 463            | 463                          |                               |                               |                            |
| X4066418    | BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "C", N90 | TON   | 1,687          |                              | 667                           | 128                           | 542                        |
| * 20054505  | ROCK FILL (REPLACEMENT)                                     | TON   | 12             |                              |                               |                               | 12                         |

\* SPECIALTY ITEMS

SUMMARY OF QUANTITIES

PLT DATE : 2/6/2006  
FILE NAME : c:\projects\0602\05\0602\05\m3  
PLT SCALE : 185.6824 'x' IN.  
USER NAME : rolliver