

PARTIAL DEPTH PATCHING

MILE STATION (MI.)	DIRECTION (EB / WB)	LANE DESCRIPTION	LENGTH (FT)	WIDTH (FT)	AREA (SQ YD)	PARTIAL DEPTH REMOVAL, 2" (SQ YD)	PARTIAL DEPTH PATCHING (TON)
0.66	WB	3RD LANE	6	12	8.0	8.0	0.9
0.68	WB	2ND LANE	6	12	8.0	8.0	0.9
0.69	WB	2ND LANE	6	12	8.0	8.0	0.9
0.70	WB	2ND LANE	6	12	8.0	8.0	0.9
0.71	WB	3RD LANE	6	12	8.0	8.0	0.9
0.80	WB	2ND & 3RD LANE	250	2	55.6	55.6	6.2
0.81	WB	LANE JOINTS	450	2	100.0	100.0	11.2
0.91	WB	2ND & 3RD LANE	200	2	44.4	44.4	5.0
1.04	WB	LEFT TURN LANE TAPER	100	6	66.7	66.7	7.5
1.08	WB	DL	150	2	33.3	33.3	3.7
1.08	WB	PL	150	2	33.3	33.3	3.7
1.16	WB	DL	8	12	10.7	10.7	1.2
1.16	WB	PL	15	12	20.0	20.0	2.2
1.34	WB	PL	30	6	20.0	20.0	2.2
1.67	WB	DL	12	12	16.0	16.0	1.8
2.11	WB	DL	60	6	40.0	40.0	4.5
2.14	WB	DL	15	6	10.0	10.0	1.1
2.20	WB	LEFT TURN LANE PM ROAD	450	16	800.0	800.0	89.6
2.38	WB	DL	40	12	53.3	53.3	6.0
2.38	WB	PL	40	12	53.3	53.3	6.0
2.44	WB	DL	70	12	93.3	93.3	10.5
2.44	WB	PL	70	12	93.3	93.3	10.5
2.48	WB	PL	20	12	26.7	26.7	3.0
2.48	WB	DL	6	10	6.7	6.7	0.7
2.64	WB	DL	50	12	66.7	66.7	7.5
2.64	WB	PL	50	12	66.7	66.7	7.5
2.90	WB	ALL 4 LANES	400	48	2133.3	2133.3	238.9
2.99	WB	DL	140	12	186.7	186.7	20.9
2.99	WB	PL	140	12	186.7	186.7	20.9
3.07	WB	PL	60	12	80.0	80.0	9.0
3.07	WB	DL	60	12	80.0	80.0	9.0
3.25	WB	DL	6	12	8.0	8.0	0.9
3.25	WB	PL	6	12	8.0	8.0	0.9
3.60	WB	PL	100	12	133.3	133.3	14.9
3.60	WB	DL	100	12	133.3	133.3	14.9
3.61	WB	DL	6	12	8.0	8.0	0.9

SCHEDULE CONTINUED (SEE NEXT SHEET)

FILE NAME =	USER NAME = #USER#	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
#FILE#		DRAWN -	REVISED -		SCALE: _____	SHEET NO. _____ OF _____ SHEETS	STA. _____ TO STA. _____	785	(132-2,3,4, 133-1)RS	MADISON	122	31
	PLOT SCALE = #SCALE#	CHECKED -	REVISED -					CONTRACT NO. 76B80				
	PLOT DATE = #DATE#	DATE -	REVISED -		FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT							