

L:\RCD\4\F040\08228082\CADD\CADD_Sheets\18_500_01.dgn


ITEM NUMBER	S.P.	PAY ITEM NUMBER	DESCRIPTION	UNIT	TOTAL QUANTITY	80% STATE / 20% CITY			100% CITY
						ROADWAY 0003	BRIDGE 0010	TRAINEES 0042	
1		20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	34	34			
2		20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	1,330	1,330			
3	*	20101000	TEMPORARY FENCE	FOOT	1,150	1,150			
4	*	20101100	TREE TRUNK PROTECTION	EACH	18	18			
5	*	20200100	EARTH EXCAVATION	CU YD	47,477	47,477			
6	*	20800150	TRENCH BACKFILL	CU YD	3,692	3,692			
7		21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	20,993	20,993			
8	*	21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	52,138	52,138			
9	*	21301052	EXPLORATION TRENCH 52" DEPTH	FOOT	200	200			
10	BDE	25000210	SEEDING, CLASS 2A	ACRE	9.75	9.75			
11	*	25000400	NITROGEN FERTILIZER NUTRIENT	POUND	875	875			
12	*	25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	875	875			
13	*	25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	875	875			
14	*	25100630	EROSION CONTROL BLANKET	SQ YD	47,055	47,055			
15		25200110	SODDING, SALT TOLERANT	SQ YD	5,083	5,083			
16	*	25200200	SUPPLEMENTAL WATERING	UNIT	5	5			
17	*	28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	2,917	2,917			
18	*	28000305	TEMPORARY DITCH CHECKS	FOOT	126	126			
19	*	28000400	PERIMETER EROSION BARRIER	FOOT	8,858	8,858			
20		28100105	STONE RIPRAP, CLASS A3	SQ YD	21	21			
21		28100107	STONE RIPRAP, CLASS A4	SQ YD	51	51			
22		28100109	STONE RIPRAP, CLASS A5	SQ YD	1,961	1,961			
23	*	28200200	FILTER FABRIC	SQ YD	2,122	89	2,033		
24	*	28400100	GABIONS	CU YD	1,450	1,450			
25	*	31101810	SUB-BASE GRANULAR MATERIAL, TYPE B 12"	SQ YD	21,823	21,823			
26		35101400	AGGREGATE BASE COURSE, TYPE B	TON	200	200			
27		35101600	AGGREGATE BASE COURSE, TYPE B 4"	SQ YD	3,100	3,100			
28		35101800	AGGREGATE BASE COURSE, TYPE B 6"	SQ YD	2,094	2,094			
29	*	40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	224	224			
30	*	40600100	BITUMINOUS MATERIALS (PRIME COAT)	GAL	73	73			

ITEM NUMBER	S.P.	PAY ITEM NUMBER	DESCRIPTION	UNIT	TOTAL QUANTITY	80% STATE / 20% CITY			100% CITY
						ROADWAY 0003	BRIDGE 0010	TRAINEES 0042	
31		40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	453	453			
32		40600990	TEMPORARY RAMP	SQ YD	330	330			
33		40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	34	34			
34		40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	52	52			
35	*	42000301	PORTLAND CEMENT CONCRETE PAVEMENT 8" (JOINTED)	SQ YD	16,479	16,479			
36		42100100	CONTINUOUSLY REINFORCED PORTLAND CEMENT CONCRETE PAVEMENT 8"	SQ YD	1,067	1,067			
37		42100615	PAVEMENT REINFORCEMENT	SQ YD	1,067	1,067			
38	*	42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	283	283			
39	*	42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	1,595	1,595			
40	*	42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	21,821	21,821			
41	*	42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	22,440	22,440			
42	*	42400800	DETECTABLE WARNINGS	SQ FT	712	712			
43		44000100	PAVEMENT REMOVAL	SQ YD	16,397	16,397			
44		44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	422	422			
45		44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	6,520	6,520			
46		44000600	SIDEWALK REMOVAL	SQ FT	29,237	29,237			
47		44003100	MEDIAN REMOVAL	SQ FT	1,675	1,675			
48		44004000	PAVED DITCH REMOVAL	FOOT	50	50			
49	BDE	44201335	CLASS C PATCHES, TYPE IV, 8 INCH	SQ YD	9	9			
50	*	50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1		1		
51		50200100	STRUCTURE EXCAVATION	CU YD	2,995		2,995		
52		50200300	COFFERDAM EXCAVATION	CU YD	1,130		1,130		
53	*	50202901	COFFERDAM (LOCATION-1)	EACH	2		2		
54	BDE	50300225	CONCRETE STRUCTURES	CU YD	1,305		1,305		
55	BDE	50300255	CONCRETE SUPERSTRUCTURES	CU YD	1,289		1,289		
56		50300260	BRIDGE DECK GROOVING	SQ YD	3,088		3,088		
57		50300265	SEAL COAT CONCRETE	CU YD	229		229		
58	BDE	50300280	CONCRETE ENCASEMENT	CU YD	6		6		
59	*	50300285	FORM LINER TEXTURED SURFACE	SQ FT	1,627		1,627		
60		50300300	PROTECTIVE COAT	SQ YD	10,298	5,210	5,088		

NOTES:

- INDICATES SPECIAL PROVISION
- ** INDICATES IDOT RECURRING SPECIAL PROVISION
- BDE INDICATES IDOT BDE SPECIAL PROVISION
- GBSP INDICATES IDOT GBSP SPECIAL PROVISION

Δ SPECIALTY ITEMS



USER NAME = Steve Frange	DESIGNED - SJP / MNB	REVISED -
DRAWN - ERD	CHECKED - SJP	REVISED -
DATE - 02/04/2011		

CITY OF ROCKFORD
MORGAN STREET BRIDGE

SUMMARY OF QUANTITIES

SCALE: N/A SHEET NO. 1 OF 4 SHEETS STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
5077	99-00493-00-BR	WINNEBAGO	253	7
FED. ROAD DIST. NO. 2 (ILLINOIS) FED. AID PROJECT BRM-5091651			CONTRACT NO. 85529	