PLAN
SURVEYED
PLOTTED
ALIGNMENT CHECKED
GRADES CHECKED
CADD FILE NAME
NOTE BOOK
NO.
DATE
BY

PROFILE
SURVEYED
PLOTTED
GRADES CHECKED
BENCH MARK
STRUCTURE NO(S)/ITRS CKD'ED
NOTE BOOK
NO.
DATE
BY

CONNECT TO EXIST. 6" MAIN WITH BEND AND 8" GATE VALVE & BOX

COLLEGE AVENUE

SEMINARY STREET

PROP. ℄ SEMINARY ST.

ABANDON

8" GATE VALVE & BOX

8" 45° BEND
+96, 29.4' RT

REMOVE AND REPLACE HYDRANT AND 6" VALVE & BOX

CONNECT TO EXIST. 8" MAIN

CUT & CAP 4", REMOVE EXIST. 8"x4" TEE

REMOVE EXIST. 6" MAIN AND REPLACE WITH 8"

8" GATE VALVE & BOX

8"x8" TEE

CONNECT TO EXIST. 8" MAIN

N

SCALE: 1"=20'

PROPOSED GRADELINE AT PROP. ℄

EXIST. GRADELINE AT PROP. ℄

CONNECT TO PROP. 8" WATERMAIN WITH 8"X8" TEE

PROP. WATERMAIN PROFILE

CONNECT TO PROP. 8" WATERMAIN WITH 8"X8" TEE

6" SAN. SEWER

12" SAN. SEWER

6" SAN. SEWER

770	765	760	755	750	745	740	735	730

748.93 / 751.62	749.04 / 750.88	749.23 / 750.65	749.48 / 750.48	749.63 / 750.30	749.75 / 750.13	749.89 / 750.00	750.03 / 749.94	750.16 / 749.95	750.29 / 750.03	750.42 / 750.17	750.55 / 750.38	750.71 / 750.62	750.87 / 750.86	751.10 / 751.10	751.33	751.57	751.66
10+00		10+50		11+00		11+50		12+00		12+50		13+00		13+50		14+00		14+50

L:\ROCKFORD\0826082\Dgn\CADD\Sheets\R_WATER_28.8.dgn

CMT
©Copyright CMT, Inc.
CRAWFORD, MURPHY & TILLY, INC.
CONSULTING ENGINEERS
License No. 184-000613

USER NAME = Steve Prange	DESIGNED SJP / MNB	REVISED -	
	DRAWN ERD	REVISED -	
PLOT SCALE = 40.0000 ' / IN.	CHECKED SJP	REVISED -	
PLOT DATE = 02/04/11	DATE 02/04/2011	REVISED -	

CITY OF ROCKFORD
MORGAN STREET BRIDGE

PROPOSED WATERMAIN PLAN & PROFILE
SEMINARY STREET

SCALE: 1" = 20' | SHEET NO. 8 OF 11 SHEETS | STA. 10+00 TO STA. 14+55

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
5077	99-00493-00-BR	WINNEBAGO	253	60
		CONTRACT NO. 85529		
FED. ROAD DIST. NO. 2	ILLINOIS	FED. AID PROJECT BRM-5099(165)		