

| SUMMARY OF QUANTITIES | | | TOTAL QUANTITIES URBAN | CONSTRUCTION TYPE CODE | | | | |
|-----------------------|--|-------|------------------------|---|-------------------------------------|--|--|--|
| CODE NO | ITEM | UNIT | | 0005 ROADWAY 80% NHPP (FED) 20% STATE LAKE COUNTY | 0005 ROADWAY 100% STATE LAKE COUNTY | 0021 SIGNAL 80% NHPP (FED) 20% STATE LAKE COUNTY | | |
| 20200100 | EARTH EXCAVATION | CU YD | 157 | 157 | | | | |
| 21101615 | TOPSOIL FURNISH AND PLACE, 4" | SQ YD | 426 | 426 | | | | |
| 25200110 | SODDING, SALT TOLERANT | SQ YD | 426 | 426 | | | | |
| 25200200 | SUPPLEMENTAL WATERING | UNIT | 19.2 | 19.2 | | | | |
| 35501308 | HOT-MIX ASPHALT BASE COURSE, 6" | SQ YD | 8 | 8 | | | | |
| 35501316 | HOT-MIX ASPHALT BASE COURSE, 8" | SQ YD | 24 | 24 | | | | |
| 40600290 | BITUMINOUS MATERIALS (TACK COAT) | POUND | 90914 | 90914 | | | | |
| 40600370 | LONGITUDINAL JOINT SEALANT | FOOT | 46063 | 46063 | | | | |
| 40600400 | MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS | TON | 180 | 180 | | | | |
| 40600982 | HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT | SQ YD | 804 | 804 | | | | |
| 40601005 | HOT-MIX ASPHALT REPLACEMENT OVER PATCHES | TON | 449 | 449 | | | | |
| 40602985 | HOT-MIX ASPHALT BINDER COURSE, IL-9.5, N70 | TON | 8288 | 8288 | | | | |
| 40603200 | POLYMERIZED HOT-MIX APHALT BINDER COURSE, IL-4.75, N50 | TON | 1885 | 1885 | | | | |
| 40604060 | HOT MIX ASPHALT SURFACE COURSE, MIX "D", IL-9.5, N50 | TON | 4 | 4 | | | | |

| SUMMARY OF QUANTITIES | | | TOTAL QUANTITIES URBAN | CONSTRUCTION TYPE CODE | | | | |
|-----------------------|---|-------|------------------------|---|-------------------------------------|--|--|--|
| CODE NO | ITEM | UNIT | | 0005 ROADWAY 80% NHPP (FED) 20% STATE LAKE COUNTY | 0005 ROADWAY 100% STATE LAKE COUNTY | 0021 SIGNAL 80% NHPP (FED) 20% STATE LAKE COUNTY | | |
| 40604062 | HOT MIX ASPHALT SURFACE COURSE, MIX "D", IL-9.5, N70 | TON | 10095 | 10095 | | | | |
| 40605026 | POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, STONE MATRIX ASPHALT, 9.5, MIX "F", N80 | TON | 1713 | 1713 | | | | |
| 42001300 | PROTECTIVE COAT | SQ YD | 2650 | 2650 | | | | |
| 42300200 | PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH | SQ YD | 24 | 24 | | | | |
| 42300400 | PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH | SQ YD | 71 | 71 | | | | |
| 42400200 | PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH | SQ FT | 13102 | 13102 | | | | |
| 42400800 | DETECTABLE WARNINGS | SQ FT | 556 | 556 | | | | |
| 44000100 | PAVEMENT REMOVAL | SQ YD | 158 | 158 | | | | |
| 44000159 | HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2" | SQ YD | 45626 | 45626 | | | | |
| 44000164 | HOT-MIX ASPHALT SURFACE REMOVAL, 3 3/4" | SQ YD | 73993 | 73993 | | | | |
| 44000200 | DRIVEWAY PAVEMENT REMOVAL | SQ YD | 125 | 125 | | | | |
| 44000600 | SIDEWALK REMOVAL | SQ FT | 12866 | 12866 | | | | |
| 44002210 | HOT-MIX ASPHALT REMOVAL OVER PATCHES, 2 1/2" | SQ YD | 502 | 502 | | | | |

MODEL: Default
 FILE: MainFile: pw\ilgdot-pw\berkeley.com\PW\DOT\Documents\DOT_Offices\District_1\Projects\148520\CADD\Drawings\148520-INT-500.dgn

 REVISED SHEET 4/13/2022
 * SPECIALTY ITEMS

| | | |
|-------------------------------|-------------------|-----------|
| USER NAME = rostkowski | DESIGNED - AR, RR | REVISED - |
| DRAWN - RR | CHECKED - LP | REVISED - |
| PLOT SCALE = 100.0000 ' / in. | DATE - 2/4/2022 | REVISED - |
| PLOT DATE = 2/8/2022 | | |

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

| | | | | | | | |
|----------|--|---------------------|--|--------|--|-----------|--|
| SCALE: - | | SHEET 1 OF 6 SHEETS | | STA. - | | TO STA. - | |
|----------|--|---------------------|--|--------|--|-----------|--|

SUMMARY OF QUANTITIES
IL 137 (BELVIDERE RD TO BUCKLEY RD)

| | | | | |
|--------------------|------------------------|-------------|---------------------------|-------------|
| F.A.P. RTE. 352 | SECTION 2020-090-R5&SW | COUNTY LAKE | TOTAL SHEETS 68 | SHEET NO. 4 |
| CONTRACT NO. 62L68 | | | ILLINOIS FED. AID PROJECT | |

| SUMMARY OF QUANTITIES | | | TOTAL QUANTITIES URBAN | CONSTRUCTION TYPE CODE | | | |
|-----------------------|---|--------|------------------------|---|-------------------------------------|--|--|
| CODE NO | ITEM | UNIT | | 0005 ROADWAY 80% NHPP (FED) 20% STATE LAKE COUNTY | 0005 ROADWAY 100% STATE LAKE COUNTY | 0021 SIGNAL 80% NHPP (FED) 20% STATE LAKE COUNTY | |
| * X1400378 | PEDESTRIAN SIGNAL POST, 5 FT. | EACH | 10 | | | 10 | |
| X4060995 | TEMPORARY RAMP, SPECIAL | SQ YD | 88 | 88 | | | |
| X4400501 | COMBINATION CURB AND GUTTER REMOVAL AND REPLACEMENT LESS THAN OR EQUAL TO 10 FEET | FOOT | 409 | 409 | | | |
| X4401198 | HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH | SQ YD | 1831 | 1831 | | | |
| X5537800 | STORM SEWERS TO BE CLEANED 12" | FOOT | 2000 | | 2000 | | |
| X6026050 | SANITARY MANHOLES TO BE ADJUSTED | EACH | 19 | 19 | | | |
| X6026051 | SANITARY MANHOLES TO BE RECONSTRUCTED | EACH | 16 | 16 | | | |
| X6030310 | FRAMES AND LIDS TO BE ADJUSTED (SPECIAL) | EACH | 168 | 168 | | | |
| X6700407 | ENGINEERS'S FIELD OFFICE, TYPE A (D1) | CAL MO | 12 | 12 | | | |
| * X8760200 | ACCESSIBLE PEDESTRIAN SIGNALS | EACH | 46 | | 46 | | |
| * X8780012 | CONCRETE FOUNDATION, TYPE A 12-INCH DIAMETER | FOOT | 56 | | 56 | | |
| Z0004562 | COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT | FOOT | 3722 | 3722 | | | |
| Z0018400 | DRAINAGE STRUCTURES TO BE ADJUSTED | EACH | 117 | 117 | | | |

| SUMMARY OF QUANTITIES | | | TOTAL QUANTITIES URBAN | CONSTRUCTION TYPE CODE | | | |
|-----------------------|--|-------|------------------------|---|-------------------------------------|--|--|
| CODE NO | ITEM | UNIT | | 0005 ROADWAY 80% NHPP (FED) 20% STATE LAKE COUNTY | 0005 ROADWAY 100% STATE LAKE COUNTY | 0021 SIGNAL 80% NHPP (FED) 20% STATE LAKE COUNTY | |
| Z0018500 | DRAINAGE STRUCTURES TO BE CLEANED | EACH | 285 | 285 | | | |
| Z0018600 | DRAINAGE STRUCTURES TO BE RECONSTRUCTED | EACH | 16 | 16 | | | |
| Z0030850 | TEMPORARY INFORMATION SIGNING | SQ FT | 51.4 | 51.4 | | | |
| * Z0033044 | RE-OPTIMIZE TRAFFIC SIGNAL SYSTEM LEVEL 1 | EACH | 3 | | | 3 | |
| * Z0033046 | RE-OPTIMIZE TRAFFIC SIGNAL SYSTEM LEVEL 2 | EACH | 1 | | | 1 | |
| Z0048665 | RAILROAD PROTECTIVE LIABILITY INSURANCE | L SUM | 1 | 1 | | | |
| Z0076600 | TRAINEES | HOURS | 500 | 500 | | | |
| Z0076604 | TRAINEES - TRAINING PROGRAM GRADUATE | HOURS | 500 | 500 | | | |
| 88200410 | TRAFFIC SIGNAL BACKPLATE, LOUVERED, FORMED PLASTIC | EACH | 1 | 1 | | | |
| 89502380 | REMOVE EXISTING HANDHOLE | EACH | 1 | 1 | | | |
| X1400388 | VIDEO VEHICLE DETECTION SYSTEM, SINGLE APPROACH | EACH | 4 | 4 | | | |
| X4240800 | DETECTABLE WARNINGS (SPECIAL) | SQ FT | 242 | 242 | | | |



REVISD SHEET 4/13/2022

* SPECIALTY ITEMS

0042

MODEL: Default
 FILE: \\miller-pw-bentley.com\PWIDOT\Documents\DOT_Offices\District_1\Projects\148820\CADD\Drawings\148820-ht-500.dgn

| | | |
|------------------------------|-------------------|-----------|
| USER NAME = rostkowski | DESIGNED - AR, RR | REVISED - |
| DRAWN - RR | REVISED - | |
| PLOT SCALE = 100.0000' / in. | CHECKED - LP | REVISED - |
| PLOT DATE = 2/8/2022 | DATE - 2/4/2022 | REVISED - |

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

| | | | | | | |
|-------------------------------------|---------------------|-------------|----------------|--------------------|--------------|-----------|
| SUMMARY OF QUANTITIES | | F.A.P. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
| IL 137 (BELVIDERE RD TO BUCKLEY RD) | | 352 | 2020-090-R5&SW | LAKE | 68 | 9 |
| SCALE: - | SHEET 6 OF 6 SHEETS | STA. - | TO STA. - | CONTRACT NO. 62L68 | | |