

CONSTR. CODE
80% FED 20% ST

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	ROADWAY	
				0005	RURAL
40600901	HOT-MIX ASPHALT BINDER COURSE (HAND METHOD), N70	TON	93	93	
40600990	TEMPORARY RAMP	SQ YD	581	581	
40604052	HOT-MIX ASPHALT SURFACE COURSE, IL-9.5, MIX "C", N70	TON	15698	15698	
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	873	873	
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	186877	186877	
44200956	CLASS B PATCHES, TYPE II, 9 INCH	SQ YD	165	165	
44201298	DOWEL BARS 1 1/4"	EACH	400	400	
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	3528	3528	
44213200	SAW CUTS	FOOT	968	968	
54260315	TRAVERSABLE PIPE GRATE FOR CONCRETE END SECTION	FOOT	44	44	
54261818	STEEL FLARED END SECTIONS, EQUIVALENT ROUND-SIZE 18"	EACH	2	2	
54263336	CONCRETE END SECTION, STANDARD 542011, 36", 1:3	EACH	2	2	
60905305	BOX CULVERTS TO BE CLEANED	FOOT	270	270	
* 66700205	PERMANENT SURVEY MARKERS, TYPE I	EACH	11	11	
* 66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	86	86	
* 66900530	SOIL DISPOSAL ANALYSIS	EACH	4	4	

*= SPECIALTY ITEM

MODEL: Default
FILE: \\nas01\paw.bentley.com\PI\DOT\Documents\DOT_Offices\DH\dtr_3\Project\3D366L03\CADD\366L03-phs-500.dgn

USER NAME = longneckerjh	DESIGNED - EM	REVISED - _____
	DRAWN - EM	REVISED - _____
PLOT SCALE = 100.0000' / in.	CHECKED - JL	REVISED - _____
PLOT DATE = 2/23/2022	DATE - 2/23/2022	REVISED - _____

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: _____ SHEET 2 OF 4 SHEETS STA. _____ TO STA. _____

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
326	(125)RS-6,(126)RS-4&(127X)RS-3	FORD	20	4
CONTRACT NO. 66L03				
ILLINOIS FED. AID PROJECT				

