

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE			
				80%FED/20%STATE STP-R FAP 71	80%FED/20%STATE STP-R FAS 323	80%FED/20%VILLAGE STP-R FAS 323	50%FED/50%VILLAGE STP-R FAS 323
				ROADWAY 0005	ROADWAY 0005	SAFETY 0021	ROADWAY 0005
				RURAL	RURAL	RURAL	RURAL
20200100	EARTH EXCAVATION	CU YD	2		2		
20400800	FURNISHED EXCAVATION	CU YD	4	3	1		
21400100	GRADING AND SHAPING DITCHES	FOOT	555		555		
25000210	SEEDING, CLASS 2A	ACRE	0.21	0.14	0.07		
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	20	17	3		
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	20	17	3		
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	20	17	3		
25100630	EROSION CONTROL BLANKET	SQ YD	1031	887	144		
35101600	AGGREGATE BASE COURSE, TY B 4"	SQ YD	476		476		
35600708	HOT-MIX ASPHALT BASE COURSE WIDENING, 8"	SQ YD	6		6		
40600290	BITUMINOUS MATERIALS (TACK COAT)	POUND	23346	7873	15473		
40600370	LONGITUDINAL JOINT SEALANT	FOOT	10634	624	10010		
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	7	2	5		
40600900	HOT-MIX ASPHALT BINDER COURSE (HAND METHOD), N50	TON	7	3	4		
40600990	TEMPORARY RAMP	SQ YD	891	232	659		



MODEL: Default
 FILE: \\usac-paw.bentley.com\PIV\DOT\Documents\DOT_Offices\DH\dtdt_3\Projects\0366677\CADD\data\CAD\Sheet\0366677-rht-cover.dgn

* FAS 323 / FAP 71
 ** (112&112Z)&(38-5HB-4)RS-3,SW

USER NAME = pletschr PLOT SCALE = 100.0000' / in. PLOT DATE = 1/3/2022	DESIGNED - _____ DRAWN - _____ CHECKED - _____ DATE - _____	REVISED - _____ REVISED - _____ REVISED - _____ REVISED - _____	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.* RTE. SECTION COUNTY TOTAL SHEETS SHEET NO. ** ** IROQUOIS 40 3 CONTRACT NO. 66K77
SCALE: _____ SHEET ____ OF ____ SHEETS STA. _____ TO STA. _____			ILLINOIS FED. AID PROJECT		

SIDEWALK SCHEDULE FOR NEW RAMP INSTALLATION

LOCATION SIDE STREET	QUAD	SIDEWALK REMOVAL	PCC SIDEWALK 4"	AGG BASE, TY B 4"	CCC&G REMOVAL	CC&G B6-24	PAVT REM	HMA WIDENING	EARTH EX *	SODDING *	NITROGEN FERTILIZER NUTRIENT *	PHOSPHORUS FERTILIZER NUTRIENT *	POTASSIUM FERTILIZER NUTRIENT *	DETECTABLE WARNINGS
		SQ FT	SQ FT	SQ YD	FOOT	FOOT	SQ FT	SQ YD	CU YD	SQ YD	POUNDS	POUNDS	POUNDS	SQ FT
STATE HICKORY ST	SW	43.8	71.8	8.0	11	21.5		6	1.9					8
ELM ST	NW		104	11.6	15.5	15.5								8
	SW		113	12.6	18	18								8
	NE		76.1	8.5	15.5	15.5								8
	SE		123.5	13.7	16	16								8
ASH ST	NW	231.3	301.1	33.5	41	42.5	55.6			1.7	0.03	0.03	0.03	16
	SW	187.6	241.7	26.9	29.5	30.5	8.4							16
	NE	96.4	122.7	13.6	19	19								10
	SE	147.9	199.6	22.2	17	17								8
MAPLE ST	NW	114.3	136.1	15.1	13.5	13.5								8
	SW	137.2	156.7	17.4	9.5	9.5								8
	NE	151.2	170.8	19.0	22.5	22.5								16
	SE	191.5	238	26.4	44	48	92.3			6.1	0.11	0.11	0.11	20
EVERGREEN ST	NW	239.6	321.8	35.8	24	24								16
	SW	116.6	116.3	12.9	11	11								16
	NE	230.9	267.5	29.7	9	9								10
	SE	93.7	116.2	12.9	18	18								8
WALNUT ST	NW	225.8	242.8	27.0	8	16				9.8	0.18	0.18	0.18	8
	SW	138.5	155.5	17.3	24	24								8
	NE	225.7	293.5	32.6	18.5	18.5								20
	SE	238.2	238.2	26.5	34	34								16
CHESTNUT ST	NW	220.4	306.8	34.1	39	43.6	133.5							20
	NE	66.4	169.9	18.9		28	150.5							10
SUBTOTAL		3097	4284	476	458	515	440	6	2	18	0.33	0.33	0.33	274
CITY														
ELM ST	NW	68.2												
	SW	78.5												
	NE	53.6												
	SE	85.5												
SUBTOTAL		286	0	0	0	0	0	0	0	0	0.00	0.00	0.00	0
TOTAL		3383	4284	476	458	515	440	6	2	18	0.33	0.33	0.33	274

* THESE ITEMS SHALL BE INCLUDED IN THE COST OF THE SIDEWALK PAY ITEMS, AS OUTLINED IN THE SPECIAL PROVISIONS UNDER "PREPARATION AND RESTORATION OF SIDEWALK WORK AREAS".

MODEL: Default
FILE: \\fs1\caw\benetley.com\PI\DOT\Documents\DOT_Offices\DH\dot_3\Project\3D366677\CADD\data\CAD\Sheet\3D366677-phs-schedule.dgn

* FAS 323 / FAP 71
** (112&112Z)&(38-5HB-4)RS-3,5W

USER NAME = pletschr	DESIGNED - _____	REVISED - _____
	DRAWN - _____	REVISED - _____
PLOT SCALE = 100,0000 ' / in.	CHECKED - _____	REVISED - _____
PLOT DATE = 4/1/2022	DATE - _____	REVISED - _____

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SCHEDULES	
SCALE: _____	SHEET ____ OF ____ SHEETS STA. _____ TO STA. _____

F.A. RTÉ.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	IROQUOIS	40	11
CONTRACT NO. 66K77				
ILLINOIS FED. AID PROJECT				