

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
22	48R5-2	PEORIA KNOX	26	8

RAISED REFLECTIVE PAVEMENT MARKING					
LOCATION			LENGTH	RAISED REF PAVEMENT	RAISED REF PVT MRKRS
			(FT)	(EACH)	(EACH)
PEORIA COUNTY					
1+10	TO	108+45	10,735	135.00	360
BRIDGE OMISSION 108+45 TO 109+71					
109+71	TO	212+25	10,254	129.00	
KNOX COUNTY					
212+25	TO	235+50	2,325	30.00	
BRIDGE OMISSION 235+50 TO 236+76					
236+76	TO	289+00	5,224	66.00	
PEORIA COUNTY			20,989	264.00	
KNOX COUNTY			7,549	96.00	
TOTAL			28,538	360	

CLASS D PATCHING SCHEDULE (13 INCH)					
*PATCHING UNITS	PEORIA COUNTY		KNOX COUNTY		
	TYPE II	TYPE III	TYPE II	TYPE III	TYPE VI
	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD
1	815.99	130.66			
2			401.4	14.44	28.88
3 (WEST LEG)			69.32		
4 (EAST LEG)			103.98		
TOTALS	816	131	575	15	29

* SEE LINE DIAGRAM FOR PATCHING UNITS

LOCATION			LENGTH	SHORT-TERM PAVT MARKINGS 4"	WORK ZONE PAVT MARKING REMOVAL
			(FT)	(FT)	(SQ FT)
PEORIA COUNTY					
1+10	TO	212+25	21,115	10,557.50	703.83
KNOX COUNTY					
212+25	TO	289+00	7,675	3,837.50	255.83
EAST LEG					
289+00	TO	297+50	850	425.00	28.33
WEST LEG					
289+00	TO	297+90	890	445.00	29.67
PEORIA COUNTY			21,115	10,557.50	703.83
KNOX COUNTY			9,415	4,707.50	313.83
TOTAL			30,530	15,265	1,018

MOWING		
LOCATION	LENGTH (FT)	RT/LT (UNIT)
1+10 to 289+00	28,790	288
289+00 TO 297+50 EAST LEG	850	9
289+00 TO 297+90 WEST LEG	890	9
TOTAL	30,530	306

SCHEDULE OF QUANTITIES