

SUMMARY OF QUANTITIES			100% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE					URBAN 1000	SUMMARY OF QUANTITIES			100% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE					URBAN 1000
CODE NO	ITEM	UNIT		CODE NO	ITEM	UNIT	CODE NO	ITEM		UNIT									
20201006	GRADING AND SHAPING SHOULDERS	UNIT	205	205						70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	50148	50148					
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	17	17						70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	1750	1750					
40600300	AGGREGATE (PRIME COAT)	TON	83	83						70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	120	120					
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	12	12						70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	350	350					
40600895	CONSTRUCTING TEST STRIP	EACH	2	2						70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1000	1000					
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	60	60						* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	510	510					
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SQ YD	1133	1133						* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	50148	50148					
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	429	429						* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1750	1750					
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	4240	4240						* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	120	120					
40603395	HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	2642	2642						* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	350	350					
42001300	PROTECTIVE COAT	SQ YD	1502	1502						* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	550	550					
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	375	375						78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	550	550					
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	677	677						* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	632	632					
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	39842	39842						X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	51.4	51.4					
44000600	SIDEWALK REMOVAL	SQ FT	375	375						X0322494	CURB CUT	FOOT	1780	1780					
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	4505	4505						X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	2767	2767					
44201773	CLASS D PATCHES, TYPE I, 11 INCH	SQ YD	43	43						X4400100	PORTLAND CEMENT CONCRETE SURFACE REMOVAL (VARIABLE DEPTH)	SQ YD	6286	6286					
44201777	CLASS D PATCHES, TYPE II, 11 INCH	SQ YD	6430	6430						X4422030	PARTIAL DEPTH REMOVAL 3"	SQ YD	2482	2482					
44201781	CLASS D PATCHES, TYPE III, 11 INCH	SQ YD	1314	1314						XX002258	STRUCTURES TO BE ADJUSTED	EACH	12	12					
44201783	CLASS D PATCHES, TYPE IV, 11 INCH	SQ YD	651	651						Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	54	54					
44201839	CLASS D PATCHES, TYPE II, 16 INCH	SQ YD	3794	3794															
44201843	CLASS D PATCHES, TYPE III, 16 INCH	SQ YD	40	40															
44201845	CLASS D PATCHES, TYPE IV, 16 INCH	SQ YD	174	174															
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	820	820															
60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	12	12															
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6															
67100100	MOBILIZATION	L SUM	1	1															
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1															
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1															
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1															
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	6805	6805															
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	510	510															

* Specialty Items