PORTLAND CEMENT CONCRETE PAVEMENT 10 1/4" (JOINTED)

(552)								
FROM	то	NB/SB/CTR EB/WB	QUANTITY SQ YD					
3982+08	3984+11	NB	268					
3982+08	3966+50	NB	5770					
3982+08	3984+33	SB	225					
3982+08	3996+50	SB	5758					
3984+36	3985+02	CTR	118					
3984+54	3988+83	SB	126					
3985+02	3986+83	SB	241					
3985+21	3990+22	SB	656					
3986+86	3988+83	SB	133					
3990+22	3992+22	SB	133					
3996+50	4010+00	NB	5405					
3996+50	4010+00	SB	5403					
3998+47	4000+47	NB	143					
4000+47	4001+68	NB	154					
4002+01	4002+63	CTR	95					
4002+63	4004+35	SB	229					
4002+66	4004+35	SB	224					
4004+35	4006+35	SB	133					
4004+35	4006+35	SB	133					
4004+66	4006+66	NB	134					
4006+66	4008+18	NB	203					
4007+51	4009+51	NB	133					
4009+51	4013+52	NB	535					
4009+66	4011+66	NB	133					
4010+00	4023+00	NB	5200					
4010+00	4023+00	SB	5200					
4011+66	4013+31	NB	220					
4013+31	4014+79	NB	622					
4013+42	4014+70	CTR	215					
4013+60	4014+63	SB	332					
4014+62	4018+58	SB	528					
4014+63	416+43	SB	241					
4016+43	4018+43	SB	133					
4018+58	4020+58	SB	133					
4023+00	4036+50	NB	5394					
4023+00	4036+50	SB	5432					
4027+06	4029+06	NB	132					
4027+16	4029+06	NB	116					

PORTLAND CEMENT CONCRETE PAVEMENT 10 1/4" (JOINTED) (CONTINUED)

FROM	то	NB/SB/CTR	QUANTITY	
FROW	10	EB/WB	SQ YD	
4029+06	4030+38	NB	174	
4029+06	4030+80	NB	232	
4030+80	4031+44	CTR	97	
4031+61	4039+46	SB	1058	
4032+06	4033+56	NB	106	
4033+56	4035+08	NB	200	
4034+30	4036+30	NB	249	
4036+30	4040+28	NB	1061	
4036+42	4038+44	NB	148	
4036+50	4045+00	NB	3400	
4036+50	4045+00	SB	3397	
4038+44	4039+70	NB	169	
4039+46	597+97	SB	415	
4039+70	602+05	NB	386	
4040+05	4042+41	CTR	635	
597+97	599+49	EB	956	
597+97	599+49	WB	664	
600+51	602+05	EB	673	
600+51	602+05	WB	971	
597+97	4042+77	SB	388	
602+05	4043+65	NB	597	
4042+18	4045+00	SB	751	
4042+77	4045+00	SB	293	
4043+65	4045+00	NB	182	

PROJECT TOTAL

PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT 10"

FROM	то	NB/SB/CTR	QUANTITY	
FROW	10	EB/WB	SQ YD	
3984+11	3985+21	NB	633	
3984+08	3984+52	SB	56	
3984+70	3985+30	SB	94	
4001+57	4002+66	SB	302	
4001+63	4002+80	NB	354	
4008+18	4008+91	NB	131	
4023+19	4024+05	NB	385	
4030+63	4031+01	SB	92	
4030+38	4037+73	NB	589	
4031+17	4031+61	SB	152	
4035+08	4035+82	NB	143	
	ı	PROJECT TOTAL	2930	

	DESIGNED	PJ0	REVISED	-
	ORAWN	KES	REVISED	-
	CHECKED	JCM	REVISED	-
	DATE .	12/14/2012	REVISED	-

SCHEDULE OF QUANTITIES ROADWAY ITEMS					F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
					338	(112 & 113) WRS-6	DUPAGE	734	55	
							CONTRACT	NO. 6	OR31	
SCALE:	SHEET NO.	6 OF 13	SHEETS	STA.	TO STA.		ILLINOIS FED. AID PROJECT			