

TEMPORARY ACCESS (PRIVATE ENTRANCE)			
STAGE	STATION	LT/RT	QUANTITY EACH
IL ROUTE 59			
1	3994+00	LT	1
BRUCE LANE			
3C	498+50	RT	1
DIEHL ROAD			
3B	590+50	RT	1
DEARBORN COURT			
3	-	-	2
PROJECT TOTAL			5

TEMPORARY ACCESS (COMMERCIAL ENTRANCE)			
STAGE	STATION	LT/RT	QUANTITY EACH
IL ROUTE 59			
1,3D	4008+50	RT	1
1	4016+50	RT	1
1	4035+50	RT	1
3	4034+80	LT	1
3	4037+50	LT	1
3	4039+00	LT	1
Diehl Road			
1, 1A	603+65	RT	1
1B	607+10	LT	1
3, 3A	592+00	LT	1
3, 3A	596+00	LT	1
Brookdale Road			
1A	503+50	LT	1
2A	503+50	RT	1
PROJECT TOTAL			12

TEMPORARY ACCESS (ROAD)				
STAGE	STATION	LT/RT	STREET	QUANTITY EACH
IL ROUTE 59				
1	3984+50	LT	Gowdey Drive	1
1	3988+00	LT	Amersale Drive	1
1	4002+00	LT	Paxton Drive	1
1	4023+50	RT	LaSalle Avenue	1
1	4031+00	RT	McDowell Drive	1
2, 2A	3984+50	RT	Gowdey Drive	1
3	4002+00	RT	Platinum Avenue	1
3	4031+00	LT	Pebblewood Lane	1
Diehl Road				
1, 1A	607+15	RT	Bond Street	1
1A	610+75	RT	Wall Street	1
3B	587+00	RT	Country Lakes Drive	1
3B	596+50	RT	Pebblewood Lane	1
PROJECT TOTAL				12

IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 2		
STATION	LT/RT	QUANTITY EACH
PRE STAGE 1A		
3996+38	RT	1
4000+37	LT	1
STAGE 1		
4013+22	LT	1
4022+96	LT	1
STAGE 2		
4022+30	LT	1
PROJECT TOTAL		5

IMPACT ATTENUATORS, RELOCATE (FULLY REDIRECTIVE, NARROW), TEST LEVEL 2		
STATION	LT/RT	QUANTITY EACH
PRE STAGE 1B		
4021+63	LT	1
STAGE 1		
4015+63	RT	1
STAGE 1A		
4024+32	LT	1
STAGE 2		
4020+00	RT	1
4021+98	LT	1
STAGE 3		
4022+00	LT	1
PROJECT TOTAL		6

COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12 (SPECIAL)				
STAGE	FROM	TO	LT/RT	QUANTITY FOOT
IL ROUTE 59				
PS-1A	3984+93	3996+82	RT	1189
PS-1A	3997+56	4001+84	RT	428
PS-1A	4002+59	4006+90	RT	431
PS-1B	4010+30	497+83	LT/RT	492
PS-1B	4016+00	4018+30	LT	230
PS-1B	4020+80	4021+07	LT	27
PS-1B	4024+09	4030+83	LT	674
PS-1B	4031+34	4034+63	LT	329
PS-1B	4034+94	4037+27	LT	233
PS-1B	4037+56	4038+81	LT	125
PS-1B	4039+17	4040+43	LT	126
1	4006+90	4011+66	RT	476
1	4043+65	4045+00	RT	135
DIEHL ROAD				
PS-1	598+76	599+17	LT	139
PS-1	600+95	606+89	LT	594
PS-1	607+36	611+15	LT	379
1A	594+19	596+20	RT	201
1A	596+66	4039+77	RT/LT	298
1A	609+73	610+38	RT	65
1A	611+01	612+45	RT	144
PROJECT TOTAL				6715

BARRIER WALL MARKERS, TYPE C			
FROM	TO	LT/RT	QUANTITY EACH
TEMPORARY CONCRETE BARRIER ON IL ROUTE 59			
PRESTAGE 1A			
3996+38	3998+63	RT	18
3998+00	4000+37	LT	19
PRESTAGE 1B			
4020+00	4021+63	LT	13
STAGE 1			
4010+47	4013+22	LT	22
4018+09	4022+96	LT	39
4015+63	4026+00	LT	83
STAGE 1A			
4024+32	4031+07	LT	54
STAGE 2			
4020+00	4022+98	RT	24
4020+05	4022+30	LT	18
STAGE 3			
4020+00	4022+00	LT	16
PERMANENT CONCRETE BARRIER ON IL ROUTE 59			
4019+00	4023+05	RT	10
4024+43	4030+38	RT	15
4036+42	4039+80	RT	8
PROJECT TOTAL			339

DESIGNED *PJO*
 DRAWN *KES*
 CHECKED *JCM*
 DATE *12/14/2012*

REVISED -
 REVISED -
 REVISED -
 REVISED -

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES
 MAINTENANCE OF TRAFFIC / ROADWAY ITEMS

SCALE: SHEET NO. 10 OF 13 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
338	(112 & 113) WRS-6	DUPAGE	734	59
			CONTRACT NO. 60R31	
ILLINOIS FED. AID PROJECT				