

SUMMARY OF QUANTITIES

ROUTE ROCK FALLS MAINTENANCE YARD
SECTION D2 MAINT. YARD 2021-1
Whiteside County
CONTRACT # 64P86
SHEET 2 OF 28
URBAN
100% State
0005

CODE NO.	ITEM	UNIT	TOTAL QUANTITY
30300001	AGGREGATE SUBGRADE IMPROVEMENT	CU YD	425
40600290	BITUMINOUS MATERIALS (TACK COAT)	LBS	5,219
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	866
44201335	CLASS C PATCHES, TYPE IV, 8 INCH	SQ YD	430
44201721	CLASS D PATCHES, TYPE III, 6 INCH	SQ YD	20
44201723	CLASS D PATCHES, TYPE IV, 6 INCH	SQ YD	2,095
54213675	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 30 "	EACH	1
54244405	FLUSH INLET BOX FOR MEDIAN, STANDARD 542546	EACH	4
550A0070	STORM SEWERS, CLASS A, TYPE 1, 15"	FOOT	90
550A0090	STORM SEWERS, CLASS A, TYPE 1, 18"	FOOT	218
550A0120	STORM SEWERS, CLASS A, TYPE 1, 24"	FOOT	131
550A0410	STORM SEWERS, CLASS A, TYPE 2, 24"	FOOT	47
550A0430	STORM SEWERS, CLASS A, TYPE 2, 30"	FOOT	56
60221100	MANHOLES, TYPE A, 5' DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1
60255500	MANHOLES TO BE ADJUSTED	EACH	2
67100100	MOBILIZATION	L SUM	1
Z0013798	CONSTRUCTION LAYOUT	L SUM	1
Z0028415	GEOTECHNICAL REINFORCEMENT	SQ YD	2,545

*SPECIALTY ITEM