

PIPE UNDERDRAINS

LOCATION STATION TO STATION	SIDE	PIPE UNDERDRAINS, TYPE 2, 6" 60108206 FOOT	OUTLET MARKER X0322279 EACH
MONTGOMERY COUNTY			
STAGE 1			
I-55 NB OUTSIDE LANE			
12+75.00 TO 17+60.00	LT	485	
92+00.00 TO 93+02.01	LT	102	
95+28.84 TO 96+30.00	LT	101	
I-55 NB INSIDE LANE			
12+75.00 TO 17+60.00	LT	485	
92+00.00 TO 93+02.01	LT	102	
95+28.84 TO 96+30.00	LT	101	
I-55 SB INSIDE LANE			
1866+52.00	RT		1
3+98.00	RT		1
104+50.00	RT		1
108+99.00	RT		1
114+78.00	RT		1
STAGE 2			
I-55 NB OUTSIDE LANE			
7+99.00	LT		1
12+52.00	LT		1
I-55 NB INSIDE LANE			
1866+55.00	LT		1
4+00.00	LT		1
7+98.00	LT		1
20+50.00	LT		1
25+49.00	LT		1
30+49.00	LT		1
100+51.00	LT		1
104+50.00	LT		1
108+97.00	LT		1
114+73.00	LT		1
I-55 SB INSIDE LANE			
8+00.00	RT		1
10+80.00 TO 15+75.00	RT	495	
20+54.00	RT		1
25+51.00	RT		1
30+49.00	RT		1
91+05.00 TO 92+04.58	RT	100	
94+31.41 TO 95+30.00	RT	99	
100+50.00	RT		1
I-55 SB OUTSIDE LANE			
1866+49.00	RT		1
3+97.00	RT		1
8+00.00	RT		1
10+80.00 TO 15+75.00	RT	495	
15+98.00	RT		1
25+51.00	RT		1
91+05.00 TO 92+04.58	RT	100	
94+31.41 TO 95+30.00	RT	99	
PROJECT TOTAL		2,763	27

DRAIN

LOCATION STATION TO STATION	SIDE	* STONE RIPRAP, CLASS A3 28100105 SQ YD	* METAL FLARED END SECTIONS 12" 54262712 EACH	PIPE DRAINS 12" 60100945 FOOT	TYPE F INLET BOX, STD 610001 61000225 EACH	TYPE G INLET BOX, STD 610001 61000335 EACH
MONTGOMERY COUNTY						
STAGE 1						
CH 24						
47+48.00	RT	167.6	1	10		1
47+57.00	LT	175.4	1	10		1
50+48.00	RT	125.5	1	10		1
50+59.00	LT	116.1	1	10		1
STAGE 2						
IL 108						
49+00.00	LT		1	10	1	
52+00.00	LT		1	10	1	
STAGE 3						
IL 108						
49+00.00	RT		1	10	1	
52+00.00	RT		1	10	1	
PROJECT TOTAL		585	8	80	4	4

* SEE OTHER SCHEDULES FOR ADDITIONAL QUANTITY.

GUARD POSTS

LOCATION STATION TO STATION	SIDE	GUARD POSTS 63400105 EACH
MONTGOMERY COUNTY		
STAGE 2		
I-55		
1664+76.00	CL	4
1741+00.00	CL	3
33+00.00	CL	4
70+40.00	CL	2
81+00.00	CL	3
109+90.00	CL	3
136+35.00	CL	9
141+80.00	CL	9
PROJECT TOTAL		37

CLEANING UNDERDRAIN OUTLETS

LOCATION STATION TO STATION	CLEANING UNDERDRAIN OUTLETS X0320157 EACH
MONTGOMERY COUNTY	
I-55	
1620+10.00 TO 142+68.00	312
PROJECT TOTAL	312

CHANGEABLE MESSAGE SIGNS

LOCATION STATION TO STATION	COMMENT	# OF CMS BOARDS	DAYS UTILIZED	CHANGEABLE MESSAGE SIGNS 70107025 CAL DAYS
MONTGOMERY COUNTY				
I-55 NB IN ADVANCE OF EXT 44	MT. OLIVE / IL 138 INTERCHANGE	1	175	175
I-55 SB IN ADVANCE OF EXT 72	FARMERSVILLE INTERCHANGE	1	175	175
PROJECT TOTAL				350

REV. 6-4-2020