

F.A.U. ROUTE	SECTION #	CONTRACT #	TOTAL SHEETS	SHEET NO.
6801	17-00501-28-I	89738	110	2

SUMMARY OF QUANTITIES

PAY ITEM	PAY ITEM	UNITS	58% / 42% IDOT/CITY FUNDING QUANTITY	100% CITY FUNDING 100% LOCAL QUANTITY	TOTAL QUANTITY
20200100	EARTH EXCAVATION	CU YD	7925		7925
20800150	TRENCH BACKFILL	CU YD	422	410	832
21001000	GEOTECH FABRIC FOR GROUND STABILIZATION	SQ YD	13610		13610
21101615	TOPSOIL FURNISH & PLACE, 4"	SQ YD	8692		8692
△ 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	162		162
△ 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	162		162
△ 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	162		162
△ 25200110	SODDING, SALT TOLERANT	SQ YD	8692		8692
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	180		180
28000500	INLET & PIPE PROTECTION	EACH	48		48
35101582	AGGREGATE BASE COURSE, TYPE B 2	SQ YD	4755		4755
35101800	AGGREGATE BASE COURSE, TYPE B 6	SQ YD	116		116
35102100	AGGREGATE BASE COURSE, TYPE B 9	SQ YD	13610		13610
40200800	AGGREGATE BASE COURSE, TYPE B	TON	26		26
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	17		17
40600295	POLY BITUMINOUS MATERIALS (TACK COAT)	POUND	175		175
40603205	POLY HMA BINDER COURSE, IL-9.5, N50	TON	31		31
40604160	POLY HMA SURFACE COURSE IL-9.5, 4" D, N50	TON	31		31
42000211	PCC PAVEMENT, 7.5" (JOINTED)	SQ YD	11625		11625
42300200	PCC DRIVEWAY PAVEMENT, 6"	SQ YD	878		878
42300400	PCC DRIVEWAY PAVEMENT, 8"	SQ YD	497		497
42400100	PCC SIDEWALK, 4"	SQ FT	24238		24238
42400300	PCC SIDEWALK, 6"	SQ FT	4632		4632
42400410	PCC SIDEWALK, 8"	SQ FT	1503		1503
42400800	DETECTABLE WARNINGS	SQ FT	492		492
44000100	PAVEMENT REMOVAL	SQ YD	12174		12174
44000200	DRIVEWAY PAVT REMOVAL	SQ YD	889		889
44000500	COMBINATION CURB & GUTTER REMOVAL	FT	6760		6760
44000600	SIDEWALK REMOVAL	SQ FT	9130		9130
50105220	PIPE CULVERT REMOVAL	FT	41		41
542C0215	PIPE CULVERT CLASS C, TYPE 1, 10"	FT	37		37
550A0050	STORM SEWERS, CLASS A, TYPE 1, 12"	FT	232		232
550A0340	STORM SEWERS, CLASS A, TYPE 2, 12"	FT	729		729
550A0380	STORM SEWERS, CLASS A TYPE 2, 18"	FT	682		682
55100300	STORM SEWER REMOVAL, 8"	FT	9		9
55100400	STORM SEWER REMOVAL, 10"	FT	8		8
55100500	STORM SEWER REMOVAL, 12"	FT	129		129
55100700	STORM SEWER REMOVAL, 15"	FT	12		12
55100900	STORM SEWER REMOVAL, 18"	FT	31		31
55101200	STORM SEWER REMOVAL, 24"	FT	15		15
△ 56100015	DUCTILE IRON WATER MAIN TEE, 8" X 6"	EA		8	8
△ 56100020	DUCTILE IRON WATER MAIN TEE, 8" X 8"	EA		3	3
△ 56100050	DUCTILE IRON WATER MAIN TEE, 12" X 6"	EA		9	9
△ 56100065	DUCTILE IRON WATER MAIN TEE, 12" X 12"	EA		5	5
△ 56100600	WATER MAIN, 6"	FOOT		497	497
△ 56100700	WATER MAIN, 8"	FOOT		1829	1829
△ 56100900	WATER MAIN, 12"	FOOT		1921	1921

PAY ITEM	PAY ITEM	UNITS	58% / 42% IDOT/CITY FUNDING QUANTITY	100% CITY FUNDING 100% LOCAL QUANTITY	TOTAL QUANTITY
△ 56101150	DUCTILE IRON WATER MAIN REDUCER, 8 X 6	EA		3	3
△ 56101158	DUCTILE IRON WATER MAIN REDUCER, 12 X 6	EA		1	1
△ 56101160	DUCTILE IRON WATER MAIN REDUCER, 12 X 8	EA		1	1
△ 56101162	DUCTILE IRON WATER MAIN REDUCER, 12 X 10	EA		4	4
△ 56104900	WATER VALVES, 6"	EA		6	6
△ 56105000	WATER VALVES, 8"	EA		11	11
△ 56105200	WATER VALVES, 12"	EA		13	13
△ 56109418	DI WATER MAIN FITTINGS, 6" 45.0 DB	EA		15	15
△ 56109420	DI WATER MAIN FITTINGS, 8" 45.0 DB	EA		13	13
△ 56109424	DI WATER MAIN FITTINGS, 12" 45.0 DB	EA		12	12
△ 56109438	DI WATER MAIN FITTINGS, 12" 90.0 DB	EA		6	6
△ 56400500	FIRE HYDRANTS TO BE REMOVED	EA		10	10
△ 56400600	FIRE HYDRANTS	EA		11	11
60218400	MANHOLES, TYPE A, 4' DIA, TYPE 1 F, CLOSED	EACH	2		2
60218500	MANHOLES, TYPE A, 4' DIA TYPE 3 F&G	EACH	2		2
60235700	INLETS, TYPE A, TYPE 3F&G	EACH	19		19
60236200	INLETS, TYPE A, TYPE 8G	EACH	1		1
60240220	INLETS, TYPE B, TYPE 3F&G	EACH	14		14
60240301	INLETS, TYPE B, TYPE 8G	EACH	2		2
60255500	MANHOLES TO BE ADJUSTED	EACH	20		20
60260500	INLETS TO BE ADJUSTED WITH NEW T3 F&G	EACH	1		1
60500040	REMOVING MANHOLES	EACH	5		5
60500060	REMOVING INLETS	EACH	18		18
60604400	COMB CONCRETE CURB & GUTTER TYPE B6.18	FT	6986		6986
67000400	ENGINEERS FIELD OFFICE, TYPE A	CAL MO	12		12
67100100	MOBILIZATION	L SUM	1		1
△ 78005100	EPOXY PAVEMENT MARKING - LET SYM	SQ FT	517		517
△ 78005110	EPOXY PAVEMENT MARKING - LINE 4	FT	1647		1647
△ 78005130	EPOXY PAVEMENT MARKING - LINE 6	FT	514		514
△ 78005150	EPOXY PAVEMENT MARKING - LINE 12	FT	121		121
△ 78005180	EPOXY PAVEMENT MARKING - LINE 24	FT	168		168
△ 81028370	UNDERGROUND CONDUIT, PVC 3" DIA	FT	3427	2973	3427 2973
△ 81400100	HANDHOLE	EACH	6	7	6 7
X0326864	BRICK SIDEWALK REMOVAL	SQ FT	18447		18447
X0327301	RELOCATE EXISTING MAILBOX	EACH	1		1
△ X2200020	FENCE REMOVAL AND REINSTALLATION	FOOT		30	30
X4060995	TEMPORARY RAMP, SPECIAL	SQ YD	165		165
△ X5610646	PLUG WATER MAIN 6"	EA		7	7
△ X5610647	PLUG WATER MAIN 8"	EA		3	3
△ X5610649	PLUG WATER MAIN 12"	EA		6	6

△ SPECIALTY ITEMS

SUMMARY OF QUANTITIES

SEMINARY STREET RECONSTRUCTION
SECTION # 17-00501-28-RP

△ REVISED 5/19/20