

SUMMARY OF QUANTITIES

| CODE NO. | ITEM | UNIT | QUANTITY | 100% STATE JOOO |
|---------------------|--|------------------|-----------------|-----------------|
| 20200100 | EARTH EXCAVATION | CU YD | 209 | 209 |
| 21101615 | TOPSOIL FURNISH AND PLACE, 4" | SQ YD | 3 | 3 |
| 21101645 | TOPSOIL FURNISH AND PLACE, 12" | SQ YD | 178 | 178 |
| 25000210 | SEEDING, CLASS 2A | ACRE | 0.09 | 0.09 |
| 25000400 | NITROGEN FERTILIZER NUTRIENT | POUND | 8 | 8 |
| 25000500 | PHOSPHORUS FERTILIZER NUTRIENT | POUND | 8 | 8 |
| 25000600 | POTASSIUM FERTILIZER NUTRIENT | POUND | 8 | 8 |
| 25000800 | GROUND PREPARATION FOR SEEDING | ACRE | 0.06 | 0.06 |
| 25100630 | EROSION CONTROL BLANKET | SQ YD | 455 | 455 |
| 42001300 | PROTECTIVE COAT | SQ YD | 120 | 120 |
| 44004250 | PAVED SHOULDER REMOVAL | SQ YD | 166 | 166 |
| 50300225 | CONCRETE STRUCTURES | CU YD | 1.6 | 1.6 |
| 50300255 | CONCRETE SUPERSTRUCTURE | CU YD | 9.2 | 9.2 |
| 50300300 | PROTECTIVE COAT | SQ YD | 21 | 21 |
| 50300510 | RUSTICATION FINISH | SQ FT | 39 | 39 |
| 50800405 | REINFORCEMENT BARS, EPOXY COATED | POUND | 540 | 540 |
| 60618324 | CONCRETE MEDIAN SURFACE, 6" (SPECIAL) | SQ FT | 390 | 390 |
| 63200310 | GUARDRAIL REMOVAL | FOOT | 51 | 51 |
| 66400550 | CHAIN LINK FENCE, 4' (SPECIAL) | FOOT | 794 | 794 |
| 67100100 | MOBILIZATION | L SUM | 1 | 1 |
| 70101800 | TRAFFIC CONTROL AND PROTECTION, (SPECIAL) | L SUM | 1 | 1 |
| X0322256 | TEMPORARY INFORMATION SIGNING | SQ FT | 26 | 26 |
| X0323973 | SEDIMENT CONTROL, SILT FENCE | FOOT | 832 | 832 |
| X0323974 | SEDIMENT CONTROL, SILT FENCE MAINTENANCE | FOOT | 208 | 208 |
| X0324112 | BARRIER BASE | FOOT | 60 | 60 |
| X0324640 | FLUTED KNEE WALL | FOOT | 825 | 825 |
| X0065740 | CONCRETE MEDIAN SURFACE, 5" (MODIFIED) | SQ FT | 682 | 682 |
| 63700155 | CONCRETE BARRIER, SINGLE FACE, 32" HEIGHT | FOOT | 60 | 60 |
| 70106800 | CHANGEABLE MESSAGE SIGN | CAL MO | 6 | 6 |
| Z0013798 | CONSTRUCTION LAYOUT | L SUM | 1 | 1 |
| Z0029999 | IMPACT ATTENUATOR REMOVAL | EACH | 1 | 1 |
| X0325891 | IMPACT ATTENUATORS (FULLY REDIRECTIVE, RESETTABLE, TEST LEVEL 2) | EACH | 1 | 1 |
| Z0076600 | TRAINING | HOUR | | |
| 44002300 | CURB REMOVAL (PARTIAL) | FOOT | 78 | 78 |

INDEX OF SHEETS

| SHEET | DESCRIPTION |
|--------|---|
| 1 | COVER SHEET |
| 2 | GENERAL NOTES AND PROJECT COMMITMENTS |
| 3 | SUMMARY OF QUANTITIES / INDEX / HIGHWAY STANDARDS |
| 4 | EXISTING AND PROPOSED TYPICAL SECTIONS |
| 5-9 | ALIGNMENT PLANS, SURVEY TIES AND CONTROL POINTS |
| 10-12 | EXISTING AND PROPOSED KNEE WALL PLANS |
| 13-15A | STRUCTURAL DETAILS |
| 16 | BD-51 DISTRICT 1, BENCHING DETAIL FOR EMBANKMENT WIDENING |
| 17 | TC-10 DISTRICT 1, TRAFFIC CONTROL AND PROTECTION FOR SIDE ROADS, INTERSECTIONS & DRIVEWAYS |
| 18 | TC-17 DISTRICT 1, TRAFFIC CONTROL DETAILS FOR FREEWAY SHOULDER CLOSURES PARTIAL RAMP CLOSURES |
| 19 | TC-18 DISTRICT 1, SIGNING FOR FLAGGING OPERATIONS AT WORK ZONE OPENINGS |
| 20 | TC-22 DISTRICT 1, ARTERIAL ROAD INFORMATION SIGN |
| 21-25 | CROSS SECTIONS |

IDOT HIGHWAY STANDARDS

| SHEET | DESCRIPTION |
|-----------|---|
| 000001-05 | STANDARD SYMBOLS, ABBREVIATIONS, AND PATTERNS |
| 001001-01 | AREAS OF REINFORCEMENT BARS |
| 001006 | DECIMAL OF AN INCH AND OF A FOOT |
| 664001-01 | CHAIN LINK FENCE |
| 701601-05 | URBAN LANE CLOSURE, MULTILANE, 1W OR 2W WITH NONTRAVERSABLE MEDIAN |
| 701701-05 | URBAN LANE CLOSURE, MULTILANE INTERSECTION |
| 701801-03 | LANE CLOSURE, MULTILANE, 1W OR 2W, CROSSWALK OR SIDEWALK CLOSURE, for speeds < 45 mph |
| 701901 | TRAFFIC CONTROL DEVICES |
| 720001 | SIGN PANEL MOUNTING DETAILS |
| 720006-01 | SIGN PANEL ERECTION DETAILS |
| 728001 | TELESCOPING STEEL SIGN SUPPORT |
| 731001 | BASE FOR TELESCOPING STEEL SIGN SUPPORT |

| | | | | |
|---------------------|----------|------------------|--------------|-----------|
| F.A.I. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
| 94/90 | * | COOK | 25 | 3 |
| STA. | TO STA. | | | |
| FED. ROAD DIST. NO. | ILLINOIS | FED. AID PROJECT | | |

60A00

F:\9400\9400\9400\9400\SUMMARY OF QUANTITIES 60A00.DWG

BOWMAN, BARRETT & ASSOCIATES INC.
CONSULTING ENGINEERS
Chicago, Illinois
312.228.0100
www.bbainc.com



Rev. 6-2-08

Rev.

| REVISIONS | |
|-----------|------|
| NAME | DATE |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |

ILLINOIS DEPARTMENT OF TRANSPORTATION
F.A.I. 94/90 (DAN RYAN EXPRESSWAY)
SOUTHBOUND KNEE WALLS (33RD TO 31ST ST)
SUMMARY OF QUANTITIES
INDEX OF SHEETS
HIGHWAY STANDARDS

SCALE: NONE DRAWN BY: JDC
DATE: 02/08/08 CHECKED BY: DDM

SOQ-1

3:30:43 PM 2/12/2008