

SUMMARY OF QUANTITIES			URBAN 80% FED. 20% STATE TOTAL QUANTITIES	ROADWAY 1000-2A	CONSTRUCTION TYPE CODE			
CODE NO	ITEM	UNIT						
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	20	20				
40600300	AGGREGATE (PRIME COAT)	TON	51	51				
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	15	15				
40600895	CONSTRUCTING TEST STRIP	EACH	2	2				
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	360	360				
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	620	620				
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	4705	4705				
42001300	PROTECTIVE COAT	SO YD	4108	4108				
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SO FT	125	125				
42400800	DETECTABLE WARNINGS	SO FT	24	24				
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SO YD	48000	48000				
44000600	SIDEWALK REMOVAL	SO FT	125	125				
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	2150	2150				
44002224	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 6"	SO YD	1845	1845				
44201753	CLASS D PATCHES, TYPE II, 9 INCH	SO YD	887	887				
44201757	CLASS D PATCHES, TYPE III, 9 INCH	SO YD	548	548				
44201759	CLASS D PATCHES, TYPE IV, 9 INCH	SO YD	410	410				
48101200	AGGREGATE SHOULDERS, TYPE B	TON	100	100				
NP 55039700	STORM SEWERS TO BE CLEANED	FOOT	561	561				
60251740	CATCH BASINS TO BE ADJUSTED WITH NEW TYPE 24 FRAME AND GRATE	EACH	1	1				
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	9	9				
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	17	17				
60406000	FRAMES AND LIDS, TYPE 1, OPEN LID	EACH	4	4				
60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	10	10				
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6				
67100100	MOBILIZATION	L SUM	1	1				
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1				

SUMMARY OF QUANTITIES			URBAN 80% FED. 20% STATE TOTAL QUANTITIES	ROADWAY 1000-2A	CONSTRUCTION TYPE CODE			
CODE NO	ITEM	UNIT						
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1				
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1				
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1				
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	2442	2442				
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	754	754				
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	25485	25485				
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	1940	1940				
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	820	820				
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	507	507				
78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	754	754				
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	25485	25485				
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1940	1940				
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	820	820				
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	507	507				
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	1306	1306				
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	1306	1306				
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	1611	1611				
X0322256	TEMPORARY INFORMATION SIGNING	SO FT	102.8	102.8				
X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	2016	2016				
NP Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	56	56				
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1				
* Z0076600	TRAINERS	HOURL	1500	1500				
* Z0064800	SELECTIVE CLEARING	UNIT	15	15				

Rev. 10-2-05

© 1080
* - Specialty Items
NP = Non-participating

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES

4/16/2008 11:03:13 AM C:\p1\10000001.dwg