

SUMMARY OF QUANTITIES			TOTAL QUANTITY	UABAN CONSTRUCTION TYPE CODE
CODE NO.	DESCRIPTION	UNIT		80% FED. / 20% STATE ROADWAY 1000-2A
20201006	GRADING AND SHAPING SHOULDERS	UNIT	350	350
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	170	170
40600300	AGGREGATE (PRIME COAT)	TON	840	840
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	220	220
40600525	LEVELING BINDER (HAND METHOD), N50	TON	10	10
40600895	CONSTRUCTING TEST STRIP	EACH	2	2
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	500	500
40600990	TEMPORARY RAMP	SQ YD	850	850
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	2,850	2,850
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	18,520	18,520
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	214,000	214,000
44002212	HOT-MIX ASPHALT SURFACE REMOVAL OVER PATCHES, 3"	SQ YD	16,440	16,440
44201753	CLASS D PATCHES, TYPE II, 9 INCH	SQ YD	2,025	2,025
44201757	CLASS D PATCHES, TYPE III, 9 INCH	SQ YD	3,610	3,610
44201759	CLASS D PATCHES, TYPE IV, 9 INCH	SQ YD	8,660	8,660
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	3,000	3,000
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6
67100100	MOBILIZATION	L SUM	1	1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	10,700	10,700
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	450	450
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	446,000	446,000
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	1,650	1,650
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	660	660
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	50,600	50,600
78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	150	150
78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	149,000	149,000
78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	550	550
78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	220	220
78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	1,000	1,000
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	1,000	1,000
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	52	52
X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	8,700	8,700
			4,000	4,000

• 20070600 TRAINERS
• DENOTES SPECIALTY ITEM

FILE NAME = N:\PROJ\3329\3329_35_Design\Proposed\Plan\3329_35-03-Quant.txd



Ciorba Group, Inc.
CONSULTING ENGINEERS
5507 North Cumberland Avenue, Suite 402
Chicago, Illinois 60656
Tel. 773.775.4009 Fax 773.775.4014

USER NAME = mbalog	DESIGNED - NT	REVISED -
	DRAWN - NT	REVISED -
PLOT SCALE = 1/8" = 1' / IN.	CHECKED - WBL	REVISED -
PLOT DATE = 4/8/2008	DATE - 4/7/2008	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**US ROUTE 45 /52
STUENKEL ROAD TO KANKAKEE COUNTY LINE
SUMMARY OF QUANTITIES**

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
330	17 RS-3	WILL	32	3
FED. ROAD DIST. NO. - ILLINOIS FED. AID PROJECT			CONTRACT NO. 62749	