

SUMMARY OF QUANTITIES			80% FED. 20% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE			
CODE NO	ITEM	UNIT		1000 URBAN			
20201006	GRADING AND SHAPING SHOULDERS	UNIT	124	124			
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	20	20			
40600300	AGGREGATE (PRIME COAT)	TON	97	97			
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	5	5			
40600895	CONSTRUCTING TEST STRIP	EACH	1	1			
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	229	229			
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	1960	1960			
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	4248	4248			
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	1939	1939			
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	48636	48636			
44002230	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 7 1/2"	SQ YD	4666	4666			
44201737	CLASS D PATCHES, TYPE I, 8 INCH	SQ YD	825	825			
44201741	CLASS D PATCHES, TYPE II, 8 INCH	SQ YD	1020	1020			
44201745	CLASS D PATCHES, TYPE III, 8 INCH	SQ YD	996	996			
44201747	CLASS D PATCHES, TYPE IV, 8 INCH	SQ YD	1263	1263			
48102100	AGGREGATE WEDGE SHOULDERS, TYPE B	TON	350	350			
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	5	5			
67100100	MOBILIZATION	L SUM	1	1			
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1			
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1			
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1			
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1			
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	9058	9058			
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	35	35			
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	37275	37275			
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	479	479			

SUMMARY OF QUANTITIES			80% FED. 20% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE			
CODE NO	ITEM	UNIT		1000 URBAN			
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	88	88			
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1330	1330			
• 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	35	35			
• 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	37275	37275			
• 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	479	479			
• 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	88	88			
• 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	589	589			
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	350	350			
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	213	213			
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	52	52			
X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	2124	2124			
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1			
• Z0076600	TRAINERS	HOUR	1500	1500			

•SPECIALTY ITEM

© Y080

4/2/2008 c:\projects\dl22404\sh_r\dj.dgn

Rev. 5-28-08

Rev.