

| SUMMARY OF QUANTITIES | | | 80% FED. 20% STATE TOTAL QUANTITIES | CONSTRUCTION TYPE CODE | | | | |
|-----------------------|---|--------|--|------------------------|--|--|--|--|
| CODE NO | ITEM | UNIT | | 1000 URBAN | | | | |
| 20201006 | GRADING AND SHAPING SHOULDERS | UNIT | 124 | 124 | | | | |
| 40600200 | BITUMINOUS MATERIALS (PRIME COAT) | TON | 20 | 20 | | | | |
| 40600300 | AGGREGATE (PRIME COAT) | TON | 97 | 97 | | | | |
| 40600400 | MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS | TON | 5 | 5 | | | | |
| 40600895 | CONSTRUCTING TEST STRIP | EACH | 1 | 1 | | | | |
| 40600982 | HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT | SQ YD | 229 | 229 | | | | |
| 40601005 | HOT-MIX ASPHALT REPLACEMENT OVER PATCHES | TON | 1375 | 1375 | | | | |
| 40603340 | HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70 | TON | 4248 | 4248 | | | | |
| 44000155 | HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2" | SQ YD | 1939 | 1939 | | | | |
| 44000158 | HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4" | SQ YD | 48636 | 48636 | | | | |
| 44002230 | HOT-MIX ASPHALT REMOVAL OVER PATCHES, 7 1/2" | SQ YD | 4666 | 4666 | | | | |
| 44201737 | CLASS D PATCHES, TYPE I, 8 INCH | SQ YD | 825 | 825 | | | | |
| 44201741 | CLASS D PATCHES, TYPE II, 8 INCH | SQ YD | 1020 | 1020 | | | | |
| 44201745 | CLASS D PATCHES, TYPE III, 8 INCH | SQ YD | 996 | 996 | | | | |
| 44201747 | CLASS D PATCHES, TYPE IV, 8 INCH | SQ YD | 1263 | 1263 | | | | |
| 48102100 | AGGREGATE WEDGE SHOULDERS, TYPE B | TON | 350 | 350 | | | | |
| 67000400 | ENGINEER'S FIELD OFFICE, TYPE A | CAL MO | 5 | 5 | | | | |
| 67100100 | MOBILIZATION | L SUM | 1 | 1 | | | | |
| 70100450 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701201 | L SUM | 1 | 1 | | | | |
| 70102625 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701606 | L SUM | 1 | 1 | | | | |
| 70102630 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701601 | L SUM | 1 | 1 | | | | |
| 70102635 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701701 | L SUM | 1 | 1 | | | | |
| 70300100 | SHORT-TERM PAVEMENT MARKING | FOOT | 9058 | 9058 | | | | |
| 70300210 | TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS | SQ FT | 35 | 35 | | | | |
| 70300220 | TEMPORARY PAVEMENT MARKING - LINE 4" | FOOT | 37275 | 37275 | | | | |
| 70300240 | TEMPORARY PAVEMENT MARKING - LINE 6" | FOOT | 479 | 479 | | | | |

| SUMMARY OF QUANTITIES | | | 80% FED. 20% STATE TOTAL QUANTITIES | CONSTRUCTION TYPE CODE | | | | |
|-----------------------|---|-------|--|------------------------|--|--|--|--|
| CODE NO | ITEM | UNIT | | 1000 URBAN | | | | |
| 70300280 | TEMPORARY PAVEMENT MARKING - LINE 24" | FOOT | 88 | 88 | | | | |
| 70301000 | WORK ZONE PAVEMENT MARKING REMOVAL | SQ FT | 1330 | 1330 | | | | |
| • 78000100 | THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS | SQ FT | 35 | 35 | | | | |
| • 78000200 | THERMOPLASTIC PAVEMENT MARKING - LINE 4" | FOOT | 37275 | 37275 | | | | |
| • 78000400 | THERMOPLASTIC PAVEMENT MARKING - LINE 6" | FOOT | 479 | 479 | | | | |
| • 78000650 | THERMOPLASTIC PAVEMENT MARKING - LINE 24" | FOOT | 88 | 88 | | | | |
| • 78100100 | RAISED REFLECTIVE PAVEMENT MARKER | EACH | 589 | 589 | | | | |
| 78300200 | RAISED REFLECTIVE PAVEMENT MARKER REMOVAL | EACH | 350 | 350 | | | | |
| * 88600600 | DETECTOR LOOP REPLACEMENT | FOOT | 213 | 213 | | | | |
| X0322256 | TEMPORARY INFORMATION SIGNING | SQ FT | 52 | 52 | | | | |
| X4067107 | POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50 | TON | 2124 | 2124 | | | | |
| Z0048665 | RAILROAD PROTECTIVE LIABILITY INSURANCE | L SUM | 1 | 1 | | | | |
| • 20076600 | TRAINERS | HOUR | 1500 | 1500 | | | | |

•SPECIALTY ITEM

© Y080

4/2/2008

FILE NAME =
c:\projects\dl22404\sh_rdw.dgn
USER NAME = ouky
PLOT SCALE = 50.0000' / IN.
PLOT DATE = 4/2/2008

DESIGNED -
DRAWN -
CHECKED -
DATE -

REVISED -
REVISED -
REVISED -
REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
IL. RTE. 50 NORTH CITY LIMIT OF MONEE TO I.C. RAILROAD

SCALE: 1" = 50' SHEET NO. OF SHEETS STA. TO STA.

| | | | | |
|---|---------|--------|--------------------|--------------|
| F.A. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
| • 350 & 840 | 143RS-4 | WILL | 16 | 3 |
| FED. ROAD DIST. NO. 1 (ILLINOIS) FED. AID PROJECT | | | CONTRACT NO. 62762 | |

Rev.