

F.A.I.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
94/90	*	COOK	38	3
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

62998

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	URBAN	
			QUANTITY	100% STATE JOOO
20200100	EARTH EXCAVATION	CU YD	471	471
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	10	10
21101645	TOPSOIL FURNISH AND PLACE, 12"	SQ YD	417	417
25000210	SEEDING, CLASS 2A	ACRE	0.15	0.15
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	21	21
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	21	21
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	21	21
25000800	GROUND PREPARATION FOR SEEDING	ACRE	0.14	0.14
25001800	SEEDING, CLASS 4 (MODIFIED)	ACRE	0.08	0.08
25100630	EROSION CONTROL BLANKET	SQ YD	1,086	1,086
42001300	PROTECTIVE COAT	SQ YD	126	126
50300225	CONCRETE STRUCTURES	CU YD	15.2	15.2
50300255	CONCRETE SUPERSTRUCTURE	CU YD	15.5	15.5
50300300	PROTECTIVE COAT	SQ YD	74	74
50300510	RUSTICATION FINISH	SQ FT	203	203
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	2,990	2,990
60618324	CONCRETE MEDIAN SURFACE, 6" (SPECIAL)	SQ FT	847	847
66400550	CHAIN LINK FENCE, 4' (SPECIAL)	FOOT	1,856	1,856
67100100	MOBILIZATION	L SUM	1	1
70101800	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	26	26
X0323973	SEDIMENT CONTROL, SILT FENCE	FOOT	1,996	1,996
X0323974	SEDIMENT CONTROL, SILT FENCE MAINTENANCE	FOOT	499	499
X0324640	FLUTED KNEE WALL	FOOT	1,811	1,811
X2500322	SEEDING, CLASS 5A (MODIFIED)	ACRE	0.08	0.08
X6065740	CONCRETE MEDIAN SURFACE, 5" (MODIFIED)	SQ FT	196	196
70104800	CHANGEABLE MESSAGE SIGN	CAL MO	6	6
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1
X0325891	IMPACT ATTENUATORS (FULLY REDIRECTIVE, RESETTABLE), TEST LEVEL 2	EACH	2	2
Z0076600	TRAINERS	— HOUR		
44002300	CURB REMOVAL (PARTIAL)	FOOT	137	137

INDEX OF SHEETS

SHEET	DESCRIPTION
1	COVER SHEET
2	GENERAL NOTES AND PROJECT COMMITMENTS
3	SUMMARY OF QUANTITIES / INDEX / HIGHWAY STANDARDS
4	EXISTING AND PROPOSED TYPICAL SECTIONS
5-9	ALIGNMENT PLANS, SURVEY TIES AND CONTROL POINTS
10-16	EXISTING AND PROPOSED KNEE WALL PLANS
17-21A	STRUCTURAL DETAILS
22	BD-51 DISTRICT 1, BENCHING DETAIL FOR EMBANKMENT WIDENING
23	TC-10 DISTRICT 1, TRAFFIC CONTROL AND PROTECTION FOR SIDE ROADS, INTERSECTIONS & DRIVEWAYS
24	TC-17 DISTRICT 1, TRAFFIC CONTROL DETAILS FOR FREEWAY SHOULDER CLOSURES PARTIAL RAMP CLOSURES
25	TC-18 DISTRICT 1, SIGNING FOR FLAGGING OPERATIONS AT WORK ZONE OPENINGS
26	TC-22 DISTRICT 1, ARTERIAL ROAD INFORMATION SIGN
27-38	CROSS SECTIONS

IDOT HIGHWAY STANDARDS

SHEET	DESCRIPTION
000001-05	STANDARD SYMBOLS, ABBREVIATIONS, AND PATTERNS
001001-01	AREAS OF REINFORCEMENT BARS
001006	DECIMAL OF AN INCH AND OF A FOOT
664001-01	CHAIN LINK FENCE
701601-05	URBAN LANE CLOSURE, MULTILANE, 1W OR 2W WITH NONTRAVERSABLE MEDIAN
701701-05	URBAN LANE CLOSURE, MULTILANE INTERSECTION
701801-03	LANE CLOSURE, MULTILANE, 1W OR 2W, CROSSWALK OR SIDEWALK CLOSURE, for speeds < 45 mph
701901	TRAFFIC CONTROL DEVICES
720001	SIGN PANEL MOUNTING DETAILS
720006-01	SIGN PANEL ERECTION DETAILS
728001	TELESCOPING STEEL SIGN SUPPORT
731001	BASE FOR TELESCOPING STEEL SIGN SUPPORT

BOWMAN, BARRETT & ASSOCIATES INC
CONSULTING ENGINEERS
Chicago, Illinois
312.228.0100
www.bbainc.com



Rev. 6-2-08

Rev.

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
F.A.I. 94/90 (DAN RYAN EXPRESSWAY)
SOUTHBOUND KNEE WALLS (PERSHING RD TO 35TH ST)

SUMMARY OF QUANTITIES
INDEX OF SHEETS
HIGHWAY STANDARDS

SCALE: NONE
DATE: 02/08/08
DRAWN BY: JDC
CHECKED BY: DDM

S00-1

3:26:30 PM
2/12/2008