

# SCHEDULE OF QUANTITIES

## TREE REMOVAL (6 TO 15 UNITS DIAMETER)

UNIT	LOCATION
7	Rt Sta 1147 + 40
6	Rt Sta 1147 + 61
7	Rt Sta 1147 + 84
6	Rt Sta 1148 + 04
7	Rt Sta 1148 + 55
8	Rt Sta 1148 + 66
7	Rt Sta 1149 + 67
7	Rt Sta 1149 + 74
7	Rt Sta 1149 + 80
6	Rt Sta 1149 + 86
7	Rt Sta 1149 + 92
7	Rt Sta 1150 + 00
7	Rt Sta 1150 + 05
7	Rt Sta 1150 + 12
6	Rt Sta 1150 + 16
6	Rt Sta 1150 + 17
8	Rt Sta 1150 + 20
6	Rt Sta 1150 + 23
8	Rt Sta 1150 + 25
6	Rt Sta 1150 + 27
8	Rt Sta 1150 + 30
6	Rt Sta 1150 + 34
10	Rt Sta 1150 + 38
6	Rt Sta 1150 + 40
6	Rt Sta 1150 + 44
14	Rt Sta 1150 + 49
6	Rt Sta 1150 + 54
10	Rt Sta 1150 + 68
202	TOTAL

## TREE REMOVAL (OVER 15 UNITS DIAMETER)

UNIT	LOCATION
16	Rt Sta 1150+64
16	TOTAL

## TREE TRUNK PROTECTION

EACH	LOCATION
1	Rt Sta 11+40
1	Lt Sta 13+20
2	TOTAL

## SEEDING, CLASS 1

ACRE	LOCATION
0.27	Rt Sta 1139+45 - 1146+29
0.21	Rt Sta 1147+12 - 1151+50
0.48	TOTAL

## SEEDING, CLASS 2A

ACRE	LOCATION
0.53	Lt Sta 1139+45 - 1151+50
0.53	TOTAL

## MOWING

ACRE	LOCATION
1.1	Sta 1139+45 - 1151+50
1.1	TOTAL

## EROSION CONTROL BLANKET

SQ YD	LOCATION
1306.8	Rt Sta 1139+45 - 1146+29
1016.4	Rt Sta 1147+12 - 1151+50
2565.2	Lt Sta 1139+45 - 1151+50
4888.4	TOTAL

## SODDING

SQ YD	LOCATION
2005.3	Sta 10+50 - 14+75
1747.5	Sta 10+50 - 14+79
3752.8	TOTAL

## SUPPLEMENTAL WATERING

UNIT	LOCATION
34	Sta 10+50 - 14+79
34	TOTAL

## TEMPORARY EROSION CONTROL SEEDING

POUND	LOCATION
1010	IL 76 Sta 1139+45 - 1151+80
770	Walnut Grove Dr. Sta 10+50 - 14+75
1780	TOTAL

## PERIMETER EROSION BARRIER

FOOT	LOCATION
495	Sta 1142+00 - 1145+30
315	Sta 1147+28 - 1150+01
810	TOTAL

## SUB-BASE GRANULAR MATERIAL, TYPE A 12"

SQ YD	LOCATION
1170.2	Rt Sta 1139+95 - 1151+30
928	Lt Sta 1139+95 - 1151+30
2098.2	TOTAL

## AGGREGATE BASE COURSE, TYPE A

TON	LOCATION
3177.5	Sta 10+29 - 14+75
3177.5	TOTAL

## HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT

SQ YD	LOCATION
126.7	Sta 1139+45 - 1139+75
183.3	Sta 1151+50 - 1151+80
310	TOTAL

## TEMPORARY RAMP

SQ YD	LOCATION
21.1	Sta 1139+45
30.6	Sta 1151+80
51.7	TOTAL *Includes quantity to place ramp on shoulder that has butt joint

## HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH

SQ YD	LOCATION
2690	Sta 1139+95 - 1151+30
2690	TOTAL

## PAVED SHOULDER REMOVAL

SQ YD	LOCATION
662	Rt. Sta. 1139+45 - 1146+67
76.7	Rt. Sta. 1146+91 - 1151+80
1097.8	Lt. Sta. 1139+45 - 1151+80
1836.5	TOTAL

## STRIP REFLECTIVE CRACK CONTROL TREATMENT

FOOT	LOCATION
1135	Lt. Sta. 1139+95 - 1151+30
1135	Rt. Sta. 1139+95 - 1151+30
1135	CL Sta 1139+95 - 1151+30
3405	TOTAL

## REINFORCEMENT BARS

POUND	LOCATION
42	Rt Sta 1150+88
42	TOTAL

## PIPE CULVERTS, CLASS A, TYPE 1 30"

FOOT	LOCATION
13	Rt Sta 1150+88 *See note on cross section
13	TOTAL

## PIPE CULVERTS, CLASS D, TYPE 1 15"

FOOT	LOCATION
41	IL 76 LT Sta. 1143+50
35	Walnut Grove Drive LT Sta. 11+20
37	RT Sta. 11+70
43	LT Sta. 12+40
34	RT Sta. 12+85
44	LT Sta. 13+34
46	LT Sta. 14+36
280	TOTAL

## END SECTIONS 15"

EACH	LOCATION
2	IL 76 LT Sta. 1143+50
2	Walnut Grove Drive LT Sta. 11+20
2	RT Sta. 11+70
2	LT Sta. 12+40
2	RT Sta. 12+85
2	LT Sta. 13+34
2	LT Sta. 14+36
14	TOTAL

## CONCRETE COLLAR

CU YD	LOCATION
0.89	Rt Sta 1150+88
0.89	TOTAL

## DELINEATORS

EACH	LOCATION
1	LT Sta. 1150+88
1	RT Sta. 1150+88
2	TOTAL