

MEDIAN, CURB, & SIDEWALK SCHEDULE													
STATION	LOCATION LETTER	COMB CURB & GUTTER REM	MEDIAN REM	MEDIAN SURF REM	SIDEWALK REM	CCC&G TYPE B-6.12	CONC MED SURFACE 4"	CORRUGATED MEDIAN	PCC SIDEWALK 4"	PCC SIDEWALK SPECIAL	DETECTABLE WARNING	AGGREGATE BACKFILL	PRISM CURB REFLECT
		FOOT	SQ FT	SQ FT	SQ FT	FOOT	SQ FT	SQ FT	SQ FT	SQ FT	SQ FT	TON	EACH
IL 17 36+78 to 37+78	A		400					400					
37+47 LT	1	10			42	10			42		10		
37+47 RT	2	30			185	30			185		20		
IL 17 37+78 to 39+50	B	359		926		359	746					19	14
WEST MAIN	C	176		689		176	649			95	20	16	8
38+32 RT	3	10			64	10			64		12		
IL 17 & N. FRANKLIN TURN	D	65		131		65	115					3	8
IL 17 & S. FRANKLIN TURN	E	59		143		59	126					3	8
39+29 LT	4	15			65	15			65		20		
N. FRANKLIN	F	143		259		143	183			20	20	5	8
S. FRANKLIN	G	170		1321		170	1236					31	12
40+01 LT	5	10			78	10			78		14		
IL 17 TURN	H	49		105		49	83					2	12
IL 17 40+75 to 41+70	I	207		493		207	392					10	10
IL 17 41+70 to 42+20	J		230					230					
TOTAL		1303	630	4067	434	1303	3530	630	434	115	116	89	80

PAVEMENT MARKING SCHEDULE											
STATION	LOCATION LETTER	LENGTH	POLYUREA PAVEMENT MARKING						LETTERS & SYMBOLS	PAVEMENT MARKING REMOVAL	
			4"		6"	8"	12"	24"			
			WHITE	YELLOW	WHITE	WHITE	WHITE	WHITE			
			FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	SO FT	SO FT
IL 17 35+78 to 36+78		100							44		133
IL 17 36+78 to 37+78	A	100							94		86
37+47 LT	1					120			120		180
37+47 RT	2										
IL 17 37+78 to 39+50	B	172		360					54	61.2	422
WEST MAIN	C		35		110				153	55	333
38+32 RT	3										
IL 17 & N. FRANKLIN TURN	D		32						45		22
IL 17 & S. FRANKLIN TURN	E		70			45			60		20
39+29 LT	4										
N. FRANKLIN	F			145	130				126	72	445
S. FRANKLIN	G		30						45		57
40+01 LT	5										
IL 17 TURN	H			50							17
IL 17 40+75 to 41+70	I	95		210					180	36	336
IL 17 41+70 to 42+20	J	50		100					60		33
IL 17 42+20 to 43+20		100		200					75		67
TOTAL			505	1385	360	45	1002	217	183.6		2151

FILE NAME =
 c:\projects\ed03200\details.dgn

USER NAME = corcoranlm	DESIGNED -	REVISED -
	DRAWN -	REVISED -
PLOT SCALE = 100.0000' / IN.	CHECKED -	REVISED -
PLOT DATE = Mar 19, 2008 10:45:46 AM	DATE -	REVISED -

**STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION**

SCHEDULES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
41	(152)I	LIVINGSTON	10	4
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				
CONTRACT NO. 66764				